



CERTIFIED	APP'D	CHECK'D	DESCRIPTION	BY	DATE	NO.
AYK	OB	SA	FIRST ISSUE	DAR	10/2013	A

RELAY SETTING CALCULATION

REVISIONS	
DESIGNED	BY:- SA
DATE:- 10/2013	
CHECKED	BY:- OB
DATE:- 10/2013	
OPRG. DEPT	BY
DATE:-	
ENG'G. DEPT.	BY:-
DATE:-	
CERTIFIED.	BY:-
DATE:-	

AS BUILT BY		DATE					
THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION OF FOR ORDERING MATERIALS UNTIL CERTIFIED AND DATED	DOCUMENT TITLE		INDEX	PLANT	DOCUMENT NO.	SHEET NO.	REV.
	RELAY SETTING CALCULATION		A	DA441	EE-221424	01 OF 54	A
	QATIF 115/13.8 KV SUBSTATION NO. 2						
QATIF	SAUDI ARABIA	JOB ORDER NO.	1-113045.01	DWG.CON. SHT.	EE-221387		

DOCUMENT:	RELAY SETTING CALCULATION	DOC. NO.	EE-221424
STATION	QATIF 115/13.8KV SUBSTATION NO. 2	Rev.	A

INDEX

SECTION	DESCRIPTION	Page No
1	<u>115KV BB/BF PROTECTION RELAY SETTING</u>	
1.1	115KV BB DIFFERENTIAL PROTECTION (WITH BUILT IN BF) RELAY SETTING REB500 (87BB)	5
2	<u>115/13.8KV POWER TRANSFORMER PROTECTION</u>	
2.1	115/13.8 KV TRANSFORMER DIFFERENTIAL PROTECTION RELAY SETTING RET670 (87T)	6
2.2	115/13.8 KV TRANSFORMER RESTRICTED EARTH FAULT PROTECTION RELAY SETTING MCAG14 (87REF)	8
	PHASE FAULT	
2.3	115/13.8 KV TRANSFORMER HV NON DIRECTIONAL O/C PROTECTION RELAY HV P142 (50/51)	10
2.4	115/13.8 KV TRANSFORMER LV DIRECTIONAL O/C PROTECTION RELAY P142 (67/67N)	11
	EARTH FAULT	
2.5	115/13.8 KV TRANSFORMER HV NON DIRECTIONAL E/F O/C PROTECTION RELAY HV P142 (50N/51N)	12
2.6	380/115 KV TRANSFORMER DIRECTIONAL E/F PROTECTION RELAY LV-N P142 (67LV-N)	3
2.7	115/13.8 KV TRANSFORMER LV NEUTRAL O/C PROTECTION RELAY P142 (51G)	14
3	<u>115KV BUS COUPLER O/C PROTECTION RELAY SETTING</u>	
	PHASE FAULT	
3.1	115KV BUS COUPLER O/C RELAY P142 (51BC)	15
	EARTH FAULT	
3.2	115KV BUS COUPLER E/F O/C RELAY P142 (51BC-N)	16
4	<u>115KV BUS SECTION O/C PROTECTION RELAY SETTING</u>	
	PHASE FAULT	
4.1	115KV BUS SECTION O/C RELAY P142 (51BS)	17
	EARTH FAULT	
4.2	115KV BUS SECTION E/F O/C RELAY P142 (51BS-N)	18
5	<u>115KV LINE PROTECTION RELAY SETTING</u>	
5.1	115KV NEW QATIF U/G CABLE 1,2,3 & 4 PROTECTION SET-1 RELAY SETTING (will be submitted later after receiving measured line parameters) RED670 (21/87/67-1/67N-1)	19
5.2	115KV NEW QATIF U/G CABLE 1,2,3 & 4 PROTECTION SET-2 RELAY SETTING (will be submitted later after receiving measured line parameters) P546 (21/87/67N-1)	29

DOCUMENT:	RELAY SETTING CALCULATION	DOC. NO.	EE-221424
STATION	QATIF 115/13.8KV SUBSTATION NO. 2	Rev.	A

INDEX

SECTION	DESCRIPTION	Page No
6	<u>13.8KV STATION SERVICE TRANSFORMER FEEDER PROTECTION</u>	
	PHASE FAULT	
6.1	13.8KV STATION SERVICE TRANSFORMER FEEDER O/C RELAY REF615 (50/51)	36
	EARTH FAULT	
6.2	13.8KV STATION SERVICE TRANSFORMER FEEDER EARTH FAULT RELAY REF615 (50N/51N)	37
7	<u>13.8KV OUTGOING FEEDER PROTECTION</u>	
	PHASE FAULT	
7.1	13.8KV OUTGOING FEEDER O/C RELAY REF615 (50/51)	38
	EARTH FAULT	
7.2	13.8KV OUTGOING FEEDER E/F O/C RELAY REF615 (50N/51N)	39
8	<u>13.8KV BUS SECTION PROTECTION</u>	
	PHASE FAULT	
8.1	13.8KV BUS SECTION O/C RELAY REF615 (50/51)	40
	EARTH FAULT	
8.2	13.8KV BUS SECTION EARTH FAULT RELAY REF615 (50N/51N)	41
9	<u>13.8KV CAPACITOR BANK RELAY SETTING</u>	
9.1	Capacitor bank neutral un-balance setting MICOM-P142	42
9.2	13.8kV Capacitor bank inst PH O/C protection (50PA, 50PB & 50PC) ABB-RXIG22	43
9.3	13.8kV Capacitor bank INST E/F protection-RXIG22 (50PN) ABB-RXIG22	44
9.4	13.8kV Capacitor bank IDMT PH O/C protection MICOM-P142	45
9.5	13.8kV Capacitor bank IDMT E/F protection MICOM-P142	46
9.6	13.8kV Capacitor bank O/V protection 59-1 MICOM-P922	47
9.7	13.8kV Capacitor bank O/V protection 59-2 MICOM-P922	48
9.8	13.8kV Capacitor bank U/V protection MICOM-P922	49
10	<u>13.8KV BUSBAR PROTECTION RELAY SETTING</u>	
10.1	13.8KV BUSBAR PROTECTION RELAY SETTING MCAG14	50
10.2	13.8KV BUSBAR PROTECTION HIGH IMPEDANCE CT SUPERVISION RELAY MVTP11	52

DOCUMENT:	RELAY SETTING CALCULATION	Doc. No.:	EE-221424
STATION:	QATIF 115/13.8KV SUBSTATION NO.2	Rev. No.:	A

1.1 115KV BUSBAR DIFFERENTIAL PROTECTION (WITH BUILT IN BF) RELAY SETTING (REB 500)

Circuit Ref :	Bus 1A,1B,2A,2B and check zone	Relay Designation	87B+50BF	Relay Type	REB500	Make	ABB	Doc. Ref
Aux. Voltage	125 V DC	CT Ratio	2000/1	PT Ratio	-			
Nominal Current	1A	Rated Voltage		Freq	60HZ			

CT Data

CT Ratio : Primary	3000	A	Adopted tap
: Secondary	1	A	2000 A
Class	TPS		
CT Knee Point Voltage (V_{kp})	1666.6	V	
Magnetising current I_M at V_{kp}	30	mA	
CT Secondary resistance R_{CT}	3.13	Ohms	

Ik min	Op char. L1,L2.L3	1000	A
k	Op char. L1,L2.L3	0.8	
Diff. current Alarm c	Op char. L1,L2.L3	10 %	I kmin
Delay	Op char. L1,L2.L3	5	S
Ik min	Op char. L0	300	A
k	Op char. L0	0.8	
Diff. current Alarm c	Op char. L0	10 %	I kmin
Delay	Op char. L0	10	s

Breaker Failure Protection

BFP Active	Active
Setting (per CT)	1.2 In
Timer 1 Active	Active
Ttimer 2 Active	Active
Timer 1	100 ms
Ttimer 2	150 ms
Inter trip pulse Duration	200 ms
Logic type	1

Document Title:	RELAY SETTING CALCULATION	DOC. NO.	EE-221424
Substation:	QATIF 115/13.8KV SUBSTATION NO.2	Rev. No.	A

2.1 115/13.8KV Power Transformer Differential Protection

Circuit Ref :	T601, T602 & T603	Relay Designation	87T / T601 87T / T602 87T / T603	Relay Type	RET670	Make	ABB	Doc. Ref	
Aux. Voltage	125 V DC	CT Ratio	500/1A	Relay order #	RET670 *1.2-B40X00-D02-D04P01-01-C-B-K-B-B-B3-DAXE				
Nominal Current	1A	Rated Voltage	-	Freq	60HZ				

Calculation for Transformer Differential Protection 87T settings :

	HV		MV		Remarks
Voltage Ratio	115	/	13.8		kV
Connection	D	/	y		
Vector group			Dyn1		
Rating ONAN	50	/	50		MVA
Rating ONAF	67	/	67		MVA
OLTC Type					
OLTC range	115 (+10 to -16) x 1.25%kV				
Highest tap	1		129.38 kV		
Nominal tap	11		115 kV		Nominal tap
Lowest tap	27		92 kV		
Rated Current @ 67 MVA at Highest tap= $MVA * 1000 / \sqrt{3} \times KV$	299 A				
Rated Current @ 67 MVA at Nominal tap= $MVA * 1000 / \sqrt{3} \times KV$	336 A				
Rated Current @ 67 MVA at Lowest tap = $MVA * 1000 / \sqrt{3} \times KV$	420 A				
% Impedance on 50MVA Base	HV-MV		HV-TV		MV-TV
Positive Sequence Impedance, Tap 1	23.60%		-		-
Positive Sequence Impedance, Tap 11	22.00%		-		-
Positive Sequence Impedance, Tap 27	22.30%		-		-
Transformer HV side CT ratio	3000	/	1	A	MRCT
Adopted tap	500	/	1	A	
Rated HV Side. current @67MVA	336 A				

DOCUMENT:	RELAY SETTING CALCULATION	Doc. No.:	EE-221424
STATION:	QATIF 115/13.8KV SUBSTATION NO.2	Rev. No.:	A

2.2 115/13.8KV Transformer LV Restricted Earth Fault Protection Relay Setting

Circuit Ref :	T601 , T602 & T603	Relay Designation	87REF	Relay Type	MCAG 14	Make	Areva
Aux. Voltage	125 V DC	CT Ratio	4000	ORDERING NO	SS DB 0220A		
Nominal Current	1	Freq	60HZ				

CT Data

CT Ratio : Primary	4000	A
: Secondary	1	A
Class	TPS	
CT Knee Point Voltage (V_{kp})	500	V
Magnetising current I_M at V_{kp}	30	mA
CT Secondary resistance R_{CT}	14	Ohms
Max Through fault current		
Max Through fault current	25	k A

Relay setting calculations

As per MCAG relay catalogue,

$$V_s' \geq I_r (R_s + R_p)$$

$$V_{sA} = VA/I_r + I_r R_{sr}$$

$$I_s = I_r + nI_e$$

where,

V_s'	=	Minimum required stability voltage
I_r	=	Maximum sec. through fault current
R_s	=	CT secondary winding resistance
R_p	=	maximum loop lead resistance between CTs and relay
V_{sA}	=	Actual voltage setting
VA	=	relay burden
I_r	=	Relay setting current
R_{sr}	=	Resistance of Stabilising series resistor
I_s	=	Effective fault setting expressed in secondary current

DOCUMENT:	RELAY SETTING CALCULATION	Doc. No.:	EE-221424
STATION:	QATIF 115/13.8KV SUBSTATION NO.2	Rev. No.:	A

I_e = Magnetising current of CT
 n = number of CT groups forming the protected zone.

To determine stability voltage for through fault V_s'

Voltage across the relay at I_{FS} (V_s)

CT Resistance (R_{CT})	=	14	Ohms
Lead Loop Resistance (R_L)	=	0.875	Ohms
Maximum through fault current reflected in CT secondary I_f	=	$25 \times 1000 \times 1 / 4000 =$	6.3
$V_s' = I_{FS} * (R_{CT} + R_L)$	=	$6.25 \times (14 + 0.875)$	
		92.96875	Volts
Setting voltage		93	V
Setting of the Pickup for the relay, I_r		0.1	A
Rated burden of the relay at relay setting		1	VA

To determine series stabilising resistance R_{sr}

Stabilising Resistance $R_{sr} = (V_s' - VA/I_r)/I_r$ (Required)	830.00	ohms
Selected value of stabilising Resistors	1000.00	ohms
Actual Voltage Setting $V_{sA} = VA/I_r + I_r * R_{sr}$	93.00	V
the required resistance to the rated value ratio	83.00%	R_{sr} selection is suitable since its not less than 65%

Minimum Fault sensitivity

The offered CT I_m	30 mA
$I_p = T * (I_r + nI_m + I_M)$	
I_r	0.10 A
I_m at V_{sA}	$I_m \text{ at } U_{al} \times V_{sA}$
	$\frac{U_{al}}{U_{al}}$
	$30 \times 93 / 500$
	0.006 A
Total I_m for 4 CTs	4×0.0056
nI_m	0.023 A
I_M at V_s	$0.52 * (\text{sqrt}(2) * V_i / C)^{1/b}$
C	900
b	0.25
	$0.52 \times (\text{SQRT}(2) \times 93 / 900)^4$
	0.00024 A
I_p	$T * (I_r + nI_m + I_M)$
	$4000 \times (0.1 + 0.023 + 0.00024)$
	493.0 A

The Sensitivity of the bus bar Protection is 12.32% of CT rating

DOCUMENT:	RELAY SETTING CALCULATION	Doc. No.:	EE-221424
STATION:	QATIF 115/13.8KV SUBSTATION NO. 2	Rev. No.:	A

PHASE FAULT

2.3 Applicable for	115KV POWER TRANSFORMER HV Side NON DIRECTIONAL O/C Relay (AREVA-P142)		
Relay ordering number	=	P142316D6M0440J	
System voltage:	HV	= 115.0 KV	
	LV	= 13.8 KV	
CT Ratio	=	500 /1 A	
Load	=	67 MVA	
Load Current	=	$67*1000/(115*\sqrt{3})$	336
Tripping co-ordination	=	13.8kV Bus Tie O/C Protection	
Overload Factor	=	1.20	
Relay Pick up Setting	Pick up	= 1.2*336/500	0.80640 A
	Pick up current Chosen	= 0.81 In	
Fault Current on HV Side	=	$8830*13.8/115$ (ETAP Fault File-Annexure B)	1059.60 A
OPERATING TIME OF 13.8KV BUS TIE O/C RELAY FOR FAULT AT 13.8KV BUS	=	0.73S @ 8830A	
Required operating time for HV side Directional O/C relay	=	0.726 + 0.35	1.08S
Multiple of fault current w.r.t pickup current	=	$1059.6/(0.81*500)$	2.61630
Relay operating time at TMS = 1	=	$0.14 / (2.6162962963^{0.02} - 1)$	7.21 S
Required TMS	=	$1.076 / 7.20854982736079$	0.15
	TMS Chosen	= 0.150	
Operating time @ 1.052kA	=	$0.15*0.14/(2.6162962963^{0.02}-1)$	1.081282474
Highset setting	=	1.25 times of Maximum through fault current	
Maximum through fault current	=	1059.00A	
	=	$1.25*1059.6/500$	2.649
	HS Chosen	= 2.65In	
Settings for 67MVA Powertransformer HV side Non Directional O/C Relay - 50/51 HV (AREVA P142)			
IDMTL Curve	=	Standard Inverse(IEC)	
Relay Pick up Setting	=	0.81 In	- Setting Range = 0.08 to 4xIn in step of 0.01In
TMS	=	0.150	- Setting Range = 0.025 to 1.2 in step of 0.025
HS pick up setting	=	2.65In	- Setting Range = 0.08 to 32In in step of 0.01In
High Set time delay	=	0.050	- Setting Range = 0.00 to 100s in step of 0.01s

DOCUMENT:	RELAY SETTING CALCULATION	Doc. No.:	EE-221424
STATION:	QATIF 115/13.8KV SUBSTATION NO.2	Rev. No.:	A

PHASE FAULT

2.4 Applicable for	380KV AUTOTRANSFORMER MV Side DIRECTIONAL O/C Relay (AREVA-P142)		
Relay ordering number	=	P142316D6M04FOJ	
System voltage:	=	13.8 KV	
CT Ratio	=	4000 /1 A	
Load	=	67 MVA	
Load Current	=	$67*1000/(13.8*\sqrt{3})$	2803.00 A
Grading of Transformer LV Directional relay is such that it should operate before Bus Tie O/C relay for Transformer fault			
Recommended Pick up setting	=	50%	of load current
Relay Pick up Setting	Pick up	=	0.5*2803/4000
	Pick up current Chosen	=	0.36
Maximum 3 phase fault current	=	8830 A	(ETAP Fault File-Annexure B) 8830.00 A
Bus Tie operating time for this fault current	=	0.719S	
Required Transformer LV side directional O/C relay operating time	=	0.35 s	
Multiple of fault current w.r.t pickup current	=	$8830/(0.36*4000)$	
	=	6.130	
Relay operating time at TMS = 1	=	$0.14 / (6.13^{0.02} - 1)$	= 3.79 S
Required TMS	=	$0.35 / 3.79$	= 0.09 S
	TMS Chosen	=	0.100
Operating time @ 8.83 kA	=	$0.1*0.14/(6.13^{0.02}-1)$	= 0.379
Settings for 67MVA Autotransformer MV side Directional O/C Relay - 67 MV (AREVA P142)			
IDMTL Curve	=	Standard Inverse(IEC)	
Relay Pick up Setting	=	0.36 In	- Setting Range = 0.08 to 4xIn in step of 0.01In
TMS	=	0.100	- Setting Range = 0.025 to 1.2 in step of 0.025

DOCUMENT:	RELAY SETTING CALCULATION	Doc. No.:	EE-221424
STATION:	QATIF 115/13.8KV SUBSTATION NO.2	Rev. No.:	A

EARTH FAULT

2.5	Applicable for	115/13.8KV TRANSFORMER HV Side DIRECTIONAL E/F Relay (AREVA-P142)		
	Relay ordering number	= P142316D6M0540J		
	System voltage:	HV	= 115.0 KV	
		LV	= 13.8 KV	
	CT Ratio	= 500 /1 A		
	Load	= 67 MVA		
	Load Current	= $67*1000/(115*\sqrt{3})$	336	
	Tripping co-ordination	= None		
	Required Sensitivity	= 15%	(of CT Rating)	
	Relay Pick up Setting	Pick up	= 0.15 In	0.15 In
		Pick up current Chosen	= 0.15 In	
	Maximum unbalance secondary current	= 5	Times of Setting (assumed)	
	Required operating time	= 0.50S		0.50S
	Relay operating time at TMS = 1	= $0.14 / (5^{*0.02} - 1)$	=	4.28 S
	Required TMS	= $0.5 / 4.27972007094537$	=	0.117
		TMS Chosen	= 0.125	
	Operating time	= $0.125*0.14/(5^{*0.02}-1)$	=	0.534965009
	Highest setting	= 1.25 times of maximum unbalance secondary current		
		= $1.25*5*0.15*500/500$		0.9375
	= 0.94In			
Settings for 67MVA Powertransformer HV side Non Directional E/F Relay - 50N/51N (AREVA P142)				
IDMTL Curve	=	Standard Inverse(IEC)		
Relay Pick up Setting	=	0.15 In	- <i>Setting Range</i> = <i>0.08 to 4xIn in step of 0.01In</i>	
TMS	=	0.125	- <i>Setting Range</i> = <i>0.025 to 1.2 in step of 0.025</i>	
HS pick up setting	=	0.94In	- <i>Setting Range</i> = <i>0.08 to 32In in step of 0.01In</i>	
High Set time delay	=	0.000	- <i>Setting Range</i> = <i>0.00 to 100s in step of 0.01s</i>	

DOCUMENT:	RELAY SETTING CALCULATION	Doc. No.:	EE-221424
STATION:	QATIF 115/13.8KV SUBSTATION NO.2	Rev. No.:	A

EARTH FAULT

2.6	Applicable for	67 MVA POWER TRANSFORMER MV Side DIRECTIONAL E/F Relay (AREVA-P142)		
	Relay ordering number	= P142316D6M0440J		
	System voltage:	HV	= 115.0 KV	
		MV	= 13.8 KV	
	CT Ratio	= 4000 /1 A		
	Load	= 67 MVA		
	Load Current	= $67*1000/(13.8*\sqrt{3})$		2803
	Tripping co-ordination	= Annexure-B		
	Grading of Transformer LV DEF relay is such that it should operate before Bus Tie E/F relay for transformer fault			
	Relay Pick up Setting	Pick up	= 0.15 In	0.15 A
		Pick up current Chosen	= 0.15 In	
	Maximum Through fault current	= 9090 A	(ETAP Fault File-Annexure B)	
	13.8kv Bus Tie O/C Relay operating time for this fault current	= 0.703		0.703S
	Required operating time	= 0.35 s		
	Multiple of fault current w.r.t pickup current	= $9090/(0.15*4000)$		15.15000
		15.150		
	Relay operating time at TMS = 1	= $0.14 / (15.15^{0.02} - 1)$	=	2.51 S
	Required TMS	= $0.35 / 2.50605677006555$	=	0.14
		TMS Chosen	= 0.150	
	Operating time @ 9.09kA	= $0.15*0.14/(19.49^{0.02}-1)$	=	0.375908516
Settings for 67MVA Powertransformer MV side Directional E/F Relay - 67 MVN (AREVA P142)				
IDMTL Curve	=	Standard Inverse(IEC)		
Relay Pick up Setting	=	0.15 In	- <i>Setting Range</i> = 0.08 to 4xIn in step of 0.01In	
TMS	=	0.150	- <i>Setting Range</i> = 0.025 to 1.2 in step of 0.025	

DOCUMENT:	RELAY SETTING CALCULATION	Doc. No.:	EE-221424
STATION:	QATIF 115/13.8KV SUBSTATION NO. 2	Rev. No.:	A

EARTH FAULT

2.7

Substation	- QATIF 115/13.8KV SUBSTATION NO. 2		
Applicable for	- 67MVA TRANSFORMER MV GROUND O/C Relay (AREVA-P142)		
Relay ordering number	=	P142316D6M044OJ	
System voltage:	=	13.8 KV	
CT Ratio	=	4000 /1A	
Load	=	67 MVA	
Load Current	=	$67*1000/(13.8*\sqrt{3})$	= 2803.08 A
Required sensitivity	=	40.00% OF CT RATING	
Relay Pick up Setting	=	0.4*1	= 0.4000 In
Pick up Chosen	=	0.400 In	Pick up Current Chosen = 0.400 A
Required Co-ordination	=	13.8kV Bus Tie E/F Relay	
Fault current for co-ordination	=	9090 A	(ETAP Fault File - Annexure B)
Bus Tie E/F Relay operating time for this fault current	=	$0.14 \times 0.25 / (11.363^{0.02-1})$	0.70799784
Required Operating time	=	0.35+0.707	
	=	1.058S	
Multiple of fault current w.r.t pick-up current	=	$9090 / (0.4 * 4000)$	
	=	5.58	
Operating time at TMS=1	=	$0.14 / (5.581^{0.02-1})$	
	=	4.00S	
Required TMS	=	$1.05799783966979 / 4$	= 0.265
	TMS Chosen	0.275S	
Operating Time @8.93kA	=	$0.275 * 0.14 / (5.581^{0.02-1})$	= 1.100
Settings for 67MVA TRANSFORMER MV GROUND O/C Relay - 51G (AREVA P142)			
IDMTL Curve	=	Standard Inverse(IEC)	
Relay Pick up Setting	=	0.40 A	- Setting Range = 0.08 to 4xIn in step of 0.01In
TMS	=	0.275	- Setting Range = 0.025 to 1.2 in step of 0.025

DOCUMENT:	RELAY SETTING CALCULATION	Doc. No.:	EE-221424
STATION:	QATIF 115/13.8KV SUBSTATION NO.2	Rev. No.:	A

3.1 115KV BUS COUPLER OVERCURRENT RELAY SETTING

PHASE FAULT

Substation	- QATIF 115/13.8KV SUBSTATION NO.2		
Applicable for	- 115KV BUS COUPLER FEEDER OVERCURRENT RELAY		
Relay Type	= P142		
Relay Ordering No.	= P142316D6M044OJ		
System voltage:	= 115.0 KV		
CT Ratio	= 2000 /1 A		
Load Current	= 808.00 A (ASSUMED)		
Over load factor	= 1		
Tripping co-ordination curve	= Annexure-B		
Load Current	= 808 A		
Relay Pick up Setting	= 1 X 808/2000	=	0.40400 A
Pick up current Chosen	= 0.41		
Maximum fault current at 115kV Bus	= 24600 A	(ETAP Fault File - Annexure B)	
Required op. time for this fault current is	= 0.50 Sec		
Multiple of fault current w.r.t pick-up current	= 24600/(0.41x2000)	= 30	Since 30>20
Operating time at TMS =1	= 0.14 / (20 ^{0.02} -1)	=	2.2674 S
Required TMS	= 0.5 / 2.26736	=	0.221
TMS Chosen	= 0.225		
Operating time at selected TMS	= 0.14 * TMS / (multiples of optg. Current ^{0.02} - 1)	=	0.5102 s
Settings for 115kV Bus Coupler O/C Relay - 50/51 (AREVA P142)			
IDMTL Curve	=	Standard Inverse(IEC)	
Plug Setting	= 0.41	-	Setting Range = 0.08 to 4xIn in step of 0.01In
TMS	= 0.225	-	Setting Range = 0.025 to 1.2 in step of 0.025

DOCUMENT:	RELAY SETTING CALCULATION	Doc. No.:	EE-221424
STATION:	QATIF 115/13.8KV SUBSTATION NO.2	Rev. No.:	A

3.2 115KV BUS COUPLER E/F OVERCURRENT RELAY SETTING

EARTH FAULT

Substation	- QATIF 115/13.8KV SUBSTATION NO.2		
Applicable for	- 115KV BUS COUPLER E/F OVERCURRENT RELAY		
Relay Type	= P142		
Relay Ordering No.	= P142316D6M044OJ		
System voltage:	= 115.0 KV		
CT Ratio	= 2000 /1 A		
Tripping co-ordination curve	= Annexure-B		
Relay Pick up Setting	= 20% of CT RATING	=	0.2In
Pick up current Chosen	= 0.2		
Maximum 1 Ph earth fault current att 115kV Bus	= 19500 A	(ETAP Fault File - Annexure B)	
Required operating time at 19500 A	= 0.4000S		
Multiple of fault current w.r.t pick-up current	= 19500/(0.2x2000)		
	= 48.75	Since 48.75 > 20	
Operating time at TMS =1	= 0.14 / (20 ^{0.02} -1)	=	2.2674 S
Required TMS	= 0.4 / 2.26736	=	0.176
TMS Chosen	= 0.175		
Operating time at selected TMS	= 0.14 * TMS / (multiples of optg. Current ^{0.02} -1)		
	= 0.14 * 0.175 / (20 ^{0.02} - 1)	=	0.3968 s
Settings for 115kV Bus Coupler O/C Relay - 50/51 (AREVA P142)			
IDMTL Curve	=	Standard Inverse(IEC)	
Plug Setting	=	0.2	- Setting Range = 0.08 to 4xIn in step of 0.01In
TMS	=	0.175	- Setting Range = 0.025 to 1.2 in step of 0.025

DOCUMENT:	RELAY SETTING CALCULATION	Doc. No.:	EE-221424
STATION:	QATIF 115/13.8KV SUBSTATION NO.2	Rev. No.:	A

4.1 115KV BUS SECTION OVERCURRENT RELAY SETTING

PHASE FAULT

Substation	- QATIF 115/13.8KV SUBSTATION NO.2		
Applicable for	- 115KV BUS SECTION FEEDER OVERCURRENT RELAY		
Relay Type	= P142		
Relay Ordering No.	= P142316D6M044OJ		
System voltage:	= 115.0 KV		
CT Ratio	= 2000 /1 A		
Tripping co-ordination curve	= Annexure-B		
Load Current	= 808 A	(assumed)	
Overload Factor	= 1.0 KV		
Relay Pick up Setting	= 1 X 808/2000	=	0.40400 A
Pick up current Chosen	= 0.41		
Max. 3 ph. fault current	= 24600 A	(ETAP Fault File - Annexure B)	
BUS COUPLER operating time for this fault current	= 0.51 Sec		
Required op. time for B/S relay is	= 0.51+0.35		0.86016
Multiple of fault current w.r.t pick-up current	= 24600/(0.41x2000)		
	= 30	Since 30 > 20	
Operating time at TMS =1	= 0.14 / (20 ^{0.02} -1)	=	2.2674 S
Required TMS	= 0.86016 / 2.26736	=	0.379
TMS Chosen	= 0.400		
Operating time at selected TMS	= 0.14 * TMS / (multiples of optg. Current ^{0.02} -1)		
	= 0.14 * 0.4 / (20 ^{0.02} - 1)	=	0.8593 s
Settings for 115kV Bus Section O/C Relay - 50/51 (AREVA P142)			
IDMTL Curve	=	Standard Inverse(IEC)	
Plug Setting	=	0.41	- <i>Setting Range = 0.08 to 4xIn in step of 0.01In</i>
TMS	=	0.400	- <i>Setting Range = 0.025 to 1.2 in step of 0.025</i>

DOCUMENT:	RELAY SETTING CALCULATION	Doc. No.:	EE-221424
STATION:	QATIF 115/13.8KV SUBSTATION NO.2	Rev. No.:	A

4.2 115KV BUS SECTION E/F OVERCURRENT RELAY SETTING

EARTH FAULT

Substation	- QATIF 115/13.8KV SUBSTATION NO.2		
Applicable for	- 115KV BUS SECTION E/F OVERCURRENT RELAY		
Relay Type	= P142		
Relay Ordering No.	= P142316D6M0440J		
System voltage:	= 115.0 KV		
CT Ratio	= 2000 /1 A		
Tripping co-ordination curve	= Annexure-B		
Relay Pick up Setting	= 25% of CT RATING	=	0.25In
Pick up current Chosen	= 0.25		
Maximum 1 phase earth fault current at 115 kV Bus	= 19500 A	(ETAP Fault File - Annexure B)	
BUS COUPLER operating time for this fault current	= 0.3968S		
Required Operating time	= 0.396+0.35		0.747
Multiple of fault current w.r.t pick-up current	= 19500/(0.25x2000)		
	= 39	Since 39 > 20	
Operating time at TMS =1	= 0.14 / (20 ^{0.02} -1)	=	2.2674 S
Required TMS	= 0.74679 /2.26736	=	0.329
TMS Chosen	= 0.350		
Operating time at selected TMS	= 0.14 * TMS / (multiples of optg. Current ^{0.02} -1)		
	= 0.14 * 0.35/ (20 ^{0.02} - 1)	=	0.7936 s
Settings for 115kV Bus Section O/C Relay - 50/51 (AREVA P142)			
IDMTL Curve	=	Standard Inverse(IEC)	
Plug Setting	=	0.25	- <i>Setting Range = 0.08 to 4xIn in step of 0.01In</i>
TMS	=	0.350	- <i>Setting Range = 0.025 to 1.2 in step of 0.025</i>

DOCUMENT:	RELAY SETTING CALCULATION	Doc. No.:	EE-221424
STATION:	QATIF 115/13.8KV SUBSTATION NO.2	Rev. No.:	A

6.1 13.8KV STATION SERVICE TRANSFORMER FEEDER OVERCURRENT RELAY SETTING

PHASE FAULT

Substation	- QATIF 115/13.8KV SUBSTATION NO.2		
Applicable for	- 13.8KV STATION SERVICE TRANSFORMER T301 & T302 FEEDER OVERCURRENT RELAY		
Relay Type	= REF615		
Relay Ordering No.	=		
System voltage:	HV	=	13.8 KV
	LV	=	0.38 KV
CT Ratio	= 400 /1 A		
Load (Transformer Rating)	= 0.5 MVA		
Load Current	=	21.00 A	$MVA/R3*KV=500/(1.732*13.8-TRFR \text{ primary})$
Over load factor	= 1.2		
Tripping co-ordination curve	= Annexure-B		
Load Current	= 21 A		
Relay Pick up Setting	=	$1.2*21/400$	= 0.06300 A
	Pick up current Chosen = 0.07		
Max. 3 ph. fault current at the transformer LV	=	14860 A	(ETAP Fault File - Annexure B)
Fault current seen by relay transformer HV	=	$(14860*0.38/13.8)$	
	=	409 A	
	=	409 A	
Required O/C relay Operating time for this fault current	= 0.35 Sec		
Multiple of fault current w.r.t pick-up current	=	$409/(0.07*400)$	
	=	14.607	
Operating time at TMS =1	=	$0.14 / (14.607^{0.02-1})$	= 2.5411 S
Required TMS	=	$0.35 / 2.5411$	= 0.138
	TMS Chosen = 0.150		
Operating time at selected TMS	=	$0.14 * TMS / (\text{multiples of optg. Current}^{0.02} - 1)$	
	=	$0.14 * 0.15 / (14.607^{0.02} - 1)$	= 0.3812 s
Highset setting	= 1.25 times of Maximum through fault current		
Maximum through fault current	=	409.000 A	
	=	$1.25 * 409$	= 1.28
	HS Chosen = 1.28 In		
	Time delay = 0.05 s		
Settings for Station Service Transformer HV side O/C Relay - 50/51 (REF615)			
IDMTL Curve	=	Standard Inverse(IEC)	
Plug Setting	=	0.07	- Setting Range = 0.05 to 5*In in step of 0.01
TMS	=	0.150	- Setting Range = 0.05 to 15 in step of 0.05
HS pick-up setting	=	1.280 In	- Setting Range = 0.10 to 40xIn in step of 0.01In
Highset time delay	=	0.05	- Setting Range = 0.04 to 200s in step of 0.01s

DOCUMENT:	RELAY SETTING CALCULATION	Doc. No.:	EE-221424
STATION:	QATIF 115/13.8KV SUBSTATION NO.2	Rev. No.:	A

6.2 13.8KV STATION SERVICE TRANSFORMER FEEDER E/F OVERCURRENT RELAY SETTING

EARTH FAULT

Substation	- QATIF 115/13.8KV SUBSTATION NO.2		
Applicable for	- 13.8KV STATION SERVICE TRANSFORMER T301 & T302 FEEDER E/F OVERCURRENT RELAY		
Relay Type	= REF615		
Relay Ordering No.	=		
System voltage:	HV	=	13.8 KV
CT Ratio	= 400 /1 A		
Load (Transformer Rating)	= 0.5 MVA		
Load Current	= 21.00 A		
Over load factor	= 1.2		
Load Current	= 21 A		
Recommended Pick up Setting	= 2% of CT rating		
Relay Pick up Setting	= 0.02 x 1	=	0.02000 A
Pick up current Chosen	= 0.05		
Max. through fault current	= 5 X HV FULL LOAD CURRENT		
	= 5 X 21		105.00 A
Required Operating time	= 0.35 Sec	Assumed	
Multiple of fault current w.r.t pick-up current	= 105/(0.05x400)		
	= 5.25		
Operating time at TMS =1	= 0.14 / (5.25 ^{0.02} - 1)	=	4.1518 S
Required TMS	= 0.35 / 4.15176	=	0.084
TMS Chosen	= 0.100		
Operating time at selected TMS	= 0.14 * TMS / (multiples of optg. Current ^{0.02} - 1)		
	= 0.14 * 0.1 / (5.25 ^{0.02} - 1)	=	0.4152 s
Settings for Station Service Transformer HV side E/F O/C Relay - 50N/51N (REF615)			
IDMTL Curve	=	Standard Inverse(IEC)	
Plug Setting	=	0.05	- <i>Setting Range = 0.05 to 5*In in step of 0.01</i>
TMS	=	0.100	- <i>Setting Range = 0.05 to 15 in step of 0.05</i>

DOCUMENT:	RELAY SETTING CALCULATION	Doc. No.:	EE-221424
STATION:	QATIF 115/13.8KV SUBSTATION NO.2	Rev. No.:	A

7.1 13.8KV OUTGOING FEEDER OVERCURRENT RELAY SETTING

PHASE FAULT

Substation	- QATIF 115/13.8KV SUBSTATION NO.2		
Applicable for	- 13.8KV OUTGOING FEEDER OVERCURRENT RELAY		
Relay Type	= REF615		
Relay Ordering No.	=		
System voltage:	HV	= 13.8 KV	
CT Ratio	= 600 /1 A		
Load	= 5.0 MVA	ASSUMED	
Load Current	= 209.00 A		
Over load factor	= 1.2		
Tripping co-ordination curve	= Annexure-B		
Load Current	= 209 A		
Relay Pick up Setting	= $1.2 \times 209 / 600$	=	0.41800 A
Pick up current Chosen	= 0.42		
Max. 3 ph. fault current at remote end bus	= 7870 A	(ETAP Fault File - Annexure B)	
Required O/C relay Operating time for this fault current	= 0.35 Sec	Assuming remote end relay operates instantaneously	
Multiple of fault current w.r.t pick-up current	= $7870 / (0.42 \times 600)$		
	= 31.23	Since $31.032 > 20$	
Operating time at TMS =1	= $0.14 / (20^{0.02} - 1)$	=	2.2674 S
Required TMS	= $0.35 / 2.26736$	=	0.154
TMS Chosen	= 0.160		
Operating time at selected TMS	= $0.14 * \text{TMS} / (\text{multiples of optg. Current}^{0.02} - 1)$		
	= $0.14 * 0.16 / (20^{0.02} - 1)$	=	0.3628 s
Highset setting	= 1.25 times of Maximum through fault current		
Maximum through fault current	= 7870.000 A		
	= $1.25 * 7870 / 600$	=	16.4
HS Chosen	= 16.40 In		
Time delay	= 0.05 s		
Settings for OUTGOING FEEDER O/C Relay - 50/51 (REF615)			
IDMTL Curve	=	Standard Inverse(IEC)	
Plug Setting	= 0.42	- Setting Range =	0.05 to 5*In in step of 0.01
TMS	= 0.160	- Setting Range =	0.05 to 15 in step of 0.05
HS pick-up setting	= 16.400 In	- Setting Range =	0.10 to 40xIn in step of 0.01In
Highset time delay	= 0.05	- Setting Range =	0.04 to 200s in step of 0.01s

DOCUMENT:	RELAY SETTING CALCULATION	Doc. No.:	EE-221424
STATION:	QATIF 115/13.8KV SUBSTATION NO.2	Rev. No.:	A

7.2 13.8KV OUTGOING FEEDER E/F OVERCURRENT RELAY SETTING

EARTH FAULT

Substation	-	QATIF 115/13.8KV SUBSTATION NO.2	
Applicable for	-	13.8KV OUTGOING FEEDER E/F OVERCURRENT RELAY	
Relay Type	=	REF615	
Relay Ordering No.	=		
System voltage:	HV	= 13.8 KV	
CT Ratio	=	600 /1 A	
Load	=	5.0 MVA ASSUMED	
Load Current	=	209.00 A	
Over load factor	=	1.2	
Load Current	=	209 A	
Recommended Pick up Setting	=	10% of CT rating	
Relay Pick up Setting	=	0.1 x 1	= 0.10000 A
Pick up current Chosen	=	0.1	
Max. through fault current	=	6290 A	
Required Operating time	=	0.35 Sec	Assumed
Multiple of fault current w.r.t pick-up current	=	6290/(0.1x600)	104.83
	=	20	SINCE 104.83 > 20
Operating time at TMS =1	=	0.14 / (20 ^{0.02} -1)	= 2.2674 S
Required TMS	=	0.35 / 2.26736	= 0.154
TMS Chosen	=	0.150	
Operating time at selected TMS	=	0.14 * TMS / (multiples of optg. Current ^{0.02} -1)	
	=	0.14 * 0.15/ (20 ^{0.02} - 1)	= 0.3401 s
HIGHSET SETTING	=	1.2 TIMES OF MAXIMUM REMOTE END FAULT CURRENT	
MAXIMUM REMOTE END FAULT CURRENT	=	6290.0 A	
	=	1.25*6290/600	13.1042 s
HS CHOSEN	=	13.11In	
Settings for Outgoing Feeder E/F O/C Relay - 50N/51N (REF615)			
IDMTL Curve	=	Standard Inverse(IEC)	
Plug Setting	=	0.1	- Setting Range = 0.05 to 5*In in step of 0.01
TMS	=	0.150	- Setting Range = 0.05 to 15 in step of 0.05
HIGHEST SETTING	=	13.11In	Setting Range = 1 to 40xIn in step of 0.01
HIGHEST TIME DELAY	=	0.02s	Setting Range = 0.02 to 200s in step of 0.01s

DOCUMENT:	RELAY SETTING CALCULATION	Doc. No.:	EE-221424
STATION:	QATIF 115/13.8KV SUBSTATION NO.2	Rev. No.:	A

8.1 13.8KV BUS SECTION OVERCURRENT RELAY SETTING

PHASE FAULT

Substation	- QATIF 115/13.8KV SUBSTATION NO.2		
Applicable for	- 13.8KV BUS SECTION FEEDER OVERCURRENT RELAY		
Relay Type	= REF615		
Relay Ordering No.	=		
System voltage:	= 13.8 KV		
CT Ratio	= 4000 /1 A		
Load Current	= 2803.00 A	trfr FLC	MVA/R3*KV=67000/(1.732*13.8)
Over load factor	= 1.1		
Tripping co-ordination curve	= Annexure-B		
Load Current	= 2803 A		
Relay Pick up Setting	= 1.2 X 2803/4000	=	0.84090 A
Pick up current Chosen	= 0.85		
Max. 3 ph. fault current	= 8830 A	(ETAP Fault File - Annexure B)	
fault current for coordination	= 13.8KV OUTGOING FEEDER O/C FAULT CURRENT		
	=		
IDMT optg time of 13.8kV OUTGOING Feeder O/C relay for this fault current	= 0.36 Sec		
Required op. time for B/S relay is	= 0.36+0.35		0.72
Multiple of fault current w.r.t pick-up current	= 8830/(0.85x4000)		
	= 2.597		
Operating time at TMS =1	= 0.14 / (2.597 ^{0.02} -1)	=	7.2650 S
Required TMS	= 0.7228 /7.265	=	0.099
TMS Chosen	= 0.100		
Operating time at selected TMS	= 0.14 * TMS / (multiples of optg. Current ^{0.02} -1)		
	= 0.14 * 0.1 / (2.597 ^{0.02} - 1)	=	0.7192 s
Settings for 13.8kV Bus Section O/C Relay - 50/51 (REF615)			
IDMTL Curve	=	Standard Inverse(IEC)	
Plug Setting	=	0.85	Setting Range = 0.05 to 5*In in step of 0.01
TMS	=	0.100	Setting Range = 0.05 to 15 in step of 0.05

DOCUMENT:	RELAY SETTING CALCULATION	Doc. No.:	EE-221424
STATION:	QATIF 115/13.8KV SUBSTATION NO.2	Rev. No.:	A

8.2 13.8KV BUS SECTION E/F OVERCURRENT RELAY SETTING

EARTH FAULT

Substation	- QATIF 115/13.8KV SUBSTATION NO.2		
Applicable for	- 13.8KV BUS SECTION A304 E/F OVERCURRENT RELAY		
Relay Type	= REF615		
Relay Ordering No.	=		
System voltage:	= 13.8 KV		
CT Ratio	= 4000 /1 A		
Load Current	= 2803.00 A		
Over load factor	= 1.1		
Tripping Coordination	= 13.8kV OUTGOING Feeder O/C E/F Protection.		
Tripping co-ordination curve	= Annexure-B		
Load Current	= 2803 A		
Relay Pick up Setting	= 20 % of CT Sec. rating	=	0.20000 A
Pick up current Chosen		=	0.2
Max. through fault current	= 9090 A	(ETAP Fault File - Annexure B)	
IDMT optg time of OUTGOING Feeder E/F O/C relay for this fault current	= 0.3400S		
Required Operating time	= 0.34+0.35		0.69
Multiple of fault current w.r.t pick-up current	= 9090/(0.2x4000)		
	= 11.363		
Operating time at TMS =1	= 0.14 / (11.363 ^{0.02} -1)	=	2.8108 S
Required TMS	= 0.69 /2.8108	=	0.245
TMS Chosen		=	0.250
Operating time at selected TMS	= 0.14 * TMS / (multiples of optg. Current ^{0.02} -1)		
	= 0.14 *0.25/ (11.363 ^{0.02} - 1)	=	0.7027 s
Settings for Bus Section E/F O/C Relay - 50N/51N (REF615)			
IDMTL Curve	=	Standard Inverse(IEC)	
Plug Setting	=	0.2	Setting Range = 0.05 to 5*In in step of 0.01
TMS	=	0.250	Setting Range = 0.05 to 15 in step of 0.05

DOCUMENT:	RELAY SETTING CALCULATION	Doc. No.:	EE-221424
STATION:	QATIF 115/13.8KV SUBSTATION NO.2	Rev. No.:	A

9 13.8KV CAPACITOR BANK RELAY SETTING

9.2 13.8kV Capacitor bank inst PH O/C protection (50PA, 50PB & 50PC)

Substation	- QATIF 115/13.8KV SUBSTATION NO.2	
Applicable for	- 13.8kV CAPACITOR BANK	
Relay Type	= ABB - RXIG22	
Relay Ordering Data	RK 411 008 DG	
System voltage:	= 13.8 KV	
CT Ratio	= 1200-600-400/1A	
Adopted Tap	600 /1 A	
Maximum peak inrush current	= 2.03kA	
Maximum peak outrush current	= 2.55kA	
Relay setting	= $1.2 \times \text{outrush Current} / (\text{SQRT}(2) \times \text{CTR})$	
	= $1.2 \times 2.55 \times 1000 / (\text{sqrt}(2) \times 600)$	
	= 3.61 A	
Relay setting	= 4.50 A	
Note : Since the relay operating current increases to +600% for 360HZ this setting will not operate the relay during Inrush condition.		
Back-Back switching is not consider since this detail is not available		
Settings range for 13.8kV capacitor bank instantaneous PH O/C - ABB - RXIG22 (50PA,50PB&50PC)		
RELAY SETTING	= 4.50 A	

DOCUMENT:	RELAY SETTING CALCULATION	Doc. No.:	EE-221424
STATION:	QATIF 115/13.8KV SUBSTATION NO.2	Rev. No.:	A

9 13.8KV CAPACITOR BANK RELAY SETTING

9.4 13.8kV Capacitor bank IDMT PH O/C protection

Substation	=	QATIF 115/13.8KV SUBSTATION NO.2	
Applicable for	=	13.8KV CAPACITOR BANK	
Relay Type	=	AREVA - P142	
Relay Ordering Data	=	P142316D6M0440J	
System voltage:	=	13.8 KV	
CT Ratio	=	1200-600-400/1A	
Adopted Tap	=	600 /1 A	
Capacitor rating	=	7.0 MVar	
Capacitor current	=	$= 7 \times 10^3 / (\sqrt{3} \times 13.8)$	293.00 A
Relay setting	=	$(1.35 \times \text{capacitor current} / \text{CT ratio})$	
	=	$(1.35 \times 293 / 600)$	0.66 In
Relay IDMTL curve	=	VERY INVERSE	
Fault current considered	=	5000A	Assumed
Operating time required	=	0.5 s	Assumed
Fault current in multiples of relay setting	=	$(5000 / (0.66 \times 600))$	12.63 times
Relay operating time at TMS 1 for 13.66 times the fault current	=	$(13.5 / 12.63 - 1)$	1.16 S
Required relay operating time	=	0.50 s	Assumed
Required TMS setting	=	$(0.5 / 1.16)$	0.44
TMS SETTING	=	0.45	
Settings range for 13.8kV capacitor bank IDMT PH O/C Protection(51P) - AREVA - P142			
IDMTL Curve	=	Very Inverse(IEC)	
Plug Setting	=	0.66 In	Setting Range = 0.08 to 4A in step 0.01A
TMS	=	0.45	Setting Range = 0.025 to 1.2 in step 0.005

DOCUMENT:	RELAY SETTING CALCULATION	Doc. No.:	EE-221424
STATION:	QATIF 115/13.8KV SUBSTATION NO.2	Rev. No.:	A

9 13.8KV CAPACITOR BANK RELAY SETTING

9.5 13.8kV Capacitor bank IDMT E/F protection

Substation	- QATIF 115/13.8KV SUBSTATION NO.2	
Applicable for	- 13.8KV CAPACITOR BANK	
Relay Type	= AREVA - P142	
Relay Ordering Data	P142316D6M0440J	
System voltage:	= 13.8 KV	
CT Ratio	= 1200-600-400/1A	
Adopted Tap	600 /1 A	
Capacitor rating	= 7000.0 KVar	
Capacitor current	= $7000/(\sqrt{3} \times 13.8)$	293.00 A
Relay setting	= 50% of CT current	
	= 0.5	
Relay IDMTL curve	= Normal Inverse	
Fault current considered	= 5000 A	Assumed
Operating time required	= 0.25 s	Assumed
Fault current in multiples of relay setting	= $(5000/(0.5 \times 600))$	16.67 times
	=	
Relay operating time at TMS 1 for 15.63 times the	= $(0.14/16.67^{0.02-1})$	2.42 S
Required relay operating time	= 0.25 s	
Required TMS setting	= $(0.25/2.42)$	0.10
TMS SETTING	= 0.10	

Settings range for 13.8kV capacitor bank IDMT E/F Protection(51N) -AREVA - P142

IDMTL Curve	=	Normal Inverse(IEC)	
Plug Setting	=	0.50In	Setting Range = 0.08 to 4A in step 0.01A
TMS	=	0.10	Setting Range = 0.025 to 1.2 in step 0.005

DOCUMENT:	RELAY SETTING CALCULATION	Doc. No.:	EE-221424
STATION:	QATIF 115/13.8KV SUBSTATION NO.2	Rev. No.:	A

9 13.8KV CAPACITOR BANK RELAY SETTING

9.7 13.8kV Capacitor bank O/V protection 59-2

Substation	- QATIF 115/13.8KV SUBSTATION NO.2	
Applicable for	- 13.8KV CAPACITOR BANK	
Relay Type	= AREVA P142	
Relay Ordering Data	P14231AD6M0**0BJ	
PT Ratio	= 13.8KV/SQRT(3)/115V/SQRT(3))	
Overvoltage setting- Alarm	= 105% of nominal voltage	
	= (1.05*66.39)	70.0 V
Time settings	= 5.00S	
Overvoltage setting- Trip	= 110% of nominal voltage	
	= (1.1x66.39)	73.0 V
Time settings	= 3.00 S	
Settings range for 13.8kV capacitor bank O/V Protection(59-2) -AREVA P142		
starting voltage U>	= 70 V	
Time setting tU>	= 5.00 S	
starting voltage U>>	= 73 V	
Time setting tU>>	= 3.00 S	

DOCUMENT:	RELAY SETTING CALCULATION	Doc. No.:	EE-221424
STATION:	QATIF 115/13.8KV SUBSTATION NO.2	Rev. No.:	A

10.1 13.8 KV BB Differential Protection (High Impedence) Relay Setting

Circuit Ref :	13.8KV BUS B1, B2 & B3	Relay Designation	87B1-A, 87B1-B, 87B1-C, 87B2-A, 87B2-B, 87B2-C, 87B3-A, 87B3-B, 87B3-C	Relay Type	MCAG 14	Make	Areva
Aux. Voltage	125 V DC	CT Ratio	4000/1A	ORDERING NO			
Nominal Current	1	Freq	60HZ				

CT Data

CT Ratio : Primary	4000	A
: Secondary	1	A
Class	TPS	
CT Knee Point Voltage (V_{kp})	500	V
Magnetising current I_M at V_{kp}	30	mA
CT Secondary resistance R_{CT}	14	Ohms
Max Through fault current		
Max Through fault current	25	k A

Relay setting calculations

As per MCAG relay catalogue,

$$V_s' \geq I_f (R_s + R_p)$$

$$V_{sA} = VA/I_f + I_f R_{sr}$$

$$I_s = I_f + nI_e$$

where,

- V_s' = Minimum required stability voltage
- I_f = Maximum sec. through fault current
- R_s = CT secondary winding resistance
- R_p = maximum loop lead resistance between CTs and relay
- V_{sA} = Actual voltage setting
- VA = relay burden
- I_f = Relay setting current
- R_{sr} = Resistance of Stabilising series resistor
- I_s = Effective fault setting expressed in secondary current

DOCUMENT:	RELAY SETTING CALCULATION	Doc. No.:	EE-221424
STATION:	QATIF 115/13.8KV SUBSTATION NO.2	Rev. No.:	A

I_e = Magnetising current of CT
 n = number of CT groups forming the protected zone.

To determine stability voltage for through fault V_s'

Voltage across the relay at I_{FS} (V_s)

CT Resistance (R_{CT})	=	14	Ohms
Lead Loop Resistance (R_L)	=	1.05	Ohms
Maximum through fault current reflected in CT secondary I_f	=	$25 \times 1000 \times 1 / 4000 =$	6.25
$V_s' = I_{FS} * (R_{CT} + R_L)$	=	$6.25 \times (14 + 1.05)$	
		94.0625	Volts
Setting voltage		95	V
Setting of the Pickup for the relay, I_r		0.2	A
Rated burden of the realy at relay setting		1	VA

To determine series stabilising resistance R_{sr}

Stabilising Resistance $R_{sr} = (V_s' - VA/I_r)/I_r$ (Required)	450.00	ohms
Selected value of stabilising Resistors	450.00	ohms
Actual Voltage Setting $V_{sA} = VA/I_r + I_r * R_{sr}$	95.00	V
the required resistance to the rated value ratio	100.00%	Rsr selection is suitable since its not less than 65%

Minimum Fault sensitivity

The offered CT I_m	30 mA
$I_p = T * (I_r + nI_m + I_M)$	
I_r	0.20 A
I_m at V_s'	$I_m \text{ at } U_{al} \times V_{sA}$
	$\frac{U_{al}}{U_{al}}$
	$30 \times 95 / 500$
	0.00570 A
Total I_m for 17 CTs	17×0.0057
nI_m	0.097 A
I_M at V_s	$0.52 * (\text{sqrt}(2) * V_i / C)^{1/b}$
C	540
b	0.25
	$0.52 \times (\text{SQRT}(2) \times 95 / 540)^{1/0.25}$
	0.00199 A
I_p	$T * (I_r + nI_m + I_M)$
	$4000 \times (0.2 + 0.0969 + 0.00199)$
	1195.6 A

The Sensitivity of the bus bar Protection is 29.89% of CT rating

DOCUMENT:	RELAY SETTING CALCULATION	Doc. No.:	EE-221424
STATION:	QATIF 115/13.8KV SUBSTATION NO.2	Rev. No.:	A

10.2 13.8 KV BB Differential Protection (High Impedence) CT Supervision Relay

Circuit Ref :	BUS 1B, 2B & 3B	Relay Designation	95B1-A, 95B1-B, 95B1-C, 95B2-A, 95B2-B, 95B2-C, 95B3-A, 95B3-B, 95B3-C	Relay Type	MVTP11	Make	Areva
-------------------------	-----------------	--------------------------	--	-------------------	--------	-------------	-------

Source fault level	=	25000 A
Type of protection	=	CT Secondary Supervision
Type of relay	=	MVTP
Tr. T601 Ful load current	=	2803 A
Sensitivity required	=	10% of load current
Sensitivity required	=	280.3 A
CT Ratio	=	4000/1A
CT secondary resistance R_s	=	14 Ohms
Lead resistance (6 sq mm cable) R_p	=	1.05 Ohms
	=	
<u>Voltage developed across the relay</u>		
Current reflected in CT secondary	=	280.3/(4000/1) A
	=	0.0701 A
V	=	Current x ($R_s + R_p + R_{sr}$)
V	=	0.07(14+1.05 + 450) V
	=	32.588 V
	=	33 V
	=	
Selected voltage tap in the relay	=	2 V
Time setting	=	3 s

DOCUMENT:	RELAY SETTING CALCULATION	Doc. No.:	EE-221424
STATION:	QATIF 115/13.8KV SUBSTATION NO.2	Rev. No.:	A

11.1 115KV BCU SYNCHROCHECK FUNCTION SETTING

Circuit Ref :	A601, A602, A603, A604, A605, A606, A607, A608, A609, A611, A614, A617	Relay Designation	BCU	Relay Type	REC 670	Make	ABB	Doc. Ref	
Aux. Voltage	125V	CT Ratio	-	PT Ratio	115kV/sqrt3 : 115/sqrt3 -115x 115/sqrt3 - 115V				
Nominal Current	-	Rated Voltage	Ur=110V AC	Freq	60HZ				

Synchro Check Relay - REC670 for 115 KV

Substation	QATIF 115/13.8KV SUBSTATION NO.2
System voltage:	115 KV
PT sec. Voltage: U1 L-N (line)	115/R3 = 66.4 V
PT sec. Voltage: U2 L-N (Bus)	115/R3 = 66.4 V
System Frequency	60 Hz
Relay Details	REC670
SETTINGS	
Base Voltage in kV (UBase)	115.0 kV
Voltage Difference limit	15 % UBase
Phase shift for Auto & Manual	20.00 deg
Frequency diff for Auto & Manual	0.200 HZ
Breaker closing Time	0.080 s
Bus voltage high limit	80 % UBase
Line voltage high limit	80 % UBase
Time delay output for Synch Auto	0.100 s
Time delay output for Synch Auto	0.100 s

DOCUMENT:	RELAY SETTING CALCULATION	Doc. No	EE-221424
STATION:	QATIF 115/13.8KV SUBSTATION NO.2	Rev. No.	A

12.1 115/13.8KV POWER TRANSFORMER AVR SETTING

Input data

Rating of Power transformer	=	67 MVA ONAF
Voltage ratio of Power transformer	=	115/13.8 KV
Vector group	=	Dyn1
% Impedance (HV-LV)	=	22.0% @50MVA
Tap range	=	+12.5% to -20%
Type of relay	=	MR - TAPCON260

Relay settings

Mode of operation		
Local / Remote		REMOTE
Auto / Manual		Auto
Desired voltage level		115
Bandwidth		0.750%
Delay timer 1		30s
Delay timer 2		5s
Under voltage blocking U<		90%
Over voltage detection U>		110%
Over current blocking I>		77%

Measuring transformer

Voltage transformer		13.8 KV
Current transformer		4000/1A
Phase angle between current path and voltage path		90 Deg

LDC

Ur		0
Ux		0

Z compensation

Voltage raise		0
Limitation		0

Parallel control

Master / follower		Master / follower
-------------------	--	-------------------

CT Parameter

Ratio:	4000-3000-2500-2000-1500-1000/1A
Adopted tap:	4000/1A
Class:	CL 0.5
Burden:	30VA

TR. parameter


Tr Rating:	67 MVA ONAF
Tr % impedance:	22% @ 50MVA
Voltage rating	115/13.8KV
Vector Group	Dyn1
Tap range	+12.5% to -20%

VT parameter

Ratio:	13800/115V
--------	------------

ANNEXURE-A

(Relay and metering one line diagram)



NOTES

1. DRAWING NOTE

LEGEND

FUNCTION	DESCRIPTION	EOP	TYPE	MAKE
87L-1 21-1 67-1 67N-1	LINE DIFFERENTIAL PROT. LINE DISTANCE PROT. DIRECTIONAL O/C PROT. DIRECTIONAL E/F PROT.	87L-1A 21-1/1 67N-1/1	RED 6T0	ABB
87L-2 21-2 67-2 67N-2	LINE DIFFERENTIAL PROT. LINE DISTANCE PROT. DIRECTIONAL O/C PROT. DIRECTIONAL E/F PROT.	87L-2A 21-2/1 67N-2/1	P546	ALSTOM
50BF 62-BF1 62-BF2	BREAKER FAILURE PROT. BF STAGE-1 TIMER BF STAGE-2 TIMER	87B+ 50BF/ BU-09	REB500	ABB
74	SUPERVISION RELAY FOR TRIP RELAY	74-1 74-2 74/94BF 74/86BF 74/86BB	SPERIC	ABB
74/TC	TRIP CIRCUIT SUPERVISION RELAY	74-TC1 74-TC2	MVAX31	ALSTOM
85DTTR	DIRECT TRANSFER TRIP RECEIVING RELAY	85DTTR	AR	ABB
86BB	BUSBAR PROT N TRIP LOCKOUT RELAY	86BB	LOR/HR	ES
86BF	BREAKER FAILURE PROT N TRIP LOCKOUT RELAY	86BF	LOR/HR	ES
87M 87CH	BUSBAR PROT. MAIN BUSBAR PROT. CHECK	87B+ 50BF/ -CU	REB500	ABB
94	PROTN. TRIP RELAY (SELF RESET)	94-1 94-2 94-BF	LOR/SR	ES
98	VT FUSE FAILURE SUPERVISION RELAY	98-1 98-2 98-L 98-BUS	RXBA4	ABB
BCU	BAY CONTROL UNIT WITH CURRENT, VOLTAGE, WATT, VAR MEASUREMENTS	BCU-A609	REC6T0	ABB

ABBREVIATIONS:

- FOC: FIBRE OPTIC CABLE (FOC)
- M: MEASURING VOLTAGE
- R: REFERENCE VOLTAGE
- TC1: TRIP CIRCUIT-1
- TC2: TRIP CIRCUIT-2
- HMI: HUMAN MACHINE INTERFACE
- SAS: SUBSTATION AUTOMATION SYSTEM
- ES: ETHERNET SWITCH
- FOTE: FIBER OPTIC TERMINAL EQUIPMENT
- 6RA1: DATIF 115KV UG LINE-1 SET-1 PROT. PANEL
- 6RB1: DATIF 115KV UG LINE-1 SET-2 PROT. PANEL
- 6B8CU: 115KV BUSBAR PROT. PANEL FOR CENTRAL UNIT
- 6BU1: 115KV BUSBAR BAY UNIT PANEL FOR (A609)
- LCC-A603: LOCAL CONTROL PANEL
- CICT: CURRENT ISOLATING CT TFR

REFERENCE DRAWINGS

DRAWING TITLE	DRAWING NO.
DRAWING CONTROL SHEET	EE-221387
SCOPE OF WORK & TECHNICAL SPECIFICATIONS	PTS-11EN146
MAIN SWITCHING ONE LINE DIAGRAM	EA-221470
	-
	-
	-

CONTRACTOR'S CONSULTANT:

DAR ENGINEERING **الدور الدولية للهندسة**
 ENGINEERS & DESIGNERS **مهندسون ومصممون**
 P.O. BOX 13103 **ص.ب. 13103**
 DAMMAN-31493 **الدمام 31493**

AS-BUILT BY _____ DATE _____

REV. NO.	DATE	BY	DESCRIPTION	CHKD.	CERT.	APPD.
B	03.2013	DAR	ISSUED FOR CONSTRUCTION	M.Z.K	O.B	A.Y.K
B	11.2012	DAR	ISSUED FOR DETAIL DESIGN	M.Z.K	O.B	A.Y.K
A	05.2012	DAR	FIRST ISSUE	M.Z.K	O.B	A.Y.K

DRAWING COMPLETION CERTIFICATE (DCC):

الشركة الوطنية لنقل الكهرباء **نقل الكهرباء**
 National Grid SA

DRAWN BY: G.MUSTAFA CHECKED BY: OSAMA/ZAHD SCALE: N.T.S
 DATE STARTED: 08.05.2012 DATE COMPLETED: _____
 OPR'G. DEPT. _____ ENG. DEPT. _____


THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION OR FOR ORDERING MATERIAL UNTIL CERTIFIED AND DATED BY _____ DATE _____

CERTIFIED BY _____ DATE _____

RELAYING AND METERING ONE LINE DIAGRAM
 LINE-1 115kV UG TO DATIF BSP S/S (A609)
 DATIF 115/13.8kV SUBSTATION NO. 2
 DATIF SAUDI ARABIA

CONTRACT NO.	JOB ORDER NO.	INDEX	PLANT NO.	DRAWING NUMBER	SHEET NO.	REV. NO.
31131127/00	1-113045.01	P	DA441	EA-221504	01	0

THIS DRAWING AND THE INFORMATION CONTAINED HEREIN ARE THE SOLE PROPERTY OF National Grid SA. NO REPRODUCTION IN FULL OR IN PART SHALL BE OBTAINED FROM THIS DOCUMENT WITHOUT THE WRITTEN CONSENT OF ITS OWNER.



NOTES

1. DRAWING NOTE

LEGEND

FUNCTION	DESCRIPTION	EOP	TYPE	MAKE
87L-1 21-1 67-1 67N-1	LINE DIFFERENTIAL PROT. LINE DISTANCE PROT. DIRECTIONAL O/C PROT. DIRECTIONAL E/F PROT.	87L-1& 21-1/ 67N-1/	RED 670	ABB
87L-2 21-2 67-2 67N-2	LINE DIFFERENTIAL PROT. LINE DISTANCE PROT. DIRECTIONAL O/C PROT. DIRECTIONAL E/F PROT.	87L-2& 21-2/ 67N-2/	P546	ALSTOM
50BF 62-BF1 62-BF2 87B	BREAKER FAILURE PROT. BF STAGE-1 TIMER BF STAGE-2 TIMER BUSBAR DIFFERENTIAL PROT.	87B+ 50BF/ BU-09	REB500	ABB
74	SUPERVISION RELAY FOR TRIP RELAY	74-1 74-2 74/94BF 74/86BF 74/86BB	SPERIC	ABB
74/TC	TRIP CIRCUIT SUPERVISION RELAY	74-TC1 74-TC2	MVAX31	ALSTOM
85DTTR	DIRECT TRANSFER TRIP RECEIVING RELAY	85DTTR	AR	ABB
86BB	BUSBAR PROT N TRIP LOCKOUT RELAY	86BB	LOR/HR	ES
86BF	BREAKER FAILURE PROT N TRIP LOCKOUT RELAY	86BF	LOR/HR	ES
87M 87CH	BUSBAR PROT. MAIN BUSBAR PROT. CHECK	87M+ 50BF/ -CU	REB500	ABB
94	PROTN. TRIP RELAY (SELF RESET)	94-1 94-2 94-BF	LOR/SR	ES
98	VT FUSE FAILURE SUPERVISION RELAY	98-1 98-2 98-L 98-BUS	RXBA4	ABB
BCU	BAY CONTROL UNIT WITH CURRENT, VOLTAGE, WATT, VAR MEASUREMENTS	BCU-A609	REC670	ABB

ABBREVIATIONS:

- FOC FIBRE OPTIC CABLE (FOC)
- M MEASURING VOLTAGE
- R REFERENCE VOLTAGE
- TC1 TRIP CIRCUIT-1
- TC2 TRIP CIRCUIT-2
- HMI HUMAN MACHINE INTERFACE
- SAS SUBSTATION AUTOMATION SYSTEM
- ES ETHERNET SWITCH
- FOTE FIBER OPTIC TERMINAL EQUIPMENT
- 6RA1 OATIF 115KV UG LINE-1 SET-1 PROT. PANEL
- 6RB1 OATIF 115KV UG LINE-1 SET-2 PROT. PANEL
- 6BBCU 115KV BUSBAR PROT. PANEL FOR CENTRAL UNIT
- 6BU1 115KV BUSBAR BAY UNIT PANEL FOR (A609)
- LCC-A603 LOCAL CONTROL PANEL
- CICT CURRENT ISOLATING CT TFR

REFERENCE DRAWINGS

DRAWING TITLE	DRAWING NO.
DRAWING CONTROL SHEET	EE-221387
SCOPE OF WORK & TECHNICAL SPECIFICATIONS	PTS-11EN146
MAIN SWITCHING ONE LINE DIAGRAM	EA-221470
	-
	-
	-

CONTRACTOR'S CONSULTANT:
DAR ENGINEERING **الدور الدولية للهندسة**
 ENGINEERS & DESIGNERS **مهندسون ومصممون**
 P.O. BOX 13103 **م.ب. 13103**
 DAMMAN-31493 **الدمام 31493**

AS-BUILT by _____ DATE _____

REV. NO.	DATE	BY	DESCRIPTION	CHKD.	CERT.	APPD.
0	03.2013	DAR	ISSUED FOR CONSTRUCTION	M.Z.K	O.B	A.Y.Y
B	11.2012	DAR	ISSUED FOR DETAIL DESIGN	M.Z.K	O.B	A.Y.Y
A	05.2012	DAR	FIRST ISSUE	M.Z.K	O.B	A.Y.Y

DRAWING COMPLETION CERTIFICATE (DCC):




DRAWN BY G.MUSTAFA CHECKED BY OSAMA/ZAHD SCALE: N.T.S
 DATE STARTED 08.05.2012 DATE COMPLETED _____
 PRG. DEPT. _____ ENG. DEPT. _____

THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION OR FOR ORDERING MATERIAL UNTIL CERTIFIED AND DATED BY _____ DATE _____

RELAYING AND METERING ONE LINE DIAGRAM
115kV U/G LINE TO OATIF BSP S/S (CB A609) (A611)
OATIF 115/13.8kV SUBSTATION NO. 2
OATIF SAUDI ARABIA

CONTRACT NO.	JOB ORDER NO.	INDEX	PLANT NO.	DRAWING NUMBER	SHEET NO.	REV. NO.
31131127/00	1-113045.01	P	DA441	EA-221504	02 of 15	0

THIS DRAWING AND THE INFORMATION CONTAINED HEREIN ARE THE SOLE PROPERTY OF National Grid SA NO REPRODUCTION IN FULL OR IN PART SHALL BE OBTAINED FROM THIS DOCUMENT WITHOUT THE WRITTEN CONSENT OF ITS OWNER.



NOTES

1. DRAWING NOTE

LEGEND

FUNCTION	DESCRIPTION	EOP	TYPE	MAKE
87L-1	LINE DIFFERENTIAL PROT.			
21-1	LINE DISTANCE PROT.	87L-1&21-1/67N-1/	RED 670	ABB
67-1	DIRECTIONAL O/C PROT.			
67N-1	DIRECTIONAL E/F PROT.			
87L-2	LINE DIFFERENTIAL PROT.			
21-2	LINE DISTANCE PROT.	87L-2&21-2/67N-2/	P546	ALSTOM
67-2	DIRECTIONAL O/C PROT.			
67N-2	DIRECTIONAL E/F PROT.			
50BF	BREAKER FAILURE PROT.			
62-BF1	BF STAGE-1 TIMER	87B+50BF/BU-09	REB500	ABB
62-BF2	BF STAGE-2 TIMER			
87B	BUSBAR DIFFERENTIAL PROT.			
74	SUPERVISION RELAY FOR TRIP RELAY	74-1 74-2 74/94BF 74/86BF 74/86BF	SPERIC	ABB
74/TC	TRIP CIRCUIT SUPERVISION RELAY	74-TC1 74-TC2	MVAX31	ALSTOM
85DTR	DIRECT TRANSFER TRIP RECEIVING RELAY	85DTR	AR	ABB
86BB	BUSBAR PROT TRIP LOCKOUT RELAY	86BB	LOR/HR	ES
86BF	BREAKER FAILURE PROT TRIP LOCKOUT RELAY	86BF	LOR/HR	ES
87M	BUSBAR PROT. MAIN	87B+50BF	REB500	ABB
87CH	BUSBAR PROT. CHECK	-CU		
94	PROTN. TRIP RELAY (SELF RESET)	94-1 94-2 94-BF	LOR/SR	ES
98	VT FUSE FAILURE SUPERVISION RELAY	98-1 98-2 98-L 98-BUS	RXB44	ABB
BCU	BAY CONTROL UNIT WITH CURRENT, VOLTAGE, WATT, VAR MEASUREMENTS	BCU-A606	REC670	ABB

ABBREVIATIONS:

- FOC - FIBRE OPTIC CABLE (FOC)
- M - MEASURING VOLTAGE
- R - REFERENCE VOLTAGE
- TC1 - TRIP CIRCUIT-1
- TC2 - TRIP CIRCUIT-2
- HMI - HUMAN MACHINE INTERFACE
- SAS - SUBSTATION AUTOMATION SYSTEM
- ES - ETHERNET SWITCH
- FOTE - FIBER OPTIC TERMINAL EQUIPMENT
- 6RA2 - QATIF 115KV UG LINE-2 SET-1 PROT. PANEL
- 6RB2 - QATIF 115KV UG LINE-2 SET-2 PROT. PANEL
- 6BB2 - 115KV BUSBAR PROT. PANEL FOR CENTRAL UNIT
- 6BU08 - 115KV BUSBAR BAY UNIT PANEL FOR (A606)
- LCC-A606 - LOCAL CONTROL PANEL
- CICT - CURRENT ISOLATING CT TFR

REFERENCE DRAWINGS

DRAWING TITLE	DRAWING NO.
DRAWING CONTROL SHEET	EE-221387
SCOPE OF WORK & TECHNICAL SPECIFICATIONS	PTS-11EN146
MAIN SWITCHING ONE LINE DIAGRAM	EA-221478
	-
	-
	-

CONTRACTOR'S CONSULTANT:
DAR ENGINEERING **الدار الدولية للمهندسين**
 ENGINEERS & DESIGNERS
 P.O. BOX 13103
 DAMMAM-31493

AS-BUILT By _____ DATE _____

REV. NO.	DATE	BY	DESCRIPTION	CHKD.	CERT.	APPD.
0	03.2013	DAR	ISSUED FOR CONSTRUCTION	M.Z.K	O.B	A.Y.V
B	11.2012	DAR	ISSUED FOR DETAIL DESIGN	M.Z.K	O.B	A.Y.V
A	05.2012	DAR	FIRST ISSUE	M.Z.K	O.B	A.Y.V

DRAWING COMPLETION CERTIFICATE (DCC):

الشركة الوطنية لنقل الكهرباء **نقل الكهرباء**
 National Grid SA


DRAWN BY: G.MUSTAFA CHECKED BY: OSAMA/ZAHID SCALE: N.T.S
 DATE STARTED: 08.05.2012 DATE COMPLETED: _____
 OPR'G. DEPT. _____ ENG. DEPT. _____

THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION OR FOR ORDERING MATERIAL UNTIL CERTIFIED AND DATED BY _____ DATE _____

RELAYING AND METERING ONE LINE DIAGRAM
LINE-1 115kV UG TO DATIF BSP S/S (A606)
QATIF 115/13.8kV SUBSTATION NO. 2
QATIF SAUDI ARABIA

CONTRACT NO.	JOB ORDER NO.	INDEX	PLANT NO.	DRAWING NUMBER	SHEET NO.	REV. NO.
31131127/00	1-113045.01	P	DA441	EA-221504	03 of 15	0

THIS DRAWING AND THE INFORMATION CONTAINED HEREIN ARE THE SOLE PROPERTY OF National Grid SA NO REPRODUCTION IN FULL OR IN PART SHALL BE OBTAINED FROM THIS DOCUMENT WITHOUT THE WRITTEN CONSENT OF ITS OWNER.



NOTES

1. DRAWING NOTE

LEGEND

FUNCTION	DESCRIPTION	EOP	TYPE	MAKE
87L-1	LINE DIFFERENTIAL PROT.	87L-1&21-1/67N-1	RED 670	ABB
21-1	LINE DISTANCE PROT.			
67-1	DIRECTIONAL O/C PROT.			
67N-1	DIRECTIONAL E/F PROT.			
87L-2	LINE DIFFERENTIAL PROT.	87L-2&21-2/67N-2	P546	ALSTOM
21-2	LINE DISTANCE PROT.			
67-2	DIRECTIONAL O/C PROT.			
67N-2	DIRECTIONAL E/F PROT.			
50BF	BREAKER FAILURE PROT.	87B+50BF/BU-09	REB500	ABB
62-BF1	BF STAGE-1 TIMER			
62-BF2	BF STAGE-2 TIMER			
87B	BUSBAR DIFFERENTIAL PROT.			
74	SUPERVISION RELAY FOR TRIP RELAY	74-1 74-2 74/94BF 74/86BF 74/86BF	SPERIC	ABB
74/TC	TRIP CIRCUIT SUPERVISION RELAY	74-TC1 74-TC2	MVAX31	ALSTOM
85DTR	DIRECT TRANSFER TRIP RECEIVING RELAY	85DTR	AR	ABB
86BB	BUSBAR PROT TRIP LOCKOUT RELAY	86BB	LOR/HR	ES
86BF	BREAKER FAILURE PROT TRIP LOCKOUT RELAY	86BF	LOR/HR	ES
87M	BUSBAR PROT. MAIN	87B+50BF	REB500	ABB
87CH	BUSBAR PROT. CHECK	-CU		
94	PROTN. TRIP RELAY (SELF RESET)	94-1 94-2 94-BF	LOR/SR	ES
98	VT FUSE FAILURE SUPERVISION RELAY	98-1 98-2 98-L 98-BUS	RXB44	ABB
BCU	BAY CONTROL UNIT WITH CURRENT, VOLTAGE, WATT, VAR MEASUREMENTS	BCU-A606	REC670	ABB

ABBREVIATIONS:

- FOC - FIBRE OPTIC CABLE (FOC)
- M - MEASURING VOLTAGE
- R - REFERENCE VOLTAGE
- TC1 - TRIP CIRCUIT-1
- TC2 - TRIP CIRCUIT-2
- HMI - HUMAN MACHINE INTERFACE
- SAS - SUBSTATION AUTOMATION SYSTEM
- ES - ETHERNET SWITCH
- FOTE - FIBER OPTIC TERMINAL EQUIPMENT
- 6RA2 - QATIF 115KV UG LINE-2 SET-1 PROT. PANEL
- 6RB2 - QATIF 115KV UG LINE-2 SET-2 PROT. PANEL
- 6BB2 - 115KV BUSBAR PROT. PANEL FOR CENTRAL UNIT
- 6BU09 - 115KV BUSBAR BAY UNIT PANEL FOR (A608)
- LCC-A606 - LOCAL CONTROL PANEL
- CICT - CURRENT ISOLATING CT TFR

REFERENCE DRAWINGS

DRAWING TITLE	DRAWING NO.
DRAWING CONTROL SHEET	EE-221387
SCOPE OF WORK & TECHNICAL SPECIFICATIONS	PTS-11EN146
MAIN SWITCHING ONE LINE DIAGRAM	EA-221478
	-
	-
	-

CONTRACTOR'S CONSULTANT:
DAR ENGINEERING **الدار الدولية للمهندسين**
 ENGINEERS & DESIGNERS
 P.O. BOX 13103
 DAMMAM-31493

AS-BUILT By _____ DATE _____

REV. NO.	DATE	BY	DESCRIPTION	CHKD.	CERT.	APPD.
0	03.2013	DAR	ISSUED FOR CONSTRUCTION	M.Z.K	O.B	A.Y.K
B	11.2012	DAR	ISSUED FOR DETAIL DESIGN	M.Z.K	O.B	A.Y.K
A	05.2012	DAR	FIRST ISSUE	M.Z.K	O.B	A.Y.K

DRAWING COMPLETION CERTIFICATE (DCC):

الشركة الوطنية لنقل الكهرباء **نقل الكهرباء**
 National Grid SA

DRAWN BY G.MUSTAFA CHECKED BY OSAMA/ZAHID SCALE: N.T.S

DATE STARTED 08.05.2012 DATE COMPLETED _____

PRG. DEPT. _____ ENG. DEPT. _____

THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION OR FOR ORDERING MATERIAL UNTIL CERTIFIED AND DATED BY _____ DATE _____

RELAYING AND METERING ONE LINE DIAGRAM



115kV U/G LINE TO QATIF BSP S/S (CB-A606) (A608)

QATIF 115/13.8kV SUBSTATION NO. 2

QATIF SAUDI ARABIA

CONTRACT NO.	JOB ORDER NO.	INDEX	PLANT NO.	DRAWING NUMBER	SHEET NO.	REV. NO.
31131127/00	1-113045.01	P	DA441	EA-221504	04	0

THIS DRAWING AND THE INFORMATION CONTAINED HEREIN ARE THE SOLE PROPERTY OF National Grid SA NO REPRODUCTION IN FULL OR IN PART SHALL BE OBTAINED FROM THIS DOCUMENT WITHOUT THE WRITTEN CONSENT OF ITS OWNER.



NOTES

1. DRAWING NOTE

LEGEND

FUNCTION	DESCRIPTION	EQP	TYPE	MAKE
50BF	BREAKER FAILURE PROT.	87B	REB500	ABB
62-BF1	BF STAGE-1 TIMER	87B	REB500	ABB
62-BF2	BF STAGE-2 TIMER	87B	REB500	ABB
87B	BUSBAR DIFFERENTIAL PROT.	87B	REB500	ABB
74	SUPERVISION RELAY FOR TRIP RELAY	74/94BF	SPERIC	ABB
74/TC	TRIP CIRCUIT SUPERVISION RELAY	74-TC1	ALSTOM	ALSTOM
86BB	BUSBAR PROTIN TRIP LOCKOUT RELAY	86BB	LOR/HR	ES
86BF	BREAKER FAILURE PROTIN TRIP LOCKOUT RELAY	86BF	LOR/HR	ES
87M	BUSBAR PROTIN. MAIN	87B+	REB500	ABB
87CH	BUSBAR PROTIN. CHECK	87B+	REB500	ABB
94	PROTN. TRIP RELAY (SELF RESET)	94-BF	LOR/SR	ES
98	VT FUSE FAILURE SUPERVISION RELAY	98-L	RXBA4	ABB
BCU	BAY CONTROL UNIT WITH CURRENT, VOLTAGE, WATT, VAR MEASUREMENTS	BCU-A617	REC670	ABB
BCU	BAY CONTROL UNIT WITH CURRENT, VOLTAGE, WATT, VAR MEASUREMENTS	BCU-A6014	REC670	ABB

ABBREVIATIONS:

FC	FIBRE OPTIC CABLE (FOC)
M	MEASURING VOLTAGE
R	REFERENCE VOLTAGE
TC1	TRIP CIRCUIT-1
TC2	TRIP CIRCUIT-2
HMI	HUMAN MACHINE INTERFACE
BCP	BAY CONTROL PANEL
ES	ETHERNET SWITCH
SAS	SUBSTATION AUTOMATION SYSTEM
6BBCU	115KV BUSBAR PROTIN. PANEL FOR CENTRAL UNIT
6BU1	115KV BUSBAR BAY UNIT PANEL FOR (A617)
6BU10	115KV BUSBAR BAY UNIT PANEL FOR (A614)
+6TCS1	115KV TRIP CIRCUIT SUPERVISION PANEL
LCC-A617	LOCAL CONTROL PANEL
LCC-A614	LOCAL CONTROL PANEL

REFERENCE DRAWINGS

DRAWING TITLE	DRAWING NO.
DRAWING CONTROL SHEET	EE-221387
SCOPE OF WORK & TECHNICAL SPECIFICATIONS	PTS-11EN146
MAIN SWITCHING ONE LINE DIAGRAM	EA-221478
	-
	-
	-

CONTRACTORS CONSULTANT:

DAR ENGINEERING

ENGINEERS & DESIGNERS

P.O. BOX 13103
DAMMAM-31493

المهندسين والذات العالمية للهندسة
مهندسين ومهندسين
13103
الدمام 31493

AS-BUILT

REV. NO.	DATE	BY	DESCRIPTION	CHKD.	CERT.	APPD.
0	03.2013	DAR	ISSUED FOR CONSTRUCTION	M.Z.K	O.B	A.Y.K
B	11.2012	DAR	ISSUED FOR DETAIL DESIGN	M.Z.K	O.B	A.Y.K
A	05.2012	DAR	FIRST ISSUE	M.Z.K	O.B	A.Y.K

DRAWING COMPLETION CERTIFICATE (DCC):

الشركة الوطنية لنقل الكهرباء

الشركة الوطنية لنقل الكهرباء
National Grid SA

DRAWN BY: G.MUSTAFA CHECKED BY: OSAMA/ZAHID SCALE: N.T.S


DATE STARTED: 08.05.2012 DATE COMPLETED:

PRG. DEPT. ENG. DEPT.

THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION OR FOR ORDERING MATERIAL UNTIL CERTIFIED AND DATED BY DATE

RELAYING AND METERING ONE LINE DIAGRAM
115kV SPARE LINE-1 (A617) & LINE-2 (A614)
QATIF 115/13.8kV SUBSTATION NO. 2
QATIF SAUDI ARABIA

THIS DRAWING AND THE INFORMATION CONTAINED HEREIN ARE THE SOLE PROPERTY OF National Grid SA NO REPRODUCTION IN FULL OR IN PART SHALL BE OBTAINED FROM THIS DOCUMENT WITHOUT THE WRITTEN CONSENT OF ITS OWNER.



NOTES

1. DRAWING NOTE

LEGEND

FUNCTION	DESCRIPTION	EOP	TYPE	MAKE
50BF	BREAKER FAILURE PROT.N.	87B+50BF/BU-03	REB500	ABB
62-BF1	BF STAGE-1 TIMER			
62-BF2	BF STAGE-2 TIMER			
87B1 & 2	BUSBAR DIFFERENTIAL PROT.N.			
5IBC	NON DIRECTIONAL O/C & E/F PROT.N.	5I	PI42	ALSTOM
74	SUPERVISION RELAY FOR TRIP RELAY	74/94BF	SPERIC	ABB
74/TC	TRIP CIRCUIT SUPERVISION RELAY	74-TC1 74-TC2	MVAX31	ALSTOM
86BB-1	BUSBAR PROT.N TRIP LOCKOUT RELAY	86BB	LOR/HR	ES
86BF-1	BREAKER FAILURE PROT.N TRIP	86BF	LOR/HR	ES
86BF-2	LOCKOUT RELAY	86BF-2	LOR/HR	ES
86BC1	BUSCOUPLER-1 PROT.N TRIP LOCKOUT RELAY	86BC1	LOR/HR	ES
87M	BUSBAR PROT.N. MAIN	87M	REB500	ABB
87CH	BUSBAR PROT.N. CHECK	87CH	REB500	ABB
94	PROT.N. TRIP RELAY (SELF RESET)	94-BF	LOR/SR	ES
98	VT FUSE SUPERVISION RELAY	98-1A 98-2A	RXB44	ABB
BCU	BAY CONTROL UNIT WITH CURRENT, VOLTAGE, WATT, VAR MEASUREMENTS	BCU-A603	REC670	ABB

ABBREVIATIONS:

M	MEASURING VOLTAGE
R	REFERENCE VOLTAGE
TC1	TRIP CIRCUIT-1
TC2	TRIP CIRCUIT-2
HMI	HUMAN MACHINE INTERFACE
FC	FIBRE OPTIC CABLE (FOC)
BPP	BAY PROTECTION PANEL
BCP	BAY CONTROL PANEL
BPP	BAY PROTECTION PANEL
ES	ETHERNET SWITCH
SAS	SUBSTATION AUTOMATION SYSTEM
IED-EC	INTELLIGENT ELECTRONIC DEVICE FOR EMERGENCY CONTROL
IED-C	INTELLIGENT ELECTRONIC DEVICE FOR CONTROL
6BUCU	115KV BUSBAR PROT.N. PANEL FOR CENTRAL UNIT
6BU05	115KV BUS COUPLER 1A/2A PROT.N. PANEL
+6BC1	115KV BUS COUPLER 1A/2A PROT.N. PANEL
LCC-A603	LOCAL CONTROL PANEL
CICT	CURRENT ISOLATING CT TFR

REFERENCE DRAWINGS

DRAWING TITLE	DRAWING NO.
DRAWING CONTROL SHEET	EE-221387
SCOPE OF WORK & TECHNICAL SPECIFICATIONS	PTS-11EN146
MAIN SWITCHING ONE LINE DIAGRAM	EA-221470
	-
	-
	-

CONTRACTOR'S CONSULTANT:

DAR ENGINEERING **الدور الدولية للهندسة**
 ENGINEERS & DESIGNERS
 P.O. BOX 13103
 DAMMAM-31493

AS-BUILT BY _____ DATE _____

REV. NO.	DATE	BY	DESCRIPTION	CHKD.	CERT.	APPD.
0	03.2013	DAR	ISSUED FOR CONSTRUCTION	M.Z.K	O.B	A.Y.Y
B	11.2012	DAR	ISSUED FOR DETAIL DESIGN	M.Z.K	O.B	A.Y.Y
A	05.2012	DAR	FIRST ISSUE	M.Z.K	O.B	A.Y.Y

DRAWING COMPLETION CERTIFICATE (DCC):


الشركة الوطنية لنقل الكهرباء **نقل الكهرباء**
 National Grid SA

DRAWN BY G.MUSTAFA CHECKED BY OSAMA/ZAHID SCALE: N.T.S
 DATE STARTED 08.05.2012 DATE COMPLETED _____
 PRG. DEPT. _____ ENG. DEPT. _____

THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION OR FOR ORDERING MATERIAL UNTIL CERTIFIED AND DATED BY _____ DATE _____

RELAYING AND METERING ONE LINE DIAGRAM
115kV BUS COUPLER-1 (A603)
QATIF 115/13.8kV SUBSTATION NO. 2
QATIF SAUDI ARABIA

THIS DRAWING AND THE INFORMATION CONTAINED HEREIN ARE THE SOLE PROPERTY OF National Grid SA. NO REPRODUCTION IN FULL OR IN PART SHALL BE OBTAINED FROM THIS DOCUMENT WITHOUT THE WRITTEN CONSENT OF ITS OWNER.



NOTES

1. DRAWING NOTE

LEGEND

FUNCTION	DESCRIPTION	EOP	TYPE	MAKE
50BF	BREAKER FAILURE PROT.N.	87B+50BF/BU-01	REB500	ABB
62-BF1	BF STAGE-1 TIMER			
62-BF2	BF STAGE-2 TIMER			
87B1 & 2	BUSBAR DIFFERENTIAL PROT.N.			
51BS	NON DIRECTIONAL O/C & E/F PROT.N.	51 5IN	PI42	ALSTOM
74	SUPERVISION RELAY FOR TRIP RELAY	74/94BF-74/86BF-74/86BB-74/86BS	SPERIC	ABB
74/TC	TRIP CIRCUIT SUPERVISION RELAY	74-TC1 74-TC2	VMVX31	ALSTOM
86BB-1	BUSBAR PROT.N TRIP LOCKOUT RELAY	86BB	LOR/HR	ES
86BB-2	BREAKER FAILURE PROT.N TRIP LOCKOUT RELAY	86BF	LOR/HR	ES
86BS	BUS SECTION PROT.N TRIP LOCKOUT RELAY	86BS	LOR/HR	ES
87M	BUSBAR PROT.N. MAIN	87B+50BF-CU	REB500	ABB
87CH	BUSBAR PROT.N. CHECK ZONE	87M 87CH		
94	PROT.N. TRIP RELAY (SELF RESET)	94-BF	LOR/SR	ES
95	CURRENT SUPERVISION RELAY	95B-1 95B-2	-----	-----
98	VT FUSE SUPERVISION RELAY	98-1A 98-1C	RXBA4	ABB
BCU	BAY CONTROL UNIT WITH CURRENT, VOLTAGE, WATT, VAR MEASUREMENTS	BCU-A601	REC670	ABB

- ABBREVIATIONS:**
- M MEASURING VOLTAGE
 - R REFERENCE VOLTAGE
 - TC1 TRIP CIRCUIT-1
 - TC2 TRIP CIRCUIT-2
 - HMI HUMAN MACHINE INTERFACE
 - FOC FIBRE OPTIC CABLE (FOC)
 - BCP BAY CONTROL PANEL
 - BPP BAY PROTECTION PANEL
 - ES ETHERNET SWITCH
 - SAS SUBSTATION AUTOMATION SYSTEM
 - IED-EC INTELLIGENT ELECTRONIC DEVICE FOR EMERGENCY CONTROL
 - IED-C INTELLIGENT ELECTRONIC DEVICE FOR CONTROL
 - 6BUCU 115KV BUSBAR PROT.N. PANEL FOR CENTRAL UNIT
 - 6BUB 115KV BUSBAR BAY UNIT PANEL FOR (A601)
 - 6BS1 115KV BUS SECTION IB PROT.N. PANEL
 - BCP-A601 LOCAL CONTROL PANEL
 - CICT CURRENT ISOLATING CT TFR

REFERENCE DRAWINGS

DRAWING TITLE	DRAWING NO.
DRAWING CONTROL SHEET	EE-221387
SCOPE OF WORK & TECHNICAL SPECIFICATIONS	PTS-11EN146
MAIN SWITCHING ONE LINE DIAGRAM	EA-221470
	-
	-
	-

CONTRACTOR'S CONSULTANT:

DAR ENGINEERING **الدار الدولية للهندسة**
 ENGINEERS & DESIGNERS **مهندسون ومصممون**
 P.O. BOX 13103 **الرياض**
 DAMMAM-31493 **الدمام**

AS-BUILT By _____ DATE _____

REV. NO.	DATE	BY	DESCRIPTION	CHKD.	CERT.	APPD.
0	03.2013	DAR	ISSUED FOR CONSTRUCTION	M.Z.K	O.B	A.Y.Y
B	11.2012	DAR	ISSUED FOR DETAIL DESIGN	M.Z.K	O.B	A.Y.Y
A	05.2012	DAR	FIRST ISSUE	M.Z.K	O.B	A.Y.Y

DRAWING COMPLETION CERTIFICATE (DCC):



DRAWN BY G.MUSTAFA CHECKED BY OSAMA/ZAHID SCALE: N.T.S



DATE STARTED 08.05.2012 DATE COMPLETED _____

PRG. DEPT. _____ ENG. DEPT. _____

THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION OR FOR ORDERING MATERIAL UNTIL CERTIFIED AND DATED BY _____ DATE _____

RELAYING AND METERING ONE LINE DIAGRAM
115kV BUS SECTION (A601)
QATIF 115/13.8kV SUBSTATION NO. 2
QATIF SAUDI ARABIA

THIS DRAWING AND THE INFORMATION CONTAINED HEREIN ARE THE SOLE PROPERTY OF National Grid SA NO REPRODUCTION IN FULL OR IN PART SHALL BE OBTAINED FROM THIS DOCUMENT WITHOUT THE WRITTEN CONSENT OF ITS OWNER.



NOTES

1. DRAWING NOTE

LEGEND

FUNCTION	DESCRIPTION	EOP	TYPE	MAKE
50BF	BREAKER FAILURE PROT.N.	87B+50BF/BU-02	REB500	ABB
62-BF1	BF STAGE-1 TIMER	51	PI42	ALSTOM
62-BF2	BF STAGE-2 TIMER	51	PI42	ALSTOM
87B1 & 2	BUSBAR DIFFERENTIAL PROT.N. RELAY	74/94BF, 74/86BF, 74/86BB, 74/86BC2	SPERIC	ABB
51BC	NON DIRECTIONAL O/C & E/F PROT.N.	51	PI42	ALSTOM
51BC-N		51	PI42	ALSTOM
74	SUPERVISION RELAY FOR TRIP RELAY	74/94BF, 74/86BF, 74/86BB, 74/86BC2	SPERIC	ABB
74/TC	TRIP CIRCUIT SUPERVISION RELAY	74-TC1, 74-TC2	MVAX31	AREVA
86BB-1	BUSBAR PROT.N. TRIP LOCKOUT RELAY	86BB	LOR/HR	ES
86BB-2	BUSBAR PROT.N. TRIP LOCKOUT RELAY	86BB	LOR/HR	ES
86BF-1	BREAKER FAILURE PROT.N. TRIP LOCKOUT RELAY	86BF	LOR/HR	ES
86BF-2	BREAKER FAILURE PROT.N. TRIP LOCKOUT RELAY	86BF	LOR/HR	ES
86BC2	BUSCOUPLER-2 PROT.N. TRIP LOCKOUT RELAY	86BC2	LOR/HR	ES
87M	BUSBAR PROT.N. MAIN	87B+50BF-CU	REB500	ABB
87CH	BUSBAR PROT.N. CHECK ZONE	87B+50BF-CU	REB500	ABB
94	PROT.N. TRIP RELAY (SELF RESET)	94-BF	LOR/SR	ES
98	VT FUSE SUPERVISION RELAY	98-IC, 98-2C	RXBA4	ABB
BCU	BAY CONTROL UNIT WITH CURRENT, VOLTAGE, WATT, VAR MEASUREMENTS	BCU-A602	REC670	ABB

ABBREVIATIONS:

- M MEASURING VOLTAGE
- R REFERENCE VOLTAGE
- TC1 TRIP CIRCUIT-1
- TC2 TRIP CIRCUIT-2
- HMI HUMAN MACHINE INTERFACE
- FOC FIBRE OPTIC CABLE (FOC)
- BOP BAY OPERATION PANEL
- BPP BAY PROTECTION PANEL
- ES ETHERNET SWITCH
- SAS SUBSTATION AUTOMATION SYSTEM
- FOTE FIBER OPTIC TERMINAL EQUIPMENTS
- IED-EC INTELLIGENT ELECTRONIC DEVICE FOR EMERGENCY CONTROL
- IED-C INTELLIGENT ELECTRONIC DEVICE FOR CONTROL
- 6BBU07 115KV BUSBAR PROT.N. PANEL FOR CENTRAL UNIT
- +6BC2 115KV BUS COUPLER IC/2C PROT.N. PANEL
- LCC-A602 LOCAL CONTROL PANEL
- CICT CURRENT ISOLATING CT TFR

REFERENCE DRAWINGS

DRAWING TITLE	DRAWING NO.
DRAWING CONTROL SHEET	EE-221307
SCOPE OF WORK & TECHNICAL SPECIFICATIONS	PTS-11EN146
MAIN SWITCHING ONE LINE DIAGRAM	EA-221470
	-
	-
	-

CONTRACTOR'S CONSULTANT:
DAR ENGINEERING **الدار الدولية للمهندسين**
 ENGINEERS & DESIGNERS
 P.O. BOX 13103
 DAMMAM-31493

AS-BUILT By _____ DATE _____

REV. NO.	DATE	BY	DESCRIPTION	CHKD.	CERT.	APPD.
0	03.2013	DAR	ISSUED FOR CONSTRUCTION	M.Z.K	O.B	A.Y.Y
B	11.2012	DAR	ISSUED FOR CONSTRUCTION	M.Z.K	O.B	A.Y.Y
A	05.2012	DAR	FIRST ISSUE	M.Z.K	O.B	A.Y.Y

DRAWING COMPLETION CERTIFICATE (DCC):

الشركة الوطنية لنقل الكهرباء **نقل الكهرباء**
National Grid SA

DRAWN BY: G.MUSTAFA CHECKED BY: OSAMA/ZAHD SCALE: N.T.S
 DATE STARTED: 08.05.2012 DATE COMPLETED: _____
 ORIG. DEPT. _____ ENG. DEPT. _____


THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION OR FOR ORDERING MATERIAL UNTIL CERTIFIED AND DATED BY _____ DATE _____

RELAYING AND METERING ONE LINE DIAGRAM
115kV BUS COUPLER-2 (A602)
QATIF 115/13.8kV SUBSTATION NO. 2
QATIF SAUDI ARABIA

CONTRACT NO.	JOB ORDER NO.	INDEX	PLANT NO.	DRAWING NUMBER	SHEET NO.	REV. NO.
31131127/00	1-113045.01	P	DA441	EA-221504	08	0

NG-A (2012/01) NGA00

THIS DRAWING AND THE INFORMATION CONTAINED HEREIN ARE THE SOLE PROPERTY OF National Grid SA. NO REPRODUCTION IN FULL OR IN PART SHALL BE OBTAINED FROM THIS DOCUMENT WITHOUT THE WRITTEN CONSENT OF ITS OWNER.



LEGEND

RELAY	DESCRIPTION	TYPE	MAKE
26-2	OIL TEMPERATURE HIGH (TRIP)	LOR/SR	ES
49-2/HV	WINDING TEMPERATURE HIGH-HV (TRIP)	LOR/SR	ES
49-2/LV	WINDING TEMPERATURE HIGH-LV (TRIP)	LOR/SR	ES
63PRD-1T	PRESSURE RELIEF DEVICE MAIN TANK (TRIP)	LOR/SR	ES
63PRD-2T	PRESSURE RELIEF DEVICE TAP CHANGER (TRIP)	LOR/SR	ES
96-2	BUCHHOLZ RELAY - MAIN TANK (TRIP)	LOR/SR	ES

DESCRIPTION

26-1	OIL TEMPERATURE HIGH (ALARM)
49-1/HV	WINDING TEMPERATURE HIGH-HV (ALARM)
49-1/LV	WINDING TEMPERATURE HIGH-LV (ALARM)
63PRD-1	PRESSURE RELIEF DEVICE MAIN TANK (ALARM)
63PRD-2	PRESSURE RELIEF DEVICE TAP CHANGER (ALARM)
63OP-1	OLTC PROTECTIVE RELAY (ALARM)
71OL-1	OIL LEVEL LOW - MAIN TANK (ALARM)
71OL-2	OIL LEVEL LOW - OLTC (ALARM)
961	BUCHHOLZ RELAY - MAIN TANK (ALARM)
96DA	GAS DETECTOR RELAY (ALARM)
COLF	TRANSFORMER COOLER TROUBLE (ALARM)

ABBREVIATIONS

ABTS	AUTOMATIC BUS TRANSFER SCHEME
ACCS	AUTOMATIC CAPACITOR CONTROL SYSTEM
AVR	AUTOMATIC VOLTAGE REGULATOR
BPP	BUS PROTECTION PANEL
DA	DIGITAL AMMETER
DCU	DATA COLLECTION UNIT
DPM	DIGITAL POWER METER CONVERTING MW, MVAR
DRCT	DUAL RATIO CURRENT TRANSFORMER
DV	DIGITAL VOLTMETER
HMI	HUMAN MACHINE INTERFACE
M	MEASURING VOLTAGE
MRCT	MULTIRATIO CURRENT TRANSFORMER
PQM	POWER QUALITY METER
R	REFERENCE VOLTAGE
RM	REVENUE METER
SA	SURGE ARRESTOR
TC-1	TRIP CIRCUIT-1
TC-2	TRIP CIRCUIT-2
BCP	BAY CONTROL PANEL
ES	ETHERNET SWITCH
FC	FIBRE OPTIC CABLE (FOC)

LEGEND

FUNCTION	DESCRIPTION	EOP	TYPE	MAKE
87REF /LV	RESTRICTED EARTH FAULT PROT.N.	87REF /LV	MCAG14	ALSTOM
87T	TRAF.O. DIFF. PROT.N.	87T	RET170	ABB
50BF	BREAKER FAILURE PROTECTION	50BF	REB500	ABB
62-BF1	BF STAGE-1 TIMER	87B+50BF/BU-07		
62-BF2	BF STAGE-2 TIMER			
87B	BUSBAR DIFFERENTIAL PROT.N.			
50/51-1	HV SIDE NON DIR. O/C & E/F PROT.N.-1	50/51-1	P142	ALSTOM
50/51-2	HV SIDE NON DIR. O/C & E/F PROT.N.-2	50/51-2	P142	ALSTOM
51G	LV NEUTRAL O/C PROT.N.	51G	P142	ALSTOM
67/67N	LV SIDE DIRECTIONAL O/C & E/F PROT.N.	67/67N	P142	ALSTOM
87M/A605	BUSBAR PROT.N. MAIN	87B+50BF/BU-07		
87CH/A605	BUSBAR PROT.N. CHECK			
74	SUPERVISION RELAY FOR TRIP RELAY	74/861-1	SPECIC	ABB
74/TC	TRIP CIRCUIT SUPERVISION RELAY	74/TC1	VMVX31	ALSTOM
86T	PROTECTION TRIP LOCKOUT RELAY	86T-1	LOR/HR	ES
86BB	BUSBAR PROT.N. TRIP LOCKOUT RELAY	86BB	LOR/HR	ES
86BF	BREAKER FAILURE PROT.N. TRIP LOCKOUT RELAY	86BF	LOR/HR	ES
94	PROTN. TRIP RELAY (SELF RESET)	94-BF	LOR/SR	ES
95	PROTN. TRIP RELAY (SELF RESET)	95-B	-----	-----
98	VT FUSE FAILURE SUPERVISION RELAY	98-T	RXB44	ABB
BCU	BAY CONTROL UNIT WITH CURRENT, VOLTAGE, WATT, VAR MEASUREMENTS	BCU - REC670		ABB
BCU	BAY CONTROL UNIT WITH CURRENT, VOLTAGE, WATT, VAR MEASUREMENTS	BCU - REF615		ABB
TP, V, AVR	TAP POSITION INDICATOR VOLTAGE MEASUREMENT AUTOMATIC VOLTAGE REGULATOR	90	TAPCON	MR
RM2	REVENUE METER	AMR	-----	-----
25	CONTROL & SYNCHECK FUNCTION	25	KAVS100	ALSTOM

REFERENCE DRAWINGS

DRAWING TITLE	DRAWING NO.
DRAWING CONTROL SHEET	EE-221387
SCOPE OF WORK & TECHNICAL SPECIFICATIONS	PTS-11EN146
MAIN SWITCHING ONE LINE DIAGRAM	EA-221470
	-
	-
	-

AS-BUILT

NO.	DATE	BY	DESCRIPTION	CHKD.	CERT.	APPD.
0	03.2013	DAR	ISSUED FOR CONSTRUCTION	M.Z.K	O.B	A.Y.Y.
B	11.2012	DAR	ISSUED FOR DETAIL DESIGN	M.Z.K	O.B	A.Y.Y.
A	05.2012	DAR	FIRST ISSUE	M.Z.K	O.B	A.Y.Y.

DRAWING COMPLETION CERTIFICATE (DCC):

CONTRACTOR'S CONSULTANT: **DAR ENGINEERING** (الدار الهندسية)

ENGINEERS & DESIGNERS: **مهندسون ومصممون**

P.O. BOX 13103, DAMMAM-31493, SAUDI ARABIA

RELAYING AND METERING ONE LINE DIAGRAM

DATIF 115/13.8kV SUBSTATION NO. 2

DATIF SAUDI ARABIA

DRAWN BY: G.MUSTAFA, CHECKED BY: OSAMA/ZAHID, SCALE: N.T.S.


DATE STARTED: 08.05.2012, DATE COMPLETED: _____

OPPG. DEPT.: _____, ENG. DEPT.: _____

THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION OR FOR ORDERING MATERIAL UNTIL CERTIFIED AND DATED BY _____ DATE _____

CERTIFIED BY _____ DATE _____

THIS DRAWING AND THE INFORMATION CONTAINED HEREIN ARE THE SOLE PROPERTY OF National Grid SA. NO REPRODUCTION IN FULL OR IN PART SHALL BE OBTAINED FROM THIS DOCUMENT WITHOUT THE WRITTEN CONSENT OF ITS OWNER.



NOTES

1. DRAWING NOTE

LEGEND

FUNCTION	DESCRIPTION	EOP	TYPE	MAKE
50/5IPAN	PROTECTION RELAY	80/50/5IPAN	REF615	ABB
CU +59+27	AUTOMATIC BUS TRANSFER CONTROL UNIT WITH BUILT IN UNDER VOLTAGE RELAY & OVER VOLTAGE RELAY	CU +59+27	REC670	ABB
CU-ACCS	AUTOMATIC CAPACITOR CONTROL UNIT	CU	REC670	ABB
RM	REVENUE METER FOR STN. FEEDER	RM4	-----	-----
25	SYNCHROCHECK RELAY	25	KAVS100	ALSTOM
74	SUPERVISION RELAY FOR TRIP RELAY	74-86/A304	SPECIC1	ABB
74/TC	TRIP CIRCUIT SUPERVISION RELAY	74-TC1/A304	MWAX31	ALSTOM
74/DC	DC SUPPLY SUPERVISION RELAY	74/DC	MWAX12	ALSTOM
86	PROTECTION TRIP LOCKOUT RELAY	86-A304	LOR/HR	ES
87	13.8kV BUS DIFFERENTIAL PROT.	87-B1	MCAG14	ALSTOM
95	CT SUPERVISION RELAY	95-B1	MVPII1	ALSTOM
98	VT FUSE FAILURE SUPERVISION RELAY	98-B1	RXB44	ABB

DEVICE FUNCTION NUMBERS

25	SYNCHRO CHECK RELAY
59	SYSTEM OVER VOLTAGE RELAY
79	AUTO-RECLOSE RELAY
86	LOCKOUT RELAY
87B	BUSBAR DIFFERENTIAL RELAY
94	TRIPPING RELAY, SELF RESET
95B	C.T CIRCUIT SUPERVISION RELAY
95Bx	C.T SECONDARY SHORTING LOCKOUT RELAY
98	FUSE FAILURE RELAY

ABBREVIATIONS

ABTS AUTOMATIC BUS TRANSFER SCHEME
 ACCS AUTOMATIC CAPACITOR CONTROL SYSTEM
 BCU BUS CONTROL UNIT
 DA DIGITAL AMMETER

REFERENCE DRAWINGS

DRAWING TITLE	DRAWING NO.
DRAWING CONTROL SHEET	EE-221387
SCOPE OF WORK & TECHNICAL SPECIFICATIONS	PTS-11EN146
MAIN SWITCHING ONE LINE DIAGRAM	EA-221470
	-
	-
	-

DV DIGITAL VOLTMETER
 HMI HUMAN MACHINE INTERFACE
 M MEASURING VOLTAGE
 DPDM MULTI FUNCTION METER WITH 30 DISPLAY OF CURRENT, VOLTAGE, PF RECORDING & MAXIMUM DEMAND RECORDING
 R REFERENCE VOLTAGE
 RM REVENUE METER
 TC-1 TRIP CIRCUIT-1
 TC-2 TRIP CIRCUIT-2
 ES ETHERNET SWITCH

CONTRACTOR'S CONSULTANT:
DAR ENGINEERING **الدار الدولية للمهندسين والمصممين**
 P.O. BOX 13103
 DAMMAM-31493

AS-BUILT

NO.	DATE	BY	DESCRIPTION	CHKD.	CERT.	APPD.
0	03.2013	DAR	ISSUED FOR CONSTRUCTION	M.Z.K.	O.B.	A.Y.V.
B	11.2012	DAR	ISSUED FOR DETAIL DESIGN	M.Z.K.	O.B.	A.Y.V.
A	08-05-12	DAR	FIRST ISSUE	M.Z.K.	O.B.	A.Y.V.

DRAWING COMPLETION CERTIFICATE (DCC)

الشركة الوطنية لنقل الكهرباء National Grid

DRAWN BY G.MUSTAFA CHECKED BY OSAMA/ZAHID SCALE: N.T.S
 DATE STARTED 08.05.2012 DATE COMPLETED
 ORIG. DEPT. ENG. DEPT.

THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION OR FOR ORDERING MATERIAL UNTIL CERTIFIED AND DATED BY DATE

RELAYING AND METERING ONE LINE DIAGRAM

13.8kV SYSTEM

QATIF 115/13.8kV SUBSTATION NO. 2

DATIF SAUDI ARABIA

CONTRACT NO.	JOB ORDER NO.	INDEX	PLANT NO.	DRAWING NUMBER	SHEET NO.	REV. NO.
31131127/00	1-113045.01	P	DA441	EA-221504	12	0

THIS DRAWING AND THE INFORMATION CONTAINED HEREIN ARE THE SOLE PROPERTY OF National Grid SA. NO REPRODUCTION IN FULL OR IN PART SHALL BE OBTAINED FROM THIS DOCUMENT WITHOUT THE WRITTEN CONSENT OF ITS OWNER.

1. DRAWING NOTE

LEGEND

FUNCTION	DESCRIPTION	EOP	TYPE	MAKE
50/5IP&N	PROTECTION RELAY	80/50/5IP&N	REF615	ABB
CU+59+27	AUTOMATIC BUS TRANSFER CONTROL UNIT WITH BUILT IN UNDER VOLTAGE RELAY & OVER VOLTAGE RELAY	CU+59+27	REC670	ABB
CU-ACC5	AUTOMATIC CAPACITOR CONTROL UNIT	REC670	ABB
25	SYNCHRO CHECK RELAY	25	KAVS100	ALSTOM
74	SUPERVISION RELAY FOR TRIP RELAY	74-86/A305 74-86/B3	SPERIC1	ABB
74/TC	TRIP CIRCUIT SUPERVISION RELAY	74-TC1/A305 74-TC2/A305	MVAX 31	ALSTOM
74/DC	DC SUPPLY SUPERVISION RELAY	74/DC	MVAX12	ALSTOM
86	PROTECTION TRIP LOCKOUT RELAY	86-A305 86-B3	LOR/HR	ELECTRO SW
87	13.8kV BUS DIFFERENTIAL PROT.N.	87-B3	MCAG14	ALSTOM
95	CT SUPERVISION RELAY	95-B3	MVTP11	ALSTOM
98	VT FUSE FAILURE SUPERVISION RELAY	98-B2 98-B3	RXBA4	ABB


ABBREVIATIONS :

ABTS	AUTOMATIC BUS TRANSFER SCHEME
ACC5	AUTOMATIC CAPACITOR CONTROL SYSTEM
BCU	BUS CONTROL UNIT
DA	DIGITAL AMMETER
DV	DIGITAL VOLTMETER
HMI	HUMAN MACHINE INTERFACE
DPDM	MULTIFUNCTION METER WITH 3Ø DISPLAY OF CURRENT, VOLTAGE, PF RECORDING & MAXIMUM DEMAND RECORDING
R	REFERENCE VOLTAGE
TC1	TRIP CIRCUIT-1
TC2	TRIP CIRCUIT-2
TFR	TRANSIENT FAULT RECORDER
CICT	CURRENT ISOLATING CT

REFERENCE DRAWINGS

DRAWING TITLE	DRAWING NO.
DRAWING CONTROL SHEET	EE-221387
SCOPE OF WORK & TECHNICAL SPECIFICATIONS	PTS-11EN146
MAIN SWITCHING ONE LINE DIAGRAM	EA-221478
	-
	-
	-

CONTRACTOR'S CONSULTANT:

DAR ENGINEERING  **الدار الدولية للمهندسين**

ENGINEERS & DESIGNERS

P.O. BOX 13103
DAMMAM-31493

ص.ب. 13103
الدمام 31493

AS-BUILT

REV. NO.	DATE	BY	DESCRIPTION	CHKD.	CERT.	APPD.
0	03.2013	DAR	ISSUED FOR CONSTRUCTION	M.Z.K	O.B	A.Y.Y
B	11.2012	DAR	ISSUED FOR DETAIL DESIGN	M.Z.K	O.B	A.Y.Y
A	05.2012	DAR	FIRST ISSUE	M.Z.K	O.B	A.Y.Y

DRAWING COMPLETION CERTIFICATE (DCC) :

الشركة الوطنية لنقل الكهرباء  **نقل الكهرباء**

National Grid

DRAWN BY: G.MUSTAFA CHECKED BY: OSAMA/ZAHID SCALE: N.T.S

DATE STARTED: 08.05.2012 DATE COMPLETED: _____

PRG. DEPT. _____ ENG. DEPT. _____

THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION OR FOR ORDERING MATERIAL UNTIL CERTIFIED AND DATED BY _____ DATE _____



CERTIFIED

RELAYING AND METERING ONE LINE DIAGRAM



13.8kV SYSTEM

QATIF 115/13.8kV SUBSTATION NO. 2

QATIF SAUDI ARABIA



THIS DRAWING AND THE INFORMATION CONTAINED HEREIN ARE THE SOLE PROPERTY OF National Grid SA. NO REPRODUCTION IN FULL OR IN PART SHALL BE OBTAINED FROM THIS DOCUMENT WITHOUT THE WRITTEN CONSENT OF ITS OWNER.



NOTES

1. DRAWING NOTE

FUNCTION	DESCRIPTION	EOP	TYPE	MAKE
59-1	OVER VOLTAGE RELAY STAGE-1	59-1	PI42	ALSTOM
59-2	OVER VOLTAGE RELAY STAGE-2	59-2	PI42	ALSTOM
27	UNDER VOLTAGE RELAY	27	PI42	ALSTOM
2/27	TIMER FOR UNDER VOLTAGE RELAY	2/27		
50PA	NON DIRECTIONAL O/C PROTIN. FOR PHASE-A	50PA		
50PB	NON DIRECTIONAL O/C PROTIN. FOR PHASE-B	50PB		
50PC	NON DIRECTIONAL O/C PROTIN. FOR PHASE-C	50PC		
50PN	NON DIRECTIONAL E/F PROTIN.	50PN		
50/51	NON DIRECTIONAL O/C & E/F PROTIN.	50/51	PI42	ALSTOM
46-1 & 46-2	NEUTRAL UNBALANCE OVERCURRENT RELAY	46-1 & 46-2	PI42	ALSTOM
74	SUPERVISION RELAY FOR TRIP RELAY	74/94	SPERIC	ABB
86	PROTN. TRIP LOCKOUT RELAY	86	LOR/HR	ES
94	PROTN. TRIP RELAY	94	LOR/SR	ES
98	VT FUSE FAILURE SUPERVISION RELAY	98-FFR	RXBA4	ABB
BCU	BAY CONTROL UNIT WITH CURRENT, VOLTAGE, WATT, VAR MEASUREMENTS	BCU-B313, BCU-B343, BCU-B362	REF615	ABB

ABBREVIATIONS:

- M MEASURING VOLTAGE
- R REFERENCE VOLTAGE
- TC1 TRIP CIRCUIT-1
- TC2 TRIP CIRCUIT-2
- HMI HUMAN MACHINE INTERFACE
- ES ETHERNET SWITCH
- SAS SUBSTATION AUTOMATION SYSTEM
- 3RA313 CAPACITOR BANK-1 SET-1 PROTIN. PANEL
- 3RB313 CAPACITOR BANK-1 SET-2 PROTIN. PANEL
- 3RA343 CAPACITOR BANK-2 SET-1 PROTIN. PANEL
- 3RB343 CAPACITOR BANK-2 SET-2 PROTIN. PANEL
- 3RA362 CAPACITOR BANK-3 SET-1 PROTIN. PANEL
- 3RB362 CAPACITOR BANK-3 SET-2 PROTIN. PANEL
- DPDM MULTIFUNCTION METER WITH 3Ø DISPLAY OF CURRENT, VOLTAGE, PF RECORDING & MAXIMUM DEMAND RECORDING

REFERENCE DRAWINGS

DRAWING TITLE	DRAWING NO.
DRAWING CONTROL SHEET	EE-221387
SCOPE OF WORK & TECHNICAL SPECIFICATIONS	PTS-11EN146
MAIN SWITCHING ONE LINE DIAGRAM	EA-221470
	-
	-
	-

CONTRACTOR'S CONSULTANT:

DAR ENGINEERING **الدار الدولية للهندسة**
 ENGINEERS & DESIGNERS **مهندسون ومصممون**
 P.O. BOX 31303 **1313**
 DAMMAM-31493 **الدمام**

AS-BUILT BY _____ DATE _____

REV. NO.	DATE	BY	DESCRIPTION	CHKD.	CERT.	APPD.
0	03.2013	DAR	ISSUED FOR CONSTRUCTION	M.Z.K	O.B	A.Y.Y
B	11.2012	DAR	ISSUED FOR DETAIL DESIGN	M.Z.K	O.B	A.Y.Y
A	05.2012	DAR	FIRST ISSUE	M.Z.K	O.B	A.Y.Y

DRAWING COMPLETION CERTIFICATE (DCC):

الشركة الوطنية لنقل الكهرباء **نقل الكهرباء**
National Grid SA

DRAWN BY G.MUSTAFA CHECKED BY OSAMA/ZAHID SCALE: N.T.S
 DATE STARTED 08.05.2012 DATE COMPLETED _____
 PRG. DEPT. _____ ENG. DEPT. _____

THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION OR FOR ORDERING MATERIAL UNTIL CERTIFIED AND DATED BY _____ DATE _____

CERTIFIED BY _____ DATE _____


RELAYING AND METERING ONE LINE DIAGRAM
13.8kV CAPACITOR BANK
QATIF 115/13.8kV SUBSTATION NO. 2
QATIF SAUDI ARABIA

THIS DRAWING AND THE INFORMATION CONTAINED HEREIN ARE THE SOLE PROPERTY OF National Grid SA NO REPRODUCTION IN FULL OR IN PART SHALL BE OBTAINED FROM THIS DOCUMENT WITHOUT THE WRITTEN CONSENT OF ITS OWNER.


ANNEXURE-B

(ETAP result and co-ordination graph)


One-Line Diagram - OLV1 (Short-Circuit Analysis)



One-Line Diagram - OLV1 (Short-Circuit Analysis)



Amps X 10 Bus1 (Nom. kV=13.8, Plot Ref. kV=13.8)




ETAP Star 11.0.0C

13.8KV PHASE FAULT CURVE

Project:
 Location:
 Contract:
 Engineer:
 Filename: E:\DG298\RELAY SETTINGS\REV.0\QATIF 2 SS\QATIF 2 SS.OTI

Date: 10-23-2013
 SN: DAR-ENGING
 Rev: Base
 Fault: Phase

Amps X 10 Bus14 (Nom. kV=13.8, Plot Ref. kV=13.8)



Amps X 10 Bus14 (Nom. kV=13.8, Plot Ref. kV=13.8)


ETAP Star 11.0.0C

13.8KV EARTH FAULT CURVE

Project:
 Location:
 Contract:
 Engineer:
 Filename: E:\DG298\RELAY SETTINGS\REV.0\QATIF 2 SS\QATIF 2 SS.OTI

Date: 10-23-2013
 SN: DAR-ENGINE
 Rev: Base
 Fault: Ground

Amps X 100 Bus6 (Nom. kV=115, Plot Ref. kV=115)




ETAP Star 11.0.0C

115KV PHASE FAULT CURVE

Project:
 Location:
 Contract:
 Engineer:
 Filename: E:\DG298\RELAY SETTINGS\REV.0\QATIF 2 SS\QATIF 2 SS.OTI

Date: 10-23-2013
 SN: DAR-ENGING
 Rev: Base
 Fault: Phase

Amps X 10 Bus6 (Nom. kV=115, Plot Ref. kV=115)



Amps X 10 Bus6 (Nom. kV=115, Plot Ref. kV=115)

ETAP Star 11.0.0C

115KV EARTH FAULT CURVE

Project:
 Location:
 Contract:
 Engineer:
 Filename: E:\DG298\RELAY SETTINGS\REV.0\QATIF 2 SS\QATIF 2 SS.OTI

Date: 10-23-2013
 SN: DAR-ENGING
 Rev: Base
 Fault: Ground

Project:
Location:
Contract:
Engineer:
Filename: QATIF 2 SS

ETAP
11.0.0C
Study Case: SC

Page: 1
Date: 10-23-2013
SN: DAR-ENGING
Revision: Base
Config.: Normal

Electrical Transient Analyzer Program

Short-Circuit Analysis

**ANSI Standard
3-Phase, LG, LL, & LLG Fault Currents
30-Cycle Network**

	<u>Swing</u>	<u>V-Control</u>	<u>Load</u>	<u>Total</u>
Number of Buses:	1	0	18	19

	<u>XFMR2</u>	<u>XFMR3</u>	<u>Reactor</u>	<u>Line/Cable</u>	<u>Impedance</u>	<u>Tie PD</u>	<u>Total</u>
Number of Branches:	4	0	0	1	0	19	24

	<u>Synchronous Generator</u>	<u>Power Grid</u>	<u>Synchronous Motor</u>	<u>Induction Machines</u>	<u>Lumped Load</u>	<u>Total</u>
Number of Machines:	0	1	0	0	0	1

System Frequency: 60.00 Hz

Unit System: English

Project Filename: QATIF 2 SS

Output Filename: E:\DG298\RELAY SETTINGS\REV.0\QATIF 2 SS\Untitled.SA2

Project:
Location:
Contract:
Engineer:
Filename: QATIF 2 SS

ETAP
11.0.0C

Study Case: SC

Page: 2
Date: 10-23-2013
SN: DAR-ENGING
Revision: Base
Config.: Normal

Adjustments

<u>Tolerance</u>	<u>Apply Adjustments</u>	<u>Individual /Global</u>	<u>Percent</u>
Transformer Impedance:	Yes	Individual	
Reactor Impedance:	Yes	Individual	
Overload Heater Resistance:	No		
Transmission Line Length:	No		
Cable Length:	No		

<u>Temperature Correction</u>	<u>Apply Adjustments</u>	<u>Individual /Global</u>	<u>Degree C</u>
Transmission Line Resistance:	Yes	Individual	
Cable Resistance:	Yes	Individual	

Project:
Location:
Contract:
Engineer:
Filename: QATIF 2 SS

ETAP
11.0.0C

Study Case: SC

Page: 3
Date: 10-23-2013
SN: DAR-ENGINE
Revision: Base
Config.: Normal

Bus Input Data

Bus					Initial Voltage	
ID	Type	Nom. kV	Base kV	Sub-sys	%Mag.	Ang.
Bus1	Load	13.800	13.800	1	100.00	-30.00
Bus1A	Load	115.000	115.000	1	100.00	0.00
Bus1B	Load	115.000	115.000	1	100.00	0.00
Bus2	Load	13.800	13.800	1	100.00	-30.00
Bus2A	Load	115.000	115.000	1	100.00	0.00
Bus2B	Load	115.000	115.000	1	100.00	0.00
Bus3	Load	13.800	13.800	1	100.00	-30.00
Bus5	SWNG	115.000	115.000	1	100.00	0.00
Bus6	Load	115.000	115.000	1	100.00	0.00
Bus7	Load	115.000	115.000	1	100.00	0.00
Bus8	Load	115.000	115.000	1	100.00	0.00
Bus9	Load	115.000	115.000	1	100.00	0.00
Bus11	Load	115.000	115.000	1	100.00	0.00
Bus13	Load	115.000	115.000	1	100.00	0.00
Bus14	Load	13.800	13.800	1	100.00	-30.00
Bus15	Load	13.800	13.800	1	100.00	-30.00
Bus16	Load	13.800	13.800	1	100.00	-30.00
Bus20	Load	0.380	0.380	1	100.00	0.00
Bus21	Load	13.800	13.800	1	100.00	-30.00

19 Buses Total

All voltages reported by ETAP are in % of bus Nominal kV.
Base kV values of buses are calculated and used internally by ETAP.

Project:
Location:
Contract:
Engineer:
Filename: QATIF 2 SS

ETAP
11.0.0C

Study Case: SC

Page: 4
Date: 10-23-2013
SN: DAR-ENGING
Revision: Base
Config.: Normal

Line/Cable Input Data

Ohms or Siemens per 1000 ft per Conductor (Cable) or per Phase (Line)

Line/Cable	ID	Library	Size	Length		#/Phase	T (°C)	R1	X1	Y1	R0	X0	Y0
				Adj. (ft)	% Tol.								
Cable1		15NCUS3	400	16404.2	0.0	1	75	0.0187508	0.0310896		0.0298124	0.0789676	

Line / Cable resistances are listed at the specified temperatures.

Project:
 Location:
 Contract:
 Engineer:
 Filename: QATIF 2 SS

ETAP
 11.0.0C

Study Case: SC

Page: 5
 Date: 10-23-2013
 SN: DAR-ENGING
 Revision: Base
 Config.: Normal

2-Winding Transformer Input Data

Transformer ID	Rating					Z Variation			% Tap Setting		Adjusted	Phase Shift	
	MVA	Prim. kV	Sec. kV	% Z	X/R	+ 5%	- 5%	% Tol.	Prim.	Sec.	% Z	Type	Angle
T302	0.500	13.800	0.380	5.00	3.09	0	0	0	0	0	5.0000	Dyn	-30.000
T601	67.000	115.000	13.800	29.00	50.40	0	0	0	0	0	29.0000	Dyn	30.000
T602	67.000	115.000	13.800	29.00	50.40	0	0	0	0	0	29.0000	Dyn	30.000
T603	67.000	115.000	13.800	29.00	50.40	0	0	0	0	0	29.0000	Dyn	30.000

2-Winding Transformer Grounding Input Data

Transformer ID	Rating			Grounding									
	MVA	Prim. kV	Sec. kV	Conn.	Primary			Secondary					
ID	MVA	Prim. kV	Sec. kV	Type	Type	kV	Amp	Ohm	Type	kV	Amp	Ohm	
T302	0.500	13.800	0.380	D/Y					Solid				
T601	67.000	115.000	13.800	D/Y					Solid				
T602	67.000	115.000	13.800	D/Y					Solid				
T603	67.000	115.000	13.800	D/Y					Solid				

Project:
 Location:
 Contract:
 Engineer:
 Filename: QATIF 2 SS

ETAP
 11.0.0C
 Study Case: SC

Page: 6
 Date: 10-23-2013
 SN: DAR-ENGING
 Revision: Base
 Config.: Normal

Branch Connections

CKT/Branch		Connected Bus ID		% Impedance, Pos. Seq., 100 MVAb			
ID	Type	From Bus	To Bus	R	X	Z	Y
T302	2W XFMR	Bus2	Bus20	307.90	951.42	1000.00	
T601	2W XFMR	Bus9	Bus14	0.86	43.28	43.28	
T602	2W XFMR	Bus11	Bus15	0.86	43.28	43.28	
T603	2W XFMR	Bus13	Bus16	0.86	43.28	43.28	
Cable1	Cable	Bus1	Bus21	16.15	26.78	31.27	
A301	Tie Breakr	Bus14	Bus1				
A302	Tie Breakr	Bus15	Bus2				
A303	Tie Breakr	Bus16	Bus3				
A304	Tie Breakr	Bus2	Bus1				
A601	Tie Breakr	Bus1B	Bus1A				
A602	Tie Breakr	Bus1B	Bus2B				
A603	Tie Breakr	Bus1A	Bus2A				
A604	Tie Breakr	Bus8	Bus13				
A605	Tie Breakr	Bus7	Bus11				
A607	Tie Breakr	Bus6	Bus9				
SW1	Tie Switch	Bus5	Bus1A				
SW2	Tie Switch	Bus5	Bus2A				
SW3	Tie Switch	Bus2B	Bus2A				
SW4	Tie Switch	Bus2A	Bus6				
SW5	Tie Switch	Bus1A	Bus6				
SW6	Tie Switch	Bus2A	Bus7				
SW7	Tie Switch	Bus1A	Bus7				
SW8	Tie Switch	Bus2B	Bus8				
SW9	Tie Switch	Bus1B	Bus8				

Project:
 Location:
 Contract:
 Engineer:
 Filename: QATIF 2 SS

ETAP
 11.0.0C

Study Case: SC

Page: 7
 Date: 10-23-2013
 SN: DAR-ENGING
 Revision: Base
 Config.: Normal

Power Grid Input Data

Power Grid	Connected Bus	Rating		% Positive Seq. Impedance 100 MVA Base			Grounding	% Zero Seq. Impedance 100 MVA Base		
		MVASC	kV	X/R	R	X		X/R	R0	X0
U1	Bus5	4899.972	115.000	15.60	0.13055	2.03665	Wye - Solid	8.30	0.436016	3.61893

Total Power Grids (= 1) 4899.972 MVA

Project:
 Location:
 Contract:
 Engineer:
 Filename: QATIF 2 SS

ETAP
 11.0.0C

Study Case: SC

Page: 8
 Date: 10-23-2013
 SN: DAR-ENGING
 Revision: Base
 Config.: Normal

SHORT-CIRCUIT REPORT

Fault at bus: **Bus1**

Prefault voltage = 13.800 kV = 100.00 % of nominal bus kV (13.800 kV)
 = 100.00 % of base kV (13.800 kV)

Contribution		3-Phase Fault		Line-To-Ground Fault					Positive & Zero Sequence Impedances Looking into "From Bus"			
From Bus ID	To Bus ID	% V From Bus	kA Symm. rms	% Voltage at From Bus			kA Symm. rms		% Impedance on 100 MVA base			
				Va	Vb	Vc	Ia	3I0	R1	X1	R0	X0
Bus1	Total	0.00	17.667	0.00	98.66	98.45	18.189	18.189	5.60E-001	2.37E+001	4.29E-001	2.16E+001
Bus21	Bus1	0.00	0.000	0.00	98.66	98.45	0.000	0.000				
Bus20	Bus2	0.00	0.000	56.96	100.00	56.84	0.000	0.000				
Bus11	Bus15	91.39	8.834	95.71	100.00	95.49	9.095	9.095 *	1.12E+000	4.73E+001	8.59E-001	4.33E+001
Bus9	Bus14	91.39	8.834	95.71	100.00	95.49	9.095	9.095 *	1.12E+000	4.73E+001	8.59E-001	4.33E+001

Indicates fault current contribution is from three-winding transformers

* Indicates a zero sequence fault current contribution (3I0) from a grounded Delta-Y transformer

Project:
 Location:
 Contract:
 Engineer:
 Filename: QATIF 2 SS

ETAP
 11.0.0C

Study Case: SC

Page: 9
 Date: 10-23-2013
 SN: DAR-ENGING
 Revision: Base
 Config.: Normal

Fault at bus: **Bus1A**

Prefault voltage = 115.000 kV
 = 100.00 % of nominal bus kV (115.000 kV)
 = 100.00 % of base kV (115.000 kV)

Contribution		3-Phase Fault		Line-To-Ground Fault					Positive & Zero Sequence Impedances Looking into "From Bus"			
From Bus ID	To Bus ID	% V From Bus	kA Symm. rms	% Voltage at From Bus			kA Symm. rms		% Impedance on 100 MVA base			
				Va	Vb	Vc	Ia	3I0	R1	X1	R0	X0
Bus1A	Total	0.00	24.600	0.00	110.22	113.46	19.500	19.500	1.31E-001	2.04E+000	4.36E-001	3.62E+000
Bus15	Bus11	0.00	0.000	65.51	63.64	100.00	0.000	0.000				
Bus14	Bus9	0.00	0.000	65.51	63.64	100.00	0.000	0.000				
U1	Bus5	100.00	24.600	100.00	100.00	100.00	19.500	19.500	1.31E-001	2.04E+000	4.36E-001	3.62E+000
Bus16	Bus13	0.00	0.000	65.51	63.64	100.00	0.000	0.000				

Indicates fault current contribution is from three-winding transformers

* Indicates a zero sequence fault current contribution (3I0) from a grounded Delta-Y transformer

Project:
 Location:
 Contract:
 Engineer:
 Filename: QATIF 2 SS

ETAP
 11.0.0C

Study Case: SC

Page: 10
 Date: 10-23-2013
 SN: DAR-ENGING
 Revision: Base
 Config.: Normal

Fault at bus: **Bus1B**

Prefault voltage = 115.000 kV
 = 100.00 % of nominal bus kV (115.000 kV)
 = 100.00 % of base kV (115.000 kV)

Contribution		3-Phase Fault		Line-To-Ground Fault					Positive & Zero Sequence Impedances Looking into "From Bus"			
From Bus ID	To Bus ID	% V From Bus	kA Symm. rms	% Voltage at From Bus			kA Symm. rms		% Impedance on 100 MVA base			
				Va	Vb	Vc	Ia	I0	R1	X1	R0	X0
Bus1B	Total	0.00	24.600	0.00	110.22	113.46	19.500	19.500	1.31E-001	2.04E+000	4.36E-001	3.62E+000
Bus16	Bus13	0.00	0.000	65.51	63.64	100.00	0.000	0.000				
Bus15	Bus11	0.00	0.000	65.51	63.64	100.00	0.000	0.000				
Bus14	Bus9	0.00	0.000	65.51	63.64	100.00	0.000	0.000				
U1	Bus5	100.00	24.600	100.00	100.00	100.00	19.500	19.500	1.31E-001	2.04E+000	4.36E-001	3.62E+000

Indicates fault current contribution is from three-winding transformers

* Indicates a zero sequence fault current contribution (I0) from a grounded Delta-Y transformer

Project:
 Location:
 Contract:
 Engineer:
 Filename: QATIF 2 SS

ETAP
 11.0.0C

Study Case: SC

Page: 11
 Date: 10-23-2013
 SN: DAR-ENGING
 Revision: Base
 Config.: Normal

Fault at bus: **Bus2**

Prefault voltage = 13.800 kV
 = 100.00 % of nominal bus kV (13.800 kV)
 = 100.00 % of base kV (13.800 kV)

Contribution		3-Phase Fault		Line-To-Ground Fault					Positive & Zero Sequence Impedances Looking into "From Bus"			
From Bus ID	To Bus ID	% V From Bus	kA Symm. rms	% Voltage at From Bus			kA Symm. rms		% Impedance on 100 MVA base			
				Va	Vb	Vc	Ia	I0	R1	X1	R0	X0
Bus2	Total	0.00	17.667	0.00	98.66	98.45	18.189	18.189	5.60E-001	2.37E+001	4.29E-001	2.16E+001
Bus20	Bus2	0.00	0.000	56.96	100.00	56.84	0.000	0.000				
Bus21	Bus1	0.00	0.000	0.00	98.66	98.45	0.000	0.000				
Bus9	Bus14	91.39	8.834	95.71	100.00	95.49	9.095	9.095 *	1.12E+000	4.73E+001	8.59E-001	4.33E+001
Bus11	Bus15	91.39	8.834	95.71	100.00	95.49	9.095	9.095 *	1.12E+000	4.73E+001	8.59E-001	4.33E+001

Indicates fault current contribution is from three-winding transformers

* Indicates a zero sequence fault current contribution (I0) from a grounded Delta-Y transformer

Project:
 Location:
 Contract:
 Engineer:
 Filename: QATIF 2 SS

ETAP
 11.0.0C

Study Case: SC

Page: 12
 Date: 10-23-2013
 SN: DAR-ENGING
 Revision: Base
 Config: Normal

Fault at bus: **Bus2A**

Prefault voltage = 115.000 kV
 = 100.00 % of nominal bus kV (115.000 kV)
 = 100.00 % of base kV (115.000 kV)

Contribution		3-Phase Fault		Line-To-Ground Fault					Positive & Zero Sequence Impedances Looking into "From Bus"			
From Bus ID	To Bus ID	% V From Bus	kA Symm. rms	% Voltage at From Bus			kA Symm. rms		% Impedance on 100 MVA base			
				Va	Vb	Vc	Ia	I0	R1	X1	R0	X0
Bus2A	Total	0.00	24.600	0.00	110.22	113.46	19.500	19.500	1.31E-001	2.04E+000	4.36E-001	3.62E+000
Bus15	Bus11	0.00	0.000	65.51	63.64	100.00	0.000	0.000				
Bus14	Bus9	0.00	0.000	65.51	63.64	100.00	0.000	0.000				
Bus16	Bus13	0.00	0.000	65.51	63.64	100.00	0.000	0.000				
U1	Bus5	100.00	24.600	100.00	100.00	100.00	19.500	19.500	1.31E-001	2.04E+000	4.36E-001	3.62E+000

Indicates fault current contribution is from three-winding transformers

* Indicates a zero sequence fault current contribution (I0) from a grounded Delta-Y transformer

Project:
 Location:
 Contract:
 Engineer:
 Filename: QATIF 2 SS

ETAP
 11.0.0C

Study Case: SC

Page: 13
 Date: 10-23-2013
 SN: DAR-ENGING
 Revision: Base
 Config.: Normal

Fault at bus: **Bus2B**

Prefault voltage = 115.000 kV
 = 100.00 % of nominal bus kV (115.000 kV)
 = 100.00 % of base kV (115.000 kV)

Contribution		3-Phase Fault		Line-To-Ground Fault					Positive & Zero Sequence Impedances Looking into "From Bus"			
From Bus ID	To Bus ID	% V From Bus	kA Symm. rms	% Voltage at From Bus			kA Symm. rms		% Impedance on 100 MVA base			
				Va	Vb	Vc	Ia	I0	R1	X1	R0	X0
Bus2B	Total	0.00	24.600	0.00	110.22	113.46	19.500	19.500	1.31E-001	2.04E+000	4.36E-001	3.62E+000
Bus16	Bus13	0.00	0.000	65.51	63.64	100.00	0.000	0.000				
Bus15	Bus11	0.00	0.000	65.51	63.64	100.00	0.000	0.000				
Bus14	Bus9	0.00	0.000	65.51	63.64	100.00	0.000	0.000				
U1	Bus5	100.00	24.600	100.00	100.00	100.00	19.500	19.500	1.31E-001	2.04E+000	4.36E-001	3.62E+000

Indicates fault current contribution is from three-winding transformers

* Indicates a zero sequence fault current contribution (I0) from a grounded Delta-Y transformer

Project:
 Location:
 Contract:
 Engineer:
 Filename: QATIF 2 SS

ETAP
 11.0.0C

Study Case: SC

Page: 14
 Date: 10-23-2013
 SN: DAR-ENGING
 Revision: Base
 Config.: Normal

Fault at bus: **Bus3**

Prefault voltage = 13.800 kV
 = 100.00 % of nominal bus kV (13.800 kV)
 = 100.00 % of base kV (13.800 kV)

Contribution		3-Phase Fault		Line-To-Ground Fault					Positive & Zero Sequence Impedances Looking into "From Bus"			
From Bus ID	To Bus ID	% V From Bus	kA Symm. rms	% Voltage at From Bus			kA Symm. rms		% Impedance on 100 MVA base			
				Va	Vb	Vc	Ia	3I0	R1	X1	R0	X0
Bus3	Total	0.00	9.231	0.00	99.30	99.19	9.371	9.371	9.89E-001	4.53E+001	8.59E-001	4.33E+001
Bus13	Bus16	95.50	9.231	97.78	100.00	97.67	9.371	9.371 *	9.89E-001	4.53E+001	8.59E-001	4.33E+001

Indicates fault current contribution is from three-winding transformers

* Indicates a zero sequence fault current contribution (3I0) from a grounded Delta-Y transformer

Project:
 Location:
 Contract:
 Engineer:
 Filename: QATIF 2 SS

ETAP
 11.0.0C

Study Case: SC

Page: 15
 Date: 10-23-2013
 SN: DAR-ENGING
 Revision: Base
 Config.: Normal

Fault at bus: **Bus5**

Prefault voltage = 115.000 kV
 = 100.00 % of nominal bus kV (115.000 kV)
 = 100.00 % of base kV (115.000 kV)

Contribution		3-Phase Fault		Line-To-Ground Fault					Positive & Zero Sequence Impedances Looking into "From Bus"			
From Bus ID	To Bus ID	% V From Bus	kA Symm. rms	% Voltage at From Bus			kA Symm. rms		% Impedance on 100 MVA base			
				Va	Vb	Vc	Ia	I0	R1	X1	R0	X0
Bus5	Total	0.00	24.600	0.00	110.22	113.46	19.500	19.500	1.31E-001	2.04E+000	4.36E-001	3.62E+000
U1	Bus5	100.00	24.600	100.00	100.00	100.00	19.500	19.500	1.31E-001	2.04E+000	4.36E-001	3.62E+000
Bus15	Bus11	0.00	0.000	65.51	63.64	100.00	0.000	0.000				
Bus14	Bus9	0.00	0.000	65.51	63.64	100.00	0.000	0.000				
Bus16	Bus13	0.00	0.000	65.51	63.64	100.00	0.000	0.000				

Indicates fault current contribution is from three-winding transformers

* Indicates a zero sequence fault current contribution (I0) from a grounded Delta-Y transformer

Project:
 Location:
 Contract:
 Engineer:
 Filename: QATIF 2 SS

ETAP
 11.0.0C

Study Case: SC

Page: 16
 Date: 10-23-2013
 SN: DAR-ENGING
 Revision: Base
 Config.: Normal

Fault at bus: **Bus9**

Prefault voltage = 115.000 kV
 = 100.00 % of nominal bus kV (115.000 kV)
 = 100.00 % of base kV (115.000 kV)

Contribution		3-Phase Fault		Line-To-Ground Fault					Positive & Zero Sequence Impedances Looking into "From Bus"			
From Bus ID	To Bus ID	% V From Bus	kA Symm. rms	% Voltage at From Bus			kA Symm. rms		% Impedance on 100 MVA base			
				Va	Vb	Vc	Ia	3I0	R1	X1	R0	X0
Bus9	Total	0.00	24.600	0.00	110.22	113.46	19.500	19.500	1.31E-001	2.04E+000	4.36E-001	3.62E+000
Bus14	Bus9	0.00	0.000	65.51	63.64	100.00	0.000	0.000				
Bus15	Bus11	0.00	0.000	65.51	63.64	100.00	0.000	0.000				
U1	Bus5	100.00	24.600	100.00	100.00	100.00	19.500	19.500	1.31E-001	2.04E+000	4.36E-001	3.62E+000
Bus16	Bus13	0.00	0.000	65.51	63.64	100.00	0.000	0.000				

Indicates fault current contribution is from three-winding transformers

* Indicates a zero sequence fault current contribution (3I0) from a grounded Delta-Y transformer

Project:
 Location:
 Contract:
 Engineer:
 Filename: QATIF 2 SS

ETAP
 11.0.0C

Study Case: SC

Page: 17
 Date: 10-23-2013
 SN: DAR-ENGING
 Revision: Base
 Config.: Normal

Fault at bus: **Bus11**

Prefault voltage = 115.000 kV
 = 100.00 % of nominal bus kV (115.000 kV)
 = 100.00 % of base kV (115.000 kV)

Contribution		3-Phase Fault		Line-To-Ground Fault					Positive & Zero Sequence Impedances Looking into "From Bus"			
From Bus ID	To Bus ID	% V From Bus	kA Symm. rms	% Voltage at From Bus			kA Symm. rms		% Impedance on 100 MVA base			
				Va	Vb	Vc	Ia	I0	R1	X1	R0	X0
Bus11	Total	0.00	24.600	0.00	110.22	113.46	19.500	19.500	1.31E-001	2.04E+000	4.36E-001	3.62E+000
Bus15	Bus11	0.00	0.000	65.51	63.64	100.00	0.000	0.000				
Bus14	Bus9	0.00	0.000	65.51	63.64	100.00	0.000	0.000				
U1	Bus5	100.00	24.600	100.00	100.00	100.00	19.500	19.500	1.31E-001	2.04E+000	4.36E-001	3.62E+000
Bus16	Bus13	0.00	0.000	65.51	63.64	100.00	0.000	0.000				

Indicates fault current contribution is from three-winding transformers

* Indicates a zero sequence fault current contribution (I0) from a grounded Delta-Y transformer

Project:
 Location:
 Contract:
 Engineer:
 Filename: QATIF 2 SS

ETAP
 11.0.0C

Study Case: SC

Page: 18
 Date: 10-23-2013
 SN: DAR-ENGING
 Revision: Base
 Config.: Normal

Fault at bus: **Bus13**

Prefault voltage = 115.000 kV
 = 100.00 % of nominal bus kV (115.000 kV)
 = 100.00 % of base kV (115.000 kV)

Contribution		3-Phase Fault		Line-To-Ground Fault					Positive & Zero Sequence Impedances Looking into "From Bus"			
From Bus ID	To Bus ID	% V From Bus	kA Symm. rms	% Voltage at From Bus			kA Symm. rms		% Impedance on 100 MVA base			
				Va	Vb	Vc	Ia	I0	R1	X1	R0	X0
Bus13	Total	0.00	24.600	0.00	110.22	113.46	19.500	19.500	1.31E-001	2.04E+000	4.36E-001	3.62E+000
Bus16	Bus13	0.00	0.000	65.51	63.64	100.00	0.000	0.000				
Bus15	Bus11	0.00	0.000	65.51	63.64	100.00	0.000	0.000				
Bus14	Bus9	0.00	0.000	65.51	63.64	100.00	0.000	0.000				
U1	Bus5	100.00	24.600	100.00	100.00	100.00	19.500	19.500	1.31E-001	2.04E+000	4.36E-001	3.62E+000

Indicates fault current contribution is from three-winding transformers

* Indicates a zero sequence fault current contribution (I0) from a grounded Delta-Y transformer

Project:
 Location:
 Contract:
 Engineer:
 Filename: QATIF 2 SS

ETAP
 11.0.0C

Study Case: SC

Page: 19
 Date: 10-23-2013
 SN: DAR-ENGING
 Revision: Base
 Config.: Normal

Fault at bus: **Bus14**

Prefault voltage = 13.800 kV
 = 100.00 % of nominal bus kV (13.800 kV)
 = 100.00 % of base kV (13.800 kV)

Contribution		3-Phase Fault		Line-To-Ground Fault					Positive & Zero Sequence Impedances Looking into "From Bus"			
From Bus ID	To Bus ID	% V From Bus	kA Symm. rms	% Voltage at From Bus			kA Symm. rms		% Impedance on 100 MVA base			
				Va	Vb	Vc	Ia	I0	R1	X1	R0	X0
Bus14	Total	0.00	17.667	0.00	98.66	98.45	18.189	18.189	5.60E-001	2.37E+001	4.29E-001	2.16E+001
Bus9	Bus14	91.39	8.834	95.71	100.00	95.49	9.095	9.095 *	1.12E+000	4.73E+001	8.59E-001	4.33E+001
Bus21	Bus1	0.00	0.000	0.00	98.66	98.45	0.000	0.000				
Bus20	Bus2	0.00	0.000	56.96	100.00	56.84	0.000	0.000				
Bus11	Bus15	91.39	8.834	95.71	100.00	95.49	9.095	9.095 *	1.12E+000	4.73E+001	8.59E-001	4.33E+001

Indicates fault current contribution is from three-winding transformers

* Indicates a zero sequence fault current contribution (I0) from a grounded Delta-Y transformer

Project:
 Location:
 Contract:
 Engineer:
 Filename: QATIF 2 SS

ETAP
 11.0.0C

Study Case: SC

Page: 20
 Date: 10-23-2013
 SN: DAR-ENGING
 Revision: Base
 Config.: Normal

Fault at bus: **Bus15**

Prefault voltage = 13.800 kV
 = 100.00 % of nominal bus kV (13.800 kV)
 = 100.00 % of base kV (13.800 kV)

Contribution		3-Phase Fault		Line-To-Ground Fault					Positive & Zero Sequence Impedances Looking into "From Bus"			
From Bus ID	To Bus ID	% V From Bus	kA Symm. rms	% Voltage at From Bus			kA Symm. rms		% Impedance on 100 MVA base			
				Va	Vb	Vc	Ia	I0	R1	X1	R0	X0
Bus15	Total	0.00	17.667	0.00	98.66	98.45	18.189	18.189	5.60E-001	2.37E+001	4.29E-001	2.16E+001
Bus11	Bus15	91.39	8.834	95.71	100.00	95.49	9.095	9.095 *	1.12E+000	4.73E+001	8.59E-001	4.33E+001
Bus20	Bus2	0.00	0.000	56.96	100.00	56.84	0.000	0.000				
Bus21	Bus1	0.00	0.000	0.00	98.66	98.45	0.000	0.000				
Bus9	Bus14	91.39	8.834	95.71	100.00	95.49	9.095	9.095 *	1.12E+000	4.73E+001	8.59E-001	4.33E+001

Indicates fault current contribution is from three-winding transformers

* Indicates a zero sequence fault current contribution (I0) from a grounded Delta-Y transformer

Project:
 Location:
 Contract:
 Engineer:
 Filename: QATIF 2 SS

ETAP
 11.0.0C

Study Case: SC

Page: 21
 Date: 10-23-2013
 SN: DAR-ENGING
 Revision: Base
 Config.: Normal

Fault at bus: **Bus16**

Prefault voltage = 13.800 kV
 = 100.00 % of nominal bus kV (13.800 kV)
 = 100.00 % of base kV (13.800 kV)

Contribution		3-Phase Fault		Line-To-Ground Fault					Positive & Zero Sequence Impedances Looking into "From Bus"			
From Bus ID	To Bus ID	% V From Bus	kA Symm. rms	% Voltage at From Bus			kA Symm. rms		% Impedance on 100 MVA base			
				Va	Vb	Vc	Ia	3I0	R1	X1	R0	X0
Bus16	Total	0.00	9.231	0.00	99.30	99.19	9.371	9.371	9.89E-001	4.53E+001	8.59E-001	4.33E+001
Bus13	Bus16	95.50	9.231	97.78	100.00	97.67	9.371	9.371 *	9.89E-001	4.53E+001	8.59E-001	4.33E+001

Indicates fault current contribution is from three-winding transformers

* Indicates a zero sequence fault current contribution (3I0) from a grounded Delta-Y transformer

Project:
 Location:
 Contract:
 Engineer:
 Filename: QATIF 2 SS

ETAP
 11.0.0C

Study Case: SC

Page: 22
 Date: 10-23-2013
 SN: DAR-ENGING
 Revision: Base
 Config.: Normal

Fault at bus: **Bus20**

Prefault voltage = 0.380 kV
 = 100.00 % of nominal bus kV (0.380 kV)
 = 100.00 % of base kV (0.380 kV)

Contribution		3-Phase Fault		Line-To-Ground Fault					Positive & Zero Sequence Impedances Looking into "From Bus"			
From Bus ID	To Bus ID	% V From Bus	kA Symm. rms	% Voltage at From Bus			kA Symm. rms		% Impedance on 100 MVA base			
				Va	Vb	Vc	Ia	3I0	R1	X1	R0	X0
Bus20	Total	0.00	14.856	0.00	99.44	99.82	14.967	14.967	3.08E+002	9.75E+002	3.08E+002	9.51E+002
Bus2	Bus20	97.78	14.856	99.07	98.69	100.00	14.967	14.967 *	3.08E+002	9.75E+002	3.08E+002	9.51E+002

Indicates fault current contribution is from three-winding transformers

* Indicates a zero sequence fault current contribution (3I0) from a grounded Delta- Y transformer

Project:
 Location:
 Contract:
 Engineer:
 Filename: QATIF 2 SS

ETAP
 11.0.0C

Study Case: SC

Page: 23
 Date: 10-23-2013
 SN: DAR-ENGING
 Revision: Base
 Config.: Normal

Fault at bus: **Bus21**

Prefault voltage = 13.800 kV
 = 100.00 % of nominal bus kV (13.800 kV)
 = 100.00 % of base kV (13.800 kV)

Contribution		3-Phase Fault		Line-To-Ground Fault					Positive & Zero Sequence Impedances Looking into "From Bus"			
From Bus ID	To Bus ID	% V From Bus	kA Symm. rms	% Voltage at From Bus			kA Symm. rms		% Impedance on 100 MVA base			
				Va	Vb	Vc	Ia	3I0	R1	X1	R0	X0
Bus21	Total	0.00	7.872	0.00	112.51	110.39	6.287	6.287	1.67E+001	5.05E+001	2.61E+001	8.97E+001
Bus1	Bus21	58.84	7.872	67.47	99.30	99.72	6.287	6.287	1.67E+001	5.05E+001	2.61E+001	8.97E+001

Indicates fault current contribution is from three-winding transformers

* Indicates a zero sequence fault current contribution (3I0) from a grounded Delta-Y transformer

Project:
 Location:
 Contract:
 Engineer:
 Filename: QATIF 2 SS

ETAP
 11.0.0C
 Study Case: SC

Page: 24
 Date: 10-23-2013
 SN: DAR-ENGING
 Revision: Base
 Config.: Normal

Short-Circuit Summary Report

30 Cycle - 3-Phase, LG, LL, & LLG Fault Currents

Prefault Voltage = 100 % of the Bus Nominal Voltage

Bus		3-Phase Fault			Line-to-Ground Fault			Line-to-Line Fault			*Line-to-Line-to-Ground		
ID	kV	Real	Imag.	Mag.	Real	Imag.	Mag.	Real	Imag.	Mag.	Real	Imag.	Mag.
Bus1	13.80	0.418	-17.662	17.667	0.408	-18.185	18.189	15.296	0.362	15.300	15.097	9.731	17.962
Bus1A	115.00	1.574	-24.550	24.600	1.760	-19.420	19.500	21.261	1.363	21.304	-22.128	6.663	23.110
Bus1B	115.00	1.574	-24.550	24.600	1.760	-19.420	19.500	21.261	1.363	21.304	-22.128	6.663	23.110
Bus2	13.80	0.418	-17.662	17.667	0.408	-18.185	18.189	15.296	0.362	15.300	15.097	9.731	17.962
Bus2A	115.00	1.574	-24.550	24.600	1.760	-19.420	19.500	21.261	1.363	21.304	-22.128	6.663	23.110
Bus2B	115.00	1.574	-24.550	24.600	1.760	-19.420	19.500	21.261	1.363	21.304	-22.128	6.663	23.110
Bus3	13.80	0.201	-9.229	9.231	0.199	-9.369	9.371	7.992	0.174	7.994	7.895	4.932	9.308
Bus5	115.00	1.574	-24.550	24.600	1.760	-19.420	19.500	21.261	1.363	21.304	-22.128	6.663	23.110
Bus9	115.00	1.574	-24.550	24.600	1.760	-19.420	19.500	21.261	1.363	21.304	-22.128	6.663	23.110
Bus11	115.00	1.574	-24.550	24.600	1.760	-19.420	19.500	21.261	1.363	21.304	-22.128	6.663	23.110
Bus13	115.00	1.574	-24.550	24.600	1.760	-19.420	19.500	21.261	1.363	21.304	-22.128	6.663	23.110
Bus14	13.80	0.418	-17.662	17.667	0.408	-18.185	18.189	15.296	0.362	15.300	15.097	9.731	17.962
Bus15	13.80	0.418	-17.662	17.667	0.408	-18.185	18.189	15.296	0.362	15.300	15.097	9.731	17.962
Bus16	13.80	0.201	-9.229	9.231	0.199	-9.369	9.371	7.992	0.174	7.994	7.895	4.932	9.308
Bus20	0.38	4.481	-14.164	14.856	4.545	-14.260	14.967	12.266	3.880	12.866	-14.572	3.298	14.940
Bus21	13.80	2.475	-7.472	7.872	1.875	-6.001	6.287	6.471	2.143	6.817	5.720	4.649	7.371

All fault currents are symmetrical momentary (30 Cycle network) values in rms kA

* LLG fault current is the larger of the two faulted line currents

Project:
 Location:
 Contract:
 Engineer:
 Filename: QATIF 2 SS

ETAP
 11.0.0C
 Study Case: SC

Page: 25
 Date: 10-23-2013
 SN: DAR-ENGING
 Revision: Base
 Config.: Normal

Short-Circuit Summary Report

Bus		Positive Sequence Imp. (ohm)			Negative Sequence Imp. (ohm)			Zero Sequence Imp. (ohm)		
ID	kV	Resistance	Reactance	Impedance	Resistance	Reactance	Impedance	Resistance	Reactance	Impedance
Bus1	13.800	0.01066	0.45085	0.45098	0.01066	0.45085	0.45098	0.00818	0.41207	0.41215
Bus1A	115.000	0.17266	2.69347	2.69899	0.17266	2.69347	2.69899	0.57663	4.78603	4.82065
Bus1B	115.000	0.17266	2.69347	2.69899	0.17266	2.69347	2.69899	0.57663	4.78603	4.82065
Bus2	13.800	0.01066	0.45085	0.45098	0.01066	0.45085	0.45098	0.00818	0.41207	0.41215
Bus2A	115.000	0.17266	2.69347	2.69899	0.17266	2.69347	2.69899	0.57663	4.78603	4.82065
Bus2B	115.000	0.17266	2.69347	2.69899	0.17266	2.69347	2.69899	0.57663	4.78603	4.82065
Bus3	13.800	0.01884	0.86292	0.86312	0.01884	0.86292	0.86312	0.01635	0.82413	0.82429
Bus5	115.000	0.17266	2.69347	2.69899	0.17266	2.69347	2.69899	0.57663	4.78603	4.82065
Bus9	115.000	0.17266	2.69347	2.69899	0.17266	2.69347	2.69899	0.57663	4.78603	4.82065
Bus11	115.000	0.17266	2.69347	2.69899	0.17266	2.69347	2.69899	0.57663	4.78603	4.82065
Bus13	115.000	0.17266	2.69347	2.69899	0.17266	2.69347	2.69899	0.57663	4.78603	4.82065
Bus14	13.800	0.01066	0.45085	0.45098	0.01066	0.45085	0.45098	0.00818	0.41207	0.41215
Bus15	13.800	0.01066	0.45085	0.45098	0.01066	0.45085	0.45098	0.00818	0.41207	0.41215
Bus16	13.800	0.01884	0.86292	0.86312	0.01884	0.86292	0.86312	0.01635	0.82413	0.82429
Bus20	0.380	0.00445	0.01408	0.01477	0.00445	0.01408	0.01477	0.00445	0.01374	0.01444
Bus21	13.800	0.31825	0.96085	1.01219	0.31825	0.96085	1.01219	0.49722	1.70746	1.77839

ANNEXURE-C

(Relay ordering details)

LOCATION REF.	ITEM DESIGNATION	DESCRIPTION	QTY.	TYPE	MAKE	ORDERING INFORMATION
		115/13.8KV TRANSFORMER T601 SET-1 PROTECTION PANEL -6T1A1 CONSISTING OF THE FOLLOWING :	1	VSH 200	ABB	
U03.5001	74/CC-1	DC SUPERVISION RELAY WITH THE FOLLOWING CONTACTS : 1 NO - 3 NC DC VOLTAGE : 110/125 V DC OPERATION INDICATOR : SELF RESET	1	MVAX 12	AREVA	MVAX12 RIC00757A
U03.5002	74/TC-1//A607	TRIP CIRCUIT-1 SUPERVISION RELAY-A607 AUXILIARY VOLTAGE : 110 /125V DC NO. OF CONTACTS : 1NO - 2NC OPERATION INDICATOR : HAND RESET	1	MVAX31	AREVA	MVAX31S1DE0754A
C	R1 R2,R3	1.5K OHMS EXTERNAL RESISTOR FOR TRIP CKT. SUPERVISION RELAY 4.0K OHMS EXTERNAL RESISTOR FOR TRIP CKT. SUPERVISION RELAY	1 2		AREVA	
U08.5001	87T	TRANSFORMER DIFFERENTIAL PROTECTION RELAY RATED CURRENT : 1A AUX. SUPPLY : 90-250V DC RATED FREQUENCY : 50/60HZ	1	RET670 VER.1.2	ABB	RET670-1.2-240X00-D02-D04 P01-01-C-B-K-B-B-B-DAWE
U15.113	74/86T-1	SUPERVISION RELAY FOR TRIP RELAY DC VOLTAGE : 40-265V DC CONTACTS : 2 C/O	1	SPERIC1	ABB	RS 485 002-AA
U15.5001	87REF	RESTRICTED EARTH FAULT RELAY FOR HV WINDING RATED CURRENT : 1A CONTACTS : 2 NO RATED FREQUENCY : 60HZ SETTING VOLTAGE : 5-40 % OF IN STAB.RESISTOR : 1000 OHMS OPERATION INDICATOR : HAND RESET	1	MCAG 14	AREVA	MCAG14 SS DB 0220A
U20.5001	86T-1	HAND RESET LOCKOUT TRIP RELAY FOR SET-1 PROT. WITH THE FOLLOWING: RATED VOLTAGE : 125V DC NO. OF DECKS : 10 NO. OF CONTACTS : 20 NO - 20NC OPERATING COIL TYPE : F	1	LOR H/R	ELECTRO SWITCH	7010 F
U33.5001 U33.5002 U33.5003	TS-1 TS-2 TS-3	FLEXI TEST SWITCH WITH 8C-2P FOR 87T CT ISOLATION FLEXI TEST SWITCH WITH 8C-2P FOR 87T CT ISOLATION FLEXI TEST SWITCH WITH 10C FOR 87REF CT ISOLATION	1	FT-19R	ABB	FR20 083 083 073
U36.5001 U36.5002 U36.5003	TS-4 TS-5 TS-6	FLEXI TEST SWITCH WITH 8C-2P FOR 87REF CT ISOLATION FLEXI TEST SWITCH WITH 2P-2T-6P FOR TRIP ISOLATION FLEXI TEST SWITCH WITH 10P FOR TRIP ISOLATION	1	FT-19R	ABB	FR2G 083 819 001
	B1.1	NON LINEAR RESISTOR FOR (87REF)	1	METROSIL	AREVA	
	SR1	STABILISING RESISTOR FOR MCAG14 RELAY	1		AREVA	
U39.5001	F1	6A MCB FOR DC AUX SUPPLY	1	STOTZ	ABB	S202-UC-K6
U39.5002	CD1,CD2	POWER SOCKET DUPLEX TYPE. 127 & 220V AC	1	US M45 & US M545	LEGRAND	74140 & 74180
U39.5003	TJ	TELEPHONE JACK	1	EDF 410	EDISON ELECTRIC	EDF 410
	LK1-LK3	NEUTRAL ISOLATION LINK	3	RS20	AREVA	
	C1	2 POLE 20AMP MCB RATED 127V FOR INCOMING AC AUX. SUPPLY	1	S202P-K20	ABB	S202P-K20
	C2	2 POLE 20AMP MCB RATED 220V FOR INCOMING AC AUX. SUPPLY	1	S202P-K20	ABB	S202P-K20
	SW	TOGGLE SWITCH FOR SPACE HEATER	1	MCB-10 M2551-100	ABB	1SFA 611 605 R1101 1SFA 611 200 R1006
	TH	THERMOSTAT FOR SPACE HEATER	1	SK3110	RITTAL	SK3110
	SH	SPACE HEATER-150W, 120V, 60HZ	1	1FZEK7500104	COMPOTECH	
	DS	ODOR SWITCH FOR CUBICLE ILLUMINATION LAMP WITH 2NC CONTACTS	1	LS30P	ABB	1SBV010213R1202
	IL	FLUORESCENT LAMP, 127V AC	1	T-4 SP-20W	AMHORN INT'L GROUP LTD.	
	1X1S,2X1S,3X1S,4X1S	TERMINAL BLOCK FOR CT CKT (6WAYS BLOCK)	4	EB27	GE	0790462
	1X3	TERMINAL BLOCK FOR AUX. DC CKT	10	M10/10_RS	ENTRELEC	1SNA 115 320 R2700
	1X3.1	TERMINAL BLOCK FOR AUX. AC CKT	10	M10/10_RS	ENTRELEC	1SNA 115 320 R2700
	1X41	TERMINAL BLOCK FOR TRIP CIRCUIT-1	15	M10/10_RS	ENTRELEC	1SNA 115 320 R2700
	1X43	TERMINAL BLOCK FOR INITIATION CKT	10	M10/10_RS	ENTRELEC	1SNA 115 320 R2700
	1X45	TERMINAL BLOCK FOR CLOSING CKT	10	M10/10_RS	ENTRELEC	1SNA 115 320 R2700
	1X46	TERMINAL BLOCK FOR SPARE CONTACTS	50	M10/10_RS	ENTRELEC	1SNA 115 320 R2700
	1X6	TERMINAL BLOCK FOR ALARM CIRCUIT	10	M6/0_RS	ENTRELEC	115.685.12
	1X82	TERMINAL BLOCK FOR TRIP CIRCUIT	5	M6/0_RS	ENTRELEC	115.685.12
	1X5H	TERMINAL BLOCK FOR SPACE HEATER	2	M10/10_RS	ENTRELEC	1SNA 115 320 R2700
	1XTJ	TERMINAL BLOCK FOR TEL. JACK	5	M10/10_RS	ENTRELEC	1SNA 115 320 R2700
	CICT-A,B,C,N	CURRENT ISOLATION CURRENT TRANSFORMER	4	CICT	AMETEK	

REFERENCE DRAWINGS

DRAWING TITLE	DRAWING NO.
DRAWING CONTROL SHEET	EE-221307
RELAYING AND METERING ONE LINE DIAGRAM	EA-221504
AC ELEMENTARY DIAGRAM	EA-221755
DC ELEMENTARY DIAGRAM	EA-221855

AS-BUILT

REV. NO.	DATE	BY	DESCRIPTION	CHK.	CERT.	APPL.
0	03-2013	ABB	ISSUED FOR CONSTRUCTION	MDS	SS	AK
B	11-2012	ABB	ISSUED FOR DETAIL DESIGN	MDS	SS	AK
A	06/2012	ABB	ISSUED FOR BASE DESIGN	MDS	SS	ARK

الشركة السعودية للكهرباء
Saudi Electricity Company

DRAWN BY: UK CHECKED BY: MDS SCALE: NONE
DATE STARTED: 2012-06-16 DATE COMPLETED: -
DRVL DEPT: PSN ENG. DEPT: AUT

THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION OR FOR ORDERING MATERIAL UNTIL CERTIFIED AND DATED BY: -- DATE: --

GENERAL ARRANGEMENT AND LIST OF APPARATUS -6T1A1
115/13.8KV TRANSFORMER T601 SET-1 PROTECTION PANEL
DATIF 115/13.8KV SUBSTATION # 2
DATIF SAUDI ARABIA

THIS DRAWING AND THE INFORMATION CONTAINED HEREIN ARE THE SOLE PROPERTY OF SAUDI ELECTRICITY CO. NO REPRODUCTION IN FULL OR IN PART SHALL BE OBTAINED FROM THIS DOCUMENT WITHOUT THE WRITTEN CONSENT OF ITS OWNER.

LOCATION REF.	ITEM DESIGNATION	DESCRIPTION	QTY.	TYPE	MAKE	ORDERING INFORMATION
		115/13.8KV TRANSFORMER T601 SET-2 PROTECTION PANEL -6T1B1 CONSISTING OF THE FOLLOWING:	1	VSH 200	ABB	
U14.113 U14.313	74/86T-2 74/86T-4	LDR COIL SUPERVISION RELAY RATED VOLTAGE : 40-265V DC CONTACTS : 2C/O	2	SPERIC1	ABB	RS 485 002-AA
U14.101	98/67/67N	FUSE FAILURE SUPERVISION RELAY FOR HV SIDE OF TRANSFORMER VT RATED VOLTAGE : 110V AC (L-L) FREQUENCY : 50/60HZ CONTACTS : 3NO	1	RXB44	ABB	RK 420 004-AA
U02.5001	67/67N	NUMERICAL DIRECTIONAL O/C PROTECTION FOR LV SIDE RATED CURRENT : 1A AUX. SUPPLY : 90-250V DC RATED FREQUENCY : 50/60HZ	1	P142	AREVA	P142 316DSM0440J
U02.5002 U06.5001	50/51/50N/51N-1 50/51/50N/51N-2	NUMERICAL O/C & E/F PROTECTION RATED CURRENT : 1A AUX. SUPPLY : 90-250V DC RATED FREQUENCY : 50/60HZ	2	P142	AREVA	P142 316DSM0440J
U06.5002	510	NUMERICAL NEUTRAL O/C PROTECTION RATED CURRENT : 1A AUX. SUPPLY : 90-250V DC RATED FREQUENCY : 50/60HZ	1	P142	AREVA	P142 316DSM0440J
U18.5001 U19.5002	86T-2 86T-4	HAND RESET LOCKOUT RELAY FOR TRANSFORMER SET-2 PROT. WITH THE FOLLOWING: RATED VOLTAGE : 125V DC NO. OF DECKS : 10 NO. OF CONTACTS : 20 NO - 20NC OPERATING COIL TYPE : F	2	LDR H/R	ELECTRO SWITCH	7810 F
U14.5001	74/DC-2	DC SUPPLY SUPERVISION RELAY WITH REVERSE FLAG RATED DC SUPPLY VOLTAGE : 110-125V DC NO. OF CONTACTS : 1NO - 3NC OPERATION INDICATOR : SELF RESET	1	MVAX12	AREVA	MVAX12R1CB0757A
U14.5002	74/TC-2//A607	TRIP CIRCUIT-2 SUPERVISION RELAY-A607 AUXILIARY VOLTAGE : 110 /125V DC NO. OF CONTACTS : 1NO - 2NC OPERATION INDICATOR : HAND RESET	1	MVAX31	AREVA	MVAX31S1DE0754A
	R1 R2,R3	1.5K OHMS EXTERNAL RESISTOR FOR TRIP CKT. SUPERVISION RELAY 4.0K OHMS EXTERNAL RESISTOR FOR TRIP CKT. SUPERVISION RELAY	1 2		AREVA	
U26.5001 U26.5001 U26.5002	TS-1 TS-2 TS-3	FLEXI TEST SWITCH WITH 8C+2P FOR 67/67N CT ISOLATION FLEXI TEST SWITCH WITH 10P FOR 67/67N VT ISOLATION FLEXI TEST SWITCH WITH 10P FOR 98/67/67N VT ISOL.	1	FT-19R	ABB	FR20 083 001 001
U29.5001 U29.5002 U29.5003	TS-4 TS-5 TS-6	FLEXI TEST SWITCH WITH 8C+2P FOR 50/51/50N/51N-1 CT ISOLATION FLEXI TEST SWITCH WITH 8C+2P FOR 50/51/50N/51N-2 CT ISOLATION FLEXI TEST SWITCH WITH 8C+2P FOR 51G CT ISOLATION	1	FT-19R	ABB	FR20 083 083 083
U32.5001 U32.5002	TS-7 TS-8	FLEXI TEST SWITCH WITH 2P+2T+6P FOR 86T-2 TRIP ISOL. FLEXI TEST SWITCH WITH 2P+2T+6P FOR 86T-4 TRIP ISOL.	1	FT-19R	ABB	FR20 819 819 000

LOCATION REF.	ITEM DESIGNATION	DESCRIPTION	QTY.	TYPE	MAKE	ORDERING INFORMATION
U39.5001	FJ	6A MCB FOR INCOMING DC AUX. SUPPLY	1	STOZ	ABB	S282-UC-K6
U39.5002	CO1,CO2	POWER SOCKET DUPLEX - 127 & 220V AC	1	US M45& US M545	LEGRAND	74140 & 74180
U39.5003	TJ	TELEPHONE JACK, 4WIRE, 10ANG	1	EDF 410	EDISON ELECTRIC	DEDF 410
	LK1-LK3	NEUTRAL ISOLATION LINK	3	RS20	AREVA	
	C1	2 POLE 20AMP MCB RATED 127V FOR INCOMING AC AUX. SUPPLY	1	S282 P-K20	ABB	S282 P-K20
	C2	2 POLE 20AMP MCB RATED 220V FOR INCOMING AC AUX. SUPPLY	1	S282 P-K20	ABB	S282 P-K20
	SW	SWITCH FOR SPACE HEATER	1	MC8H-10	ABB	1SFA 611 608 R1101
	TH	THERMOSTAT FOR SPACE HEATER	1	M2S51-10B	ABB	1SFA 611 200 R1035
	SH	SPACE HEATER-152W, 127V AC, 60HZ	1	SK3110	RITTAL	SK3110
	DS	DOOR SWITCH FOR CUBICLE ILLUMINATION LAMP WITH 2ND CONTACTS	1	1FZ6K000002	COMPTON	1SBV010213R1202
	FL	FLUORESCENT LAMP, 127V AC	1	SP-20W	ANHORN	T-4 SP-20W
	IX1S - 3X1S	TERMINAL BLOCK FOR CT CKT (6 WAYS IN A GROUP)	3	EB27	GE	EB27005SC
	X2	TERMINAL BLOCK FOR VT CKT	15	DTTAS/P/P	PHONIX	
	X3	TERMINAL BLOCK FOR AUX. DC CKT	5	M10/10_RS	ENTRELEC	1SNA 115-320-R2700
	X3.1	TERMINAL BLOCK FOR AUX. AC CKT	10	M10/10_RS	ENTRELEC	1SNA 115-320-R2700
	X6	TERMINAL BLOCK FOR COMMON ALARM PANEL	15	M6/8_RS	ENTRELEC	115.685.12
	X42	TERMINAL BLOCK FOR TC-2	15	M10/10_RS	ENTRELEC	1SNA 115-320-R2700
	X43	TERMINAL BLOCK FOR BFI	5	M10/10_RS	ENTRELEC	1SNA 115-320-R2700
	X45	TERMINAL BLOCK FOR CLOSE BLOCK	12	M10/10_RS	ENTRELEC	1SNA 115-320-R2700
	X5W	TERMINAL BLOCK FOR SPACE HEATER	2	M10/10_RS	ENTRELEC	1SNA 115-320-R2700
	XTJ	TERMINAL BLOCK FOR TEL. JACK	4	M10/10_RS	ENTRELEC	1SNA 115-320-R2700
	X46	TERMINAL BLOCK FOR SPARE CONTACTS	40	M10/10_RS	ENTRELEC	1SNA 115-320-R2700
	X82	TERMINAL BLOCK FOR DFR	5	M10/10_RS	ENTRELEC	1SNA 115-320-R2700
	CICT-N	CURRENT ISOLATION CURRENT TRANSFORMER	4	CICT	AMETEK	

REFERENCE DRAWINGS	
DRAWING TITLE	DRAWING NO.
DRAWING CONTROL SHEET	EA-221307
RELAYING AND METERING ONE LINE DIAGRAM	EA-221584
AC ELEMENTARY DIAGRAM	EA-221756
DC ELEMENTARY DIAGRAM	EA-221856

AS-BUILT					
NO.	DATE	BY	DESCRIPTION	CHKD.	APPD.
0	03-2013	ABB	ISSUED FOR CONSTRUCTION	MDS	SS AK
B	11-2012	ABB	ISSUED FOR DETAIL DESIGN	MDS	SS AK
A	05/2012	ABB	ISSUED FOR BASE DESIGN	MDS	SS ARK

الشركة السعودية للكهرباء
Saudi Electricity Company

DRAWN BY: LJK CHECKED BY: MDS SCALE: NONE
 DATE STARTED: 2012-05-16 DATE COMPLETED: -
 PRD. DEPT.: PSN ENG. DEPT.: AUT

THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION OR FOR ORDERING MATERIAL UNTIL CERTIFIED AND DATED BY: -- DATE: --

GENERAL ARRANGEMENT AND LIST OF APPARATUS -6T1B1
115/13.8KV TRANSFORMER T601 SET-2 PROTECTION PANEL
DATIF 115/13.8KV SUBSTATION # 2
DATIF SAUDI ARABIA

MANUFACTURER/VENDOR NAME		
ABB Automation Co. Ltd.		
DRAWING NUMBER	SHEET NO.	REV. NO.
S-13610 EA-221656	02 of 02	B

THIS DRAWING AND THE INFORMATION CONTAINED HEREIN ARE THE SOLE PROPERTY OF SAUDI ELECTRICITY CO. NO REPRODUCTION IN FULL OR IN PART SHALL BE OBTAINED FROM THIS DOCUMENT WITHOUT THE WRITTEN CONSENT OF ITS OWNER.

NOTES

LOCATION REF.	ITEM DESIGNATION	DESCRIPTION	QTY.	TYPE	MAKE	ORDERING INFORMATION
		115KV BUS COUPLER-1 PROTECTION PANEL -6BC1 CONSISTING OF THE FOLLOWING :	1	VSH 200	ABB	
U03.5001	51BC	THREE PHASE NUMERICAL OVER CURRENT RELAY WITH INVERSE TIME CHARACTERISTICS & INSTANTANEOUS 8 LOGIC INPUT & 15 RELAY OUTPUT IEC61850 OVER ETHERNET AND COURIER VIA REAR K-BUS/RS485 RATED CURRENT : 1A VN : 100-120V AC FREQUENCY : 60HZ AUX. DC SUPPLY : 110-250V DC	1	P142	AREVA	P142 31606M0440J
U03.5002	51BC-N	THREE PHASE NUMERICAL OVER CURRENT RELAY WITH INVERSE TIME CHARACTERISTICS & INSTANTANEOUS 8 LOGIC INPUT & 15 RELAY OUTPUT IEC61850 OVER ETHERNET AND COURIER VIA REAR K-BUS/RS485 RATED CURRENT : 1A VN : 100-120V AC FREQUENCY : 60HZ AUX. DC SUPPLY : 110-250V DC	1	P142	AREVA	P142 31606M0440J
U17.5001	86BC-1	HAND RESET LOCKOUT TRIP RELAY FOR BUS COUPLER 1A/2A PROT. WITH THE FOLLOWING: RATED VOLTAGE : 125V DC NO. OF DECKS : 10 NO. OF CONTACTS : 20 NO + 20NC OPERATING COIL TYPE : F HAND RESET : D	1	LOR H/R	ELECTRO SWITCH	7810 F
U21.5001	74/DC	DC SUPERVISION RELAY WITH THE FOLLOWING CONTACTS : 1 NO + 3 NC DC VOLTAGE : 110/125 V DC OPERATION INDICATOR : SELF RESET	1	MVAX 12	AREVA	MVAX12 R1CB0757A
U21.5002	74/TC-1//A603	TRIP CIRCUIT-1 SUPERVISION RELAY-A603 AUXILIARY VOLTAGE : 110 /125V DC NO. OF CONTACTS : 1NO + 2NC OPERATION INDICATOR : HAND RESET	1	MVAX31	AREVA	MVAX31S1DE0754A
C	1R1 1R2-1R3	1.5K OHMS EXTERNAL RESISTOR FOR TRIP CKT. SUPERVISION RELAY 4.0K OHMS EXTERNAL RESISTOR FOR TRIP CKT. SUPERVISION RELAY	1 2		AREVA	
U21.5003	74/TC-2//A603	TRIP CIRCUIT-2 SUPERVISION RELAY-A603 AUXILIARY VOLTAGE : 110 /125V DC NO. OF CONTACTS : 1NO + 2NC OPERATION INDICATOR : HAND RESET	1	MVAX31	AREVA	MVAX31S1DE0754A
C	2R1 2R2-2R3	1.5K OHMS EXTERNAL RESISTOR FOR TRIP CKT. SUPERVISION RELAY 4.0K OHMS EXTERNAL RESISTOR FOR TRIP CKT. SUPERVISION RELAY	1 2		AREVA	
U25.101	74/86BC-1	SUPERVISION RELAY FOR TRIP RELAY DC VOLTAGE : 40-265V DC CONTACTS : 2 C/O	1	SPERIC1	ABB	RS 485 002-AA
U33.5001 U33.5002 U33.5003	TS-1 TS-2 TS-3	FLEXI TEST SWITCH WITH 8C-2P FOR 51BC CT ISOLATION FLEXI TEST SWITCH WITH 8C-2P FOR 51BC-N CT ISOLATION FLEXI TEST SWITCH WITH 2P-2T-6P FOR TRIP CKT & TRIP ISOLATION	1	FT-19R	ABB	FR20 083 083 819
U39.5001	F1	6A MCB FOR DC AUX SUPPLY	1	ST0T2	ABB	S282-UC-K6
U39.5002	CD1,CD2	POWER SOCKET DUPLEX TYPE, 127 & 220V AC	1	US M45 & US M45	LEGRAND	74140 & 74160
U39.5003	TJ	TELEPHONE JACK	1	EDP410	EDISON ELECTRIC	EDP 410
	LK1	NEUTRAL ISOLATION LINK	1	RS 20	AREVA	
	C1	2 POLE 20AMP MCB RATED 127V FOR INCOMING AC AUX. SUPPLY	1	S202P-K20	ABB	S202P-K20
	C2	2 POLE 20AMP MCB RATED 220V FOR INCOMING AC AUX. SUPPLY	1	S202P-K20	ABB	S202P-K20
	SW	TOGGLE SWITCH FOR SPACE HEATER	1	MCB-10, M2551-10B	ABB	1SFA 611 605 R110 1SFA 611 200 R1006
	TH	THERMOSTAT FOR SPACE HEATER	1	SL3M0	RITTAL	SK3110
	SH	SPACE HEATER-150W, 120V, 60HZ	1	1FZEK7500104	COMPOTECH	
	DS	DOOR SWITCH FOR CUBICLE ILLUMINATION LAMP WITH 2NC CONTACTS	1	LS30P	ABB	1S8V 010213R1202
	IL	FLUORESCENT LAMP, 127V AC	1	SP-20W	AMORN	T-4 SP-20W
	1X1S	TERMINAL BLOCK FOR CT CKT (6WAYS BLOCK)	1	EB27	OE	0790462
	X3	TERMINAL BLOCK FOR AUX. DC CKT	5	M10/10_RS	ENTRELEC	1SNA 115 320 R2700
	X3.1	TERMINAL BLOCK FOR AUX. AC CKT	10	M10/10_RS	ENTRELEC	1SNA 115 320 R2700
	X41	TERMINAL BLOCK FOR TRIP CIRCUIT-1	5	M10/10_RS	ENTRELEC	1SNA 115 320 R2700
	X42	TERMINAL BLOCK FOR TRIP CIRCUIT-2	5	M10/10_RS	ENTRELEC	1SNA 115 320 R2700
	X43	TERMINAL BLOCK FOR INTIATION CKT	5	M10/10_RS	ENTRELEC	1SNA 115 320 R2700
	X45	TERMINAL BLOCK FOR CLOSING CKT	5	M10/10_RS	ENTRELEC	1SNA 115 320 R2700
	X82	TERMINAL BLOCK FOR CLOSING CKT	5	M10/10_RS	ENTRELEC	1SNA 115 320 R2700
	X46	TERMINAL BLOCK FOR SPARE CONTACTS	35	M10/10_RS	ENTRELEC	1SNA 115 320 R2700
	X6	TERMINAL BLOCK FOR COMMON ALARM	15	M6/8_RS	ENTRELEC	115.685.12
	XSH	TERMINAL BLOCK FOR SPACE HEATER	2	M10/10_RS	ENTRELEC	1SNA 115 320 R2700
	XTJ	TERMINAL BLOCK FOR TEL. JACK	5	M10/10_RS	ENTRELEC	1SNA 115 320 R2700
	C1CT-A C1CT-B C1CT-C C1CT-N	CURRENT ISOLATION CURRENT TRANSFORMER	4	C1CT	AMETEK	

REFERENCE DRAWINGS	
DRAWING TITLE	DRAWING NO.
DRAWING CONTROL SHEET	EE-221307
RELAYING AND METERING ONE LINE DIAGRAM	EA-221504
AC ELEMENTARY DIAGRAM	EA-221751
DC ELEMENTARY DIAGRAM	EA-221851

AS-BUILT					
REV. NO.	DATE	BY	DESCRIPTION	CHKD.	APPR.
0	03-2013	ABB	ISSUED FOR CONSTRUCTION	MDS	SS AK
B	11-2012	ABB	ISSUED FOR DETAIL DESIGN	MDS	SS AK
A	07/2012	ABB	ISSUED FOR BASE DESIGN	MDS	SS AK

الشركة السعودية للكهرباء
Saudi Electricity Company

DRAWN BY: LK CHECKED BY: MDS SCALE: NONE
 DATE STARTED: 2012-07-04 DATE COMPLETED: -
 PROJ. DEPT.: PSN ENG. DEPT.: AUT

THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION OR FOR ORDERING MATERIAL UNTIL CERTIFIED AND DATED BY: -- DATE: --

GENERAL ARRANGEMENT AND LIST OF APPARATUS -6BC1
115KV BUS COUPLER-1 PROTECTION PANEL
DATIF 115/13.8KV SUBSTATION # 2
DATIF SAUDI ARABIA

MANUFACTURER/VENDOR NAME		
ABB Automation Co. Ltd.		
DRAWING NUMBER	SHEET NO.	REV. NO.
S-13610 EA-221651	02 of 02	B

JOB ORDER NO.	INDEX	PLANT NO.	DRAWING NUMBER	SHEET NO.	REV. NO.
1-113045.01	P	DA441	EA-221651	02 of 02	0

THIS DRAWING AND THE INFORMATION CONTAINED HEREIN ARE THE SOLE PROPERTY OF SAUDI ELECTRICITY CO. NO REPRODUCTION IN FULL OR IN PART SHALL BE OBTAINED FROM THIS DOCUMENT WITHOUT THE WRITTEN CONSENT OF ITS OWNER.

LOCATION REF.	ITEM DESIGNATION	DESCRIPTION	QTY.	TYPE	MAKE	ORDERING INFORMATION
		13.8KV CAPACITOR BANK-1 SET-2 PROTECTION PANEL -3RBI CONSISTING OF THE FOLLOWING:	1	VSH.200	ABB	
U03.5001	59-1	OVER VOLTAGE RELAY RATED CURRENT : 1A FREQUENCY : 60HZ AUX. DC SUPPLY : 110-250V DC	1	P142	AREVA	P142 31A06M0-00J
U03.5002	59-2	OVER VOLTAGE RELAY RATED CURRENT : 1A FREQUENCY : 60HZ AUX. DC SUPPLY : 110-250V DC	1	P142	AREVA	P142 31A06M0-00J
U03.5002	27-1/27-2	UNDER VOLTAGE RELAY RATED CURRENT : 1A FREQUENCY : 60HZ AUX. DC SUPPLY : 110-250V DC	1	P142	AREVA	P142 31A06M0-00J
U21.101	90/27	VT FUSE FAILURE RELAY RATED VOLTAGE : 110V AC L-L CONTACTS : 3NO RATED FREQUENCY : 50-60 HZ	1	RXBA4	ABB	RK 428 004-AA
U21.113	74/94	TRIP RELAY COIL SUPERVISION RELAY CONTACTS : 2 C/O RATED VOLTAGE : 40-265 V DC	1	SPERIC1	ABB	RS 485 002-AA
U25.5001	74/DC-2	DC SUPPLY SUPERVISION RELAY AUX. VOLTAGE : 110-125V DC CONTACTS : 1NO + 3NC OPERATION INDICATOR-SELF RESET	1	HVAX12	AREVA	HVAX12R1C90757A
U17.5001	94	SELF RESET TRIP RELAY WITH THE FOLLOWING SPECIFICATION: RATED VOLTAGE : 125V DC NO. OF DECKS : 8 NO. OF CONTACTS : 16 NO + 16 NC OPERATING COIL TYPE : F RESET COIL TYPE : D	1	LOR S/R	ES	7068FD
U33.5001	TS-1	FLEXIBLE TEST SWITCH 10P FOR VT ISOLATION	1	FT-19R	ABB	FR2G 001 019 001
U33.5002	TS-2	FLEXIBLE TEST SWITCH 2P-2T-6P FOR TRIP ISOLATION	1	FT-19R	ABB	FR2G 001 001 001
U33.5003	TS-3	FLEXIBLE TEST SWITCH 10P FOR TRIP ISOLATION	1	FT-19R	ABB	FR2G 001 001 001
U33.5001	TS-4	FLEXIBLE TEST SWITCH 10P FOR VT ISOLATION OF 59-1	1	FT-19R	ABB	FR2G 001 001 001
U33.5002	TS-5	FLEXIBLE TEST SWITCH 10P FOR VT ISOLATION OF 59-2	1	FT-19R	ABB	FR2G 001 001 001
U33.5003	TS-6	FLEXIBLE TEST SWITCH 10P FOR VT ISOLATION OF 27/27-2	1	FT-19R	ABB	FR2G 001 001 001
U39.5001	F1	6A MCB FOR INCOMING DC AUX. SUPPLY	1	S202UC-K6	ABB	S202-VC-K6
U39.5002	CO1/CO2	POWER SOCKET DUPLEX TYPE 127V AC & 220V AC	1	US 145 & US 145-5	LEGRAND	74140 & 74100
U39.5003	C1	2 POLE 20AMP MCB RATED 127V FOR INCOMING AC AUX. SUPPLY	1	S202P-K20	ABB	2CDS 202 001 R0407
	C2	2 POLE 20AMP MCB RATED 220V FOR INCOMING AC AUX. SUPPLY	1	S202P-K20	ABB	2CDS 202 001 R0407
	SH	SWITCH FOR SPACE HEATER	1	MCBH-10, M25S1-10B	ABB	1SFA 611 605 R110 1SFA 611 200 R1006
	TH	THERMOSTAT FOR SPACE HEATER	1	SK 3110	RITTAL	SK3110
	SH	SPACE HEATER-150W, 127V, 60HZ	1	1FZEK006002	COMPOTECH	1FZEK006002
	DS	DOOR SWITCH FOR CUBICLE ILLUMINATION LAMP WITH 2NC CONTACTS	1	LS30P	ABB	1S0V 010213R1202
	IL	FLUORESCENT LAMP, 127V AC	1	EB27	SINAR	EB27/006SC
	TJ1	TELEPHONE JACK	1	EDF410	EDISON ELECTRIC	EDF 410
	X3	TERMINAL BLOCK FOR DC AUX. POWER CIRCUITS	5	M10/10_RS	ENTRELEC	1SNA 115 320 R2700
	X3.1	TERMINAL BLOCK FOR AC AUX. POWER CIRCUITS	10	M10/10_RS	ENTRELEC	1SNA 115 320 R2700
	X41	TERMINAL BLOCK FOR TRIP CKT-1	5	M10/10_RS	ENTRELEC	1SNA 115 320 R2700
	X42	TERMINAL BLOCK FOR TRIP CKT-2	5	M10/10_RS	ENTRELEC	1SNA 115 320 R2700
	X46	TERMINAL BLOCK FOR SPARE CKT	17	M10/10_RS	ENTRELEC	1SNA 115 320 R2700
	X2	TERMINAL BLOCKS FOR VT INPUT	15	OTTA 6T/PP	PHOENIX	790462
	X6	TERMINAL BLOCKS FOR COMMON ALARM	20	M6/6_RS	ENTRELEC	115-685-12
	XTJ	TERMINAL BLOCKS FOR TELEPHONE JACK	9	M10/10_RS	ENTRELEC	1SNA 115 320 R2700
	XSH	TERMINAL BLOCKS FOR SPACE HEATER	2	M10/10_RS	ENTRELEC	1SNA 115 320 R2700

REFERENCE DRAWINGS

DRAWING TITLE	DRAWING NO.
DRAWING CONTROL SHEET	EE-221367
RELAYING AND METERING ONE LINE DIAGRAM	EA-221504
AC ELEMENTARY DIAGRAM	EA-221701
DC ELEMENTARY DIAGRAM	EA-221801

AS-BUILT

REV. NO.	DATE	BY	DESCRIPTION	CHNG.	CERT.	APP'D.
0	23-2013	ABB	ISSUED FOR CONSTRUCTION	MDS	SS	AK
B	11-2012	ABB	ISSUED FOR DETAIL DESIGN	MDS	SS	AK
A	06/2012	ABB	ISSUED FOR BASE DESIGN	MDS	SS	AK

الشركة السعودية للكهرباء
Saudi Electricity Company

DRAWN BY: UK CHECKED BY: MDS SCALE: NONE
DATE STARTED: 2012-08-16 DATE COMPLETED: _____
DRG. DEPT.: PSS ENG. DEPT.: AJT

THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION OR FOR ORDERING MATERIAL UNTIL CERTIFIED AND DATED BY: _____ DATE: _____

GENERAL ARRANGEMENT AND LIST OF APPARATUS -3RBI
13.8KV CAPACITOR BANK-1 SET-2 PROTECTION PANEL
DATIF 115/13.8KV SUBSTATION # 2
DATIF SAUDI ARABIA

MANUFACTURER/VENDOR NAME		
ABB Automation Co. Ltd.		
DRAWING NUMBER	SHEET NO.	REV. NO.
S-13610 EA-221681	02 of 02	B

THIS DRAWING AND THE INFORMATION CONTAINED HEREIN ARE THE SOLE PROPERTY OF SAUDI ELECTRICITY CO. NO REPRODUCTION IN FULL OR IN PART SHALL BE OBTAINED FROM THIS DOCUMENT WITHOUT THE WRITTEN CONSENT OF ITS OWNER.

ANNEXURE-D

(Transformer Data & Fault Level Data)



7.0 DATA SCHEDULE

**POWER TRANSFORMERS,
RATED 2 MVA UP TO 100 MVA
(QATIF- EA-221577)**

SEC Enquiry No. _____ Date: _____

SEC Purchase Order No. _____ Date: _____
or Contract No. _____

SEC PTS No./Project Title with J.O. No. _____ Refer to Main SOW/TS

<u>REFERENCE SECTION NO.</u>	<u>DESCRIPTION</u>	<u>'A'</u>	<u>'B'</u>	<u>'C'</u>
	Power Transformer Model No./Type No.	*	1ZTR121500	
	Type of System Grounding (Solidly grounded, resistance grounded, other)			
	HV	Effectively Grounded	N/A	
	LV	Effectively Grounded	Solidly grounded	
	TV (if applicable)		N/A	
	Common Neutral (Auto Transformer)		N/A	
3.0	Applicable Industry Standards	*	IEC 60076	
4.0	<u>DESIGN AND CONSTRUCTION REQUIREMENTS</u>			55 (max. ambient)
4.1	Design Ambient Temperature (°C)	*	35 (yearly average)	
	Number of Windings	Two	Two	
	Type of Cooling	ON AN /ON AF	ONAN/ONAF	
	Vector Group Designation	Dyn1	Dyn1	

A' - SEC SPECIFIED DATA/PARAMETER.

'B' - BIDDER/SUPPLIER/VENDOR/CONTRACTOR PROPOSED DATA/PARAMETERS.

'C' - REMARKS SUPPORTING THE PROPOSED DEVIATION IN COLUMN 'B'.

(*)-DATA/PARAMETER TO BE PROVIDED/PROPOSED BY THE BIDDER/SUPPLIER/VENDOR/CONTRACTOR IN COLUMN 'B'.

ABB
 ABB Elektrik Sanayi A.Ş.

Date:01/08/2012



7.0 DATA SCHEDULE

POWER TRANSFORMERS,
RATED 2 MVA UP TO 100 MVA

REFERENCE SECTION NO.	DESCRIPTION	'A'	'B'	'C'
4.2.1 Natural Cooling Rating				
	HV/LV/TV (MVA)	50 50	50/50/N/A	//
	1st Stage Forced Cooling			
	HV/LV/TV (MVA)	67 / 67/	67/67/N/A	//
	2nd Stage Forced Cooling			
	HV/LV/TV (MVA)	- / - / -	N/A/N/A/N/A	//
	Rated Voltage Transformation Ratio			
	HV/LV/TV (kV)	115 / 13.8/	115/13.8/N/A	//
Temperature Rise Based on Ambient Temperature Conditions Specified in 01-TMSS-01				
	Winding °C	*	50 rise	
	Oil °C	*	45 rise	
	Winding maximum (hot spot) Temperature (°C)	*	63 rise	
	Design X/R ratio		≤50.4	
	HV	*	N/A	
	LV	*	N/A	
	TV	*	N/A	
Impedance Voltage natural cooling power base and reference temp. of 75°C (%) (Manufacturer shall indicate the value with applicable tolerance)				
	1. At Principal Tap (Guaranteed values)	22%		
	HV - LV	50MVA Base	22% (50 MVA Base)	
	HV-TV (if applicable)	*	N/A	
	LV-TV (if applicable)	*	N/A	
	2. At Extreme Plus Tap		23.6% (at 50 MVA Base)	
	HV - LV	*		
	HV-TV (if applicable)	*	N/A	
	LV-TV (if applicable)	*	N/A	



Date:01/08/2012



7.0 DATA SCHEDULE

POWER TRANSFORMERS,
RATED 2 MVA UP TO 100 MVA

REFERENCE

SECTION NO.

DESCRIPTION

'A'

'B'

'C'

4.2.1 (continued)

3. At Extreme Minus Tap

HV - LV

⌘

22.3% (at 50 MVA Base)

HV-TV (if applicable)

⌘

N/A

LV-TV (if applicable)

⌘

N/A

Zero-sequence impedance on natural cooling power base and reference temp. of 75°C (%) (Manufacturer shall indicate the value with applicable tolerance)

1. At Principal Tap

HV - LV

⌘

Approx. 22.2 (at 50 MVA base)

HV-TV (if applicable)

⌘

N/A

LV-TV (if applicable)

⌘

N/A

2. At Extreme Plus Tap

HV - LV

⌘

Approx. 23.5 (at 50 MVA base)

HV-TV (if applicable)

⌘

N/A

LV-TV (if applicable)

⌘

N/A

3. At Extreme Minus Tap

HV - LV

⌘

Approx. 22.2 (at 50 MVA base)

HV-TV (if applicable)

⌘

N/A

LV-TV (if applicable)

⌘

N/A

Highest Design Operating Voltage for the tappings

continuous operation (%)

105

105

emergency operation (%)

110

110

Maximum Design Flux Density

at rated voltage (Tesla)

⌘

1.6

at 110% rated voltage (Tesla)

⌘

1.76

Saturation Voltage (% UN)

⌘

≥121%

Current density at rated output

Primary winding (Amp/mm²)

⌘

4.5

Secondary winding (Amp/mm²)

⌘

4.5

Tertiary winding (Amp/mm²)

⌘

N/A

No-load current when excited from LV side as % of full load current

ABB
ABB Elektrik Sanayi A.Ş.

Date:01/08/2012



7.0 DATA SCHEDULE


POWER TRANSFORMERS,
RATED 2 MVA UP TO 100 MVA

REFERENCE SECTION NO.	DESCRIPTION	'A'	'B'	'C'
4.2.1 (continued)				
	100% voltage (Guaranteed value)	*	≤0.10 (Tol=30%)	
	105% voltage	*	≤0.15 (Tol=30%)	
	110% voltage	*	≤0.20 (Tol=30%)	
	No-load current harmonics at 100% and 110% rated voltage (%)		at 100% /110%	
	2 nd Harmonics	*	-	
	3 rd Harmonics	*	approx.19.9/24.2	
	4 th Harmonics	*	-	
	5 th Harmonics	*	approx. 13.8/39.9	
	6 th Harmonics	*	-	
	7 th Harmonics	*	approx.8/23.7	
	8 th Harmonics	*	-	
	9 th Harmonics	*	-	
	Basic Impulse Withstand Voltage (BIL)			
	HV winding (kV _{peak})	*	550	
	LV winding (kV _{peak})	*	95	
	HV neutral end (kV _{peak})	*	N/A	
	LV neutral end (kV _{peak})	*	95	
	Common neutral for auto transformer winding (kV _{peak})	*	N/A	
	Tertiary winding (kV _{peak})	*	N/A	
	Tertiary neutral end (kV _{peak}) (if applicable)	*	N/A	
	Switching Impulse Withstand Voltage (BSL) if applicable (kV_{peak})	*	N/A	
	Separate Source Power Frequency Withstand Voltage			
	HV winding (kV _{rms})	*	230	
	LV winding (kV _{rms})	*	38	
	HV neutral end (kV _{rms})	*	N/A	
	LV neutral end (kV _{rms})	*	38	
	Common neutral for auto transformer winding (kV _{rms})	*	N/A	
	Tertiary Winding (kV _{rms})	*	N/A	



Date:01/08/2012

**1ZTR121500
DAMAGE CURVE**



ANNEXURE-E
(Other Relevant Data)

7.0 DATA SCHEDULE

PAD-MOUNTED STATION SERVICE TRANSFORMER UP TO 20 MVA.

SEC Enquiry No. _____ Date: _____

SEC Purchase Order No. _____ Date: _____
or Contract No.

SEC PTS No /Project Title with J.O. No. _____

REFERENCE SECTION NO.	DESCRIPTION	'A'	'B'	'C'
3.0	<u>APPLICABLE CODES AND STANDARDS</u>			
	Applicable Industry Standards	*	IEC-60076	
4.0	<u>DESIGN AND CONSTRUCTION REQUIREMENTS</u>			
4.1	General.			
	Model Designation	*	E05/1G/3C/2U, Rev.0	
	Estimated transformer life to operate under service conditions (year)	*	Approximately 20 Years	
	Type of system grounding (solidly grounded, resistance grounding, other)	SOLIDLY GROUND	Solidly Grounded	
4.2	Performance Characteristics and Ratings:			
	Rated power (kVA)	500 (MIN.)	500 kVA	
	Vector group designation (Dyn11 or Dyn5)	Dyn11	Dyn11	
	Primary voltage (V) (13800, 33000 or 34000)	13800	13800	
	Secondary voltage (V) (400/231, 380/220 or 231/133)	380/220	380/220	




'A'- SEC SPECIFIED DATA/PARAMETER.
'B'- BIDDER/SUPPLIER/VENDOR/CONTRACTOR PROPOSED DATA/PARAMETERS.
'C'- REMARKS SUPPORTING THE PROPOSED DEVIATION IN COLUMN 'B'
(*)- DATA/PARAMETER TO BE PROVIDED/PROPOSED BY THE BIDDER/SUPPLIER/VENDOR/CONTRACTOR IN COLUMN 'B'.

70 DATA SCHEDULE

PAD-MOUNTED STATION SERVICE TRANSFORMER UP TO 2.0 MVA.

REFERENCE SECTION NO.	DESCRIPTION	'A'	'B'	'C'
4.2	Basic impulse withstand voltage (BIL)			
Continued	HV winding (kVpeak)	*	95	
	LV winding (kVpeak)	*	6	
	Power frequency withstand voltage			
	HV winding (kVrms)	*	38	
	LV winding (kVrms)	*	3	
	Guaranteed no-load losses at rated voltage. (kW)	*	0.75	
	Guaranteed load losses at rated voltage & 75 °C (kW)	*	5.2	
	Guaranteed impedance voltage at rated voltage & 75°C (%)	5	5%	
	Guaranteed excitation current at rated voltage excited from secondary side (A)	*	4.72 A (Refer to L.V. Side)	
	Efficiency (%) (100% Load at Unity P.F.)		98.77%	
	Voltage regulation at normal tap and 0.8 p.f (%) (100% Load at 0.8 p.f.)	*	3.91%	
	Guaranteed top oil temperature-rise at highest total load losses (K) above the maximum ambient temperature	50°c	50°c	
	Guaranteed average windings temperature-rise at highest total load losses (K) above the maximum ambient temperature	55°c	55°c	
	Hot spot temperature-rise (K)	*	68°c	
	Short circuit withstand level (KA)/sec	*	@ HV = 0.42 KA/2 seconds @ LV = 15.20 KA/2 seconds	



7.0 DATA SCHEDULE

PAD-MOUNTED STATION SERVICE TRANSFORMER UP TO 2.0 MVA.

REFERENCE SECTION NO.	DESCRIPTION	'A'	'B'	'C'
4.2	Maximum design flux density @ 100% of rated voltage (Tesla)	*	1.62	
Continued	Noise level (dBA)	*	As per NEMA TR-1	
4.3	Construction:			
	Tank:			
	Material	*	Mild Steel	
	Tank (rigid/non-rigid)	*	Non-Rigid	
	Tank (sealed /conservator)	*	Sealed	
	Thickness of tank (mm)	*	3 mm (Minimum)	
	Normal operating pressure of tank (kpa)	*	-	
	Maximum pressure withstand without permanent deformation of tank & radiator for 24 hours (kpa)	*	50	
	Minimum pressure (vacuum) withstand without permanent deformation of rigid body tank for 30 minutes (kpa)	*	-	
	Winding:			
	Material	CU	Copper	
	Core:			
	Material	*	M5, Silicon Steel	
4.4	Off-Load Tap Changer:			
	Applied standard	*	IEC-60214	
	Number of steps	5	5	
	Step voltage (%)	2.5	2.5	
	Voltage tapping range (%)	±5	±5	
	Operating method	MANUAL	Off-circuit, Manual	
	Tap position of maximum primary voltage	*	Postion-1	
4.5	Bushings and Terminations:			
	Opposite side wall mounted	YES	YES	(Refer, as per the attached G.A. dsg.)



س.ت ٦٠٠٧

From: Lepeniotis, Panos [mailto:Panos.Lepeniotis@cooperindustries.com]
Sent: Tuesday, April 09, 2013 4:21 PM
To: Maged Abdel Aziz
Cc: Hamed Mohamed Hamed; Divakaran Kannoth Kandy; Mohammed Al-Owaid; Margalla, Mary
Subject: RE: Input Data request - Capacitor bank - Qatiff S/S #2 - SA-3004

Dear Sir,

All information related to the transient currents is included in the analysis submitted to you on September 4th, approved by NG on Nov. 13th 2013.
Nevertheless, I am glad to provide the below data in red:

1. 13.8kv Capacitor bank inrush current – Ipeak=2.03kA(Table 1)
2. 13.8kv Capacitor bank Outrush current – Ipeak=2.55kA(Table 2)

Thank you.
Best Regards,

Panos Lepeniotis

Sales Engineer - Int'l Sales Office
Tel +30 210 964 6332

From: Maged Abdel Aziz [mailto:maged@abc.sa.com]
Sent: Tuesday, April 09, 2013 3:34 PM
To: Margalla, Mary; Lepeniotis, Panos
Cc: Hamed Mohamed Hamed; Divakaran Kannoth Kandy; Mohammed Al-Owaid
Subject: Input Data request - Capacitor bank - Qatiff S/S #2

Dear Mrs. Mary

Regarding the subject mentioned, Please send us the data mentioned below as requested by our Consultant:

1. 13.8kv Capacitor bank inrush current
2. 13.8kv Capacitor bank Outrush current

Your extended support and help will be much appreciated.

Thank you & Best Regards,

Mr. Maged A. Aziz

Project Manager

Tel.: +966-3 8584218, 8142018, 8592842 – Fxt. 114
Fax: +966-3 8584218, 8142018, 8592842 – Fxt. 110
Mobile: +966-551944736
Email: maged@abc.sa.com
Eng_maged63@yahoo.com

ANNEXURE-F

(Relay Configuration Files in PDF Format)